ENGINEERING NEWS-RECORD

Mining rig speeds rock sorting for dam p. 44

A McGRAW-HILL PUBLICATION

Note how the uppermost rail has been elliptically rolled. The wide range of wrought iron pipe sizes and forming methods available assures design flexibility.

Durable Wrought Iron bridge railings work easily in the shop—go up fast on the job

Wrought iron bridge railings meet the requirements of the entire roadbuilding team. Here's why.

For engineers and state highway people responsible for safety — as well as reduced costs — railings of wrought iron offer both. Wrought iron's structural strength gives it high impact resistance. And since wrought iron is not affected by attack from concrete, no special coatings are needed. Important too, is wrought iron's resistance to corrosive atmospheric conditions — another essential for long service life.

Fabricators benefit because of wrought iron's excellent working and welding qualities. Wrought iron bends and stretches with less fatigue or stress, and welds are sound and reliable. As a result, wrought iron pipe can be fabricated into easily erected units.

Once installed, wrought iron railings offer clear views through clean lines and simplicity of design. Our booklet, "Wrought Iron in Bridge Construction," contains illustrated case-history reports. Write for your copy.

A. M. Byers Company, Pittsburgh, Pa. Established 1864. Division Offices in Boston, New York, Philadelphia, Washington, Atlanta, Chicago, St. Louis, Houston, San Francisco. International Division: New York, N. Y.

Available in Canada and throughout the world

BYERS *Wrought Iron Tubular and Hot Rolled Products*

ALSO ELECTRIC FURNACE QUALITY STEEL PRODUCTS

GOODYEAR INDUSTRIAL PRODUCTS
G.T.M.-Specified
COMPASS-V-STEEL Belts
E
D
A
C
B
A Uni-plane section of endless high tensile steel cable delivers up to twice the horsepower of other belts at 10-10,000 f.p.m. with no stretch
B Vents open between pulleys, dissipating heat
C Vents compress rounding pulleys, giving continuous gripping surface
D Highest-quality rubber underbody
E Sturdy bias-laid fabric cover resists wear

G.T.M. slashes vibrating screen belt costs by 45%

THIS DRIVE is atop a hot asphalt mixer. Extreme vibration plus heavy dust, oil, tar, moisture and exposure to weather kept maintenance up and belt life down to a *five to eight weeks' average.*

Then the G.T.M.–Goodyear Technical Man–suggested a matched set of COMPASS-V-Steel Belts, sinewed with airplane-type cables (see blueprint). These super-belts served a *minimum of six months*–have cut belt costs alone virtually in half.

Similar savings on V-belts or other industrial rubber products may be yours by consulting your Goodyear Distributor and/or the G.T.M. Why not try them, today? Or write Goodyear, Industrial Products Division, Akron 16, Ohio.

COMPASS-V-STEEL BELTS by

Compass–T.M. The Goodyear Tire & Rubber Company, Akron, Ohio

GOODYEAR

THE GREATEST NAME IN RUBBER

IT'S SMART TO DO BUSINESS *with your Goodyear Distributor. He can give you fast, dependable service on Hose, V-Belts, Flat Belts and many other industrial rubber and nonrubber supplies. Look for him in the Yellow Pages under "Rubber Goods" or "Rubber Products."*

Symons FIELD REPORT...



Contractor Saves 40% with Symons Forms . . .

7,500 square feet of Symons Standard Forms were used in the new 2 million gallon capacity pumping station at Melrose Park, Illinois. 2,000 cubic yards of concrete were used on the job and the concrete contractor, Louis Macro Company, Melrose Park, reported a 40 per cent saving through the use of Symons Forms. Walls for the job were completed in three pours.

Symons engineering service can help you realize substantial savings in forming. With your plans, our engineers will prepare a complete form layout, bill of materials, and make recommendations for the most efficient and cost saving method of forming.

Our field service representatives are sales engineers, ready and able to advise you on form erection, pouring and stripping methods that will help you save time, labor and materials. You can call on them to assist you on any forming problems.

Symons Forms can be rented with purchase option. Symons Clamp & Mfg. Co., 4265 Diversey Avenue, Dept. L-6, Chicago 39, Illinois.

Sam Carniglia Company, Melrose Park, Illinois
General Contractor.

Catalogs and Added Information on
FORMS—CLAMPS—SHORES
Sent on Request

EIGHTY-SECOND YEAR OF PUBLICATION

ENGINEERING NEWS-RECORD

MEMBER

Editorial Offices, 330 W. 42nd St., New York 36, N. Y.
New York - LOngacre 4-3000; Chicago - MOhawk 4-5800; San Francisco - DOuglas 2-4600;
Washington - REpublic 7-6630

Waldo G. Bowman, Editor

Highways, Airports—Transportation

Eugene E. Halmos, Jr., *Senior Editor*
John R. Owen, Edward M. Young, Jr.

Buildings, Bridges—Structures

Frederick S. Merritt, *Senior Editor*
James B. Sullivan

Rivers, Sanitation—Water Use

Arthur J. Fox, Jr., *Senior Editor*
Howard Jacoby

Finance, Labor—Management

Clyde C. Henning, *Associate Editor*
Charles J. Harding, John Flanagan

Regional Editors

J. Roland Carr, *Chicago, 520 N. Michigan Ave.*
Lauress L. Wise, *San Francisco, 68 Post St.*

Copy, Presentation—Production

Stanley C. Jensen
Marc Leggiero
Barbara Lamb
Harry W. Jensen, *Presentation*
Ruth Solomon, *Makeup*
John C. Greenough, *Printing*

Statistics, Prices, Costs—Business News

Elsie Eaves, *Manager*
Julia Mahoney, *Construction Reports*
Mildred Wetzel, Loretta Felix,
Marion Sciorra, Florence Dembek
James Webber, *Economics*
Ruth I. Carlson, Marie Roessler, Evelyn Huber

Editorial Research and Indexing

Helen Rich
Eva Glerat, Rene Hay
Patricia Witschger, Marianne Stern

Consulting Editors

Van Tuyl Boughton, *New York*
Nathan A. Bowers, *San Francisco*

Washington News Bureau, Room 1189 National Press Building; G. B. Bryant, Jr., *Manager*, Glen Bayless, A. E. Adams, Roy Calvin, Ernest Conine, John C. L. Donaldson, Jay Flocken, Boyd France, V. Craig Richter, Sam Justice, Arthur J. Kraft, D. O. Loomis, Gladys Montgomery, A. L. Moore, Seth Payne, M. A. Reichek, Caroline Robertson, V. B. Smith.

Domestic News Bureaus: Atlanta, 801 Rhodes-Haverty Bldg., Pat Henry; **Cleveland,** 1510 Hanna Bldg., R. E. Cochran; **Detroit,** 856 Penobscot Bldg., Harry Homewood; **Houston,** 1303 Prudential Bldg., J. A. Lee; **San Francisco,** 68 Post Street, M. C. Ralston; **Los Angeles,** 1125 W. Sixth St., John Shinn; **Seattle,** 6040 Fifth Ave., N.E., Ray Bloomberg.

Correspondents: Albany, Albuquerque, Augusta, Me., Austin, Boston, Boulder, Baltimore, Birmingham, Bismarck, Charleston (W. Va.) Charleston (S. C.), Columbus, Cincinnati, Cleveland, Chicago, Cheyenne, Dallas, Denver, Des Moines, Detroit, Durham, Harrisburg, Helena, Houston, Hartford, Indianapolis, Jackson, Miss., Jacksonville, Jefferson City, Kansas City (Mo.), Lansing, Lincoln, Little Rock, Miami, Memphis, Minneapolis, Montgomery, Milwaukee, New Orleans, Norfolk, Omaha, Oklahoma City, Philadelphia, Pittsburg, Portland (Ore.), Providence, Phoenix, Pierre, St. Louis, Schenectady, Springfield (Ill.), Syracuse, St. Paul, Seattle, Salt Lake City, Spokane, Topeka, Trenton, Wilmington. **Canada:** Montreal, Toronto, Ottawa, Victoria, Regina.

McGraw-Hill Economics Department: Dexter M. Keezer, director; W. H. Chartener

Foreign News Bureaus: Editor, John Wilhelm, **New York;** G. W. Schroeder, **Bonn;** Sharokh Sabavala, **Bombay;** William J. Coughlin, **London;** John H. Kearney, **Mexico City;** John O. Coppock, **Paris;** Dan Kurzman, **Tokyo;** Peter Weaver, **Rio de Janeiro. Correspondents:** Amsterdam, Athens, Bangkok, Bogota, Brussels, Buenos Aires, Caracas, Copenhagen, Geneva, Havana, Helsinki, Johannesburg, Lima, Madrid, Melbourne, Oslo, Rome, Stockholm, Sydney, Tehran and 21 other principal cities and countries.

Robert F. Boger, Publisher

ENGINEERING NEWS-RECORD Vol. 157, No. 20, November 15, 1956

Published weekly by McGraw-Hill Publishing Company, James H. McGraw (1860-1948), Founder. **Executive, Editorial, Advertising and Subscription Offices, McGraw-Hill Building, 330 W. 42nd St., New York 36, N. Y.** Publication Office, 99-129 North Broadway, Albany 1, N. Y. Donald C. McGraw, President; Paul Montgomery, Executive Vice-President; Joseph A. Gerardi, Executive Vice-President and Treasurer; Hugh J. Kelly, Executive Vice-President; John J. Cooke, Secretary; Nelson Bond, Executive Vice-President, Publications Division; Ralph B. Smith, Vice-President and Editorial Director; Joseph H. Allen, Vice-President and Director of Advertising; J. E. Blackburn, Jr., Vice-President and Circulation Director. **SUBSCRIPTIONS:** Address correspondence to Engineering News-Record—Subscription Service, 99-129 North Broadway, Albany 1, N. Y., or 330 W. 42nd St., New York 36, N. Y. Allow one month for change of address. Subscriptions are solicited only from persons with an identifiable commercial or professional interest in construction and building. **Position and company connection must be indicated on subscription orders.** Single copies 35¢. Subscription rates: United States and possessions, $6.00 a year; $9.00 for two years; $12.00 for three years. **Canada** $8.00 a year; $12.00 for two years; $16.00 for three years. Other Western Hemisphere and the Philippines, $15.00 a year; $25.00 for two years; $30.00 for three years. All other countries $20.00 a year; $30.00 for two years; $40.00 for three years. Second class mail privileges authorized at Albany, New York. Printed in U. S. A. Copyright 1956 by McGraw-Hill Publishing Co., Inc.—All Rights Reserved.

THE NORTHWEST 25-TON TRUCK CRANE

● All over the country — California, New York, New England, Pacific Northwest, Deep South—the Northwest 25-ton Truck Crane is proving its versatility and its great ability to handle jobs of all kinds. Here is a rubber-tired unit that brings you a combination of advantages found on no other similar piece of equipment. Northwests on rubber bring greater flexibility and higher output when the days results are totalled up.

NORTHWEST ENGINEERING CO.
1502 Field Bldg., 135 South LaSalle Street, Chicago 3, Illinois

NORTHWEST

CRAWLER and TRUCK MOUNTED SHOVELS • CRANES • DRAGLINES • PULLSHOVELS

PRODUCTION PLUS · $ · MEANS MONEY



GOOD workmanship is one of the most important factors in preventing leaky brick walls.

Good workmanship includes filling the bed joints and head joints—wetting the brick—and backplastering the face brick.

Expect trouble when mortar is dabbed only on the corners of the brick, even when the head joint is slushed.

Because it is so workable, Brixment makes it easy for the bricklayer to use enough mortar to completely fill the joints, and still lay the brick easily and accurately to the line.

Brixment mortar has greater plasticity, higher water-retaining capacity and bonding quality, greater resistance to freezing and thawing, and freedom from efflorescence. Because of this *combination* of advantages, Brixment is the leading masonry cement on the market.

BRIXMENT

LOUISVILLE CEMENT COMPANY Incorporated, LOUISVILLE, KENTUCKY

Amvit CLAY LINER PLATES *resist abrasion*

provide smoother flow, added protection



Standard size 9" x 24"
Other sizes upon request

● For *complete* protection of concrete pipe sewers, industrial sewers, culverts, acid vats, sewage treatment tanks, neutralizing baths and laboratory and industrial walls and floors choose and use *Amvit* clay liner plates.

They are specially manufactured to meet all application requirements which entail resistance to acids, alkalies and chemical reaction.

Amvit clay liner plates, hardened, glazed, smooth, acid-proof and durable, permanently bond and lock to masonry and concrete work. They install easily to concrete forms and are sized according to standardized specifications for uniform spacing.

For more information, write or call for our detailed booklet on Amvit liner plates. American Vitrified Products Company, National City Bank Building, Cleveland, Ohio, or our office nearest you.

102" reinforced concrete pipe lined with Amvit curved clay liner plates being installed in a combination storm and sanitary sewer.

SINCE 1900

AMERICAN

American Vitrified Products Company

CLEVELAND, OHIO

MANUFACTURERS of: Clay pipe, flue liners, clay liner plates and concrete pipe.

Plants Across the Nation... Brazil, Indiana • Chicago, Illinois • Cleveland, Ohio • Crawfordsville, Indiana • Detroit, Michigan • East Liverpool, Ohio Fenton, Michigan • Grand Ledge, Michigan • Lisbon, Ohio • Los Angeles, California • Milwaukee, Wisconsin • South Bend, Indiana • Uhrichsville, Ohio

Chicago tests prove USS Steel



To provide authentic data showing USS steel H-beam piles capable of meeting limits allowed by the City of Chicago Building Code, United States Steel Corporation had the Armour Research Foundation of Illinois Institute of Technology conduct tests on a site having soil conditions typical of the Loop area. Tests were made at the corner of Harrison and Halstead Streets. A total of 17 piles were driven, eight of which were used as anchor piles. Data on the nine test piles is shown in the table below.

See for yourself

USS Steel H-Beam Bearing Pile Test

Pile Number	
Pile Size	
End Conditions	
Proposed Allowable Load—Tons	
Test Load—Tons	
No. of Blows in Last Inch	
Estimated Design Load by ENR Formula‡	
Total Deflection at Proposed Allowable Load	
Total Deflection at Test Load	
Rebound from Test Load	
Total Net Settlement	
Allowable Total Net Settlement by Chicago Code	
Load at Failure—Tons	
Avg. Unit Stress (fs) at Failure—psi	
Total Deflection at Failure	
Rebound from Failure Load	
Net Settlement after Removal of Failure Load	
Manner of Failure	

**Final driving of all piles by Vulcan type OR hammer—30,225 ft. lbs. ‡ENGINEERING NEWS formula.*



0.0' Ground line—Approx +14.0' Chicago city datum
-10.0' Fill and Sand
Tough clay with sand and gravel seams
-17.5'
Blue clays
-56.0'
-58.5' Hard blue clay
-60.0' Very dense silt & clay
-63.5' Med. dense silt & clay
-68.5' Hard blue clay & silt
-74.0' Grey silt, clay & sand—med. dense
-79.0' Hard blue clay, silt & gravel
-80.5' Sand & gravel
Grey silt—trace of clay, sand & gravel. Very dense Hardpan
-104.3'
Rock—Dolomitic limestone

THEIR NATURAL ADVANTAGES *make* USS STEEL H-BEAM BEARING PILES *the logical foundation for heavy, multi-story buildings*

The design possibilities, low cost, and ease of installation of USS steel H-Beam bearing piles offer definite advantages over foundation caissons for supporting heavy buildings. Buildings of any height can be founded on steel H-Beam piles without limitations resulting from insufficient penetration. Excessive amounts of free water, marsh gas, and other adverse conditions which sometimes halt construction of open-pit caissons, offer no obstacles to obtaining required design loads with steel H-beam bearing piles. Furthermore, the cost in time, materials, and equipment needed to construct open-pit caissons makes USS steel H-Beam Bearing Piles the most economical type of foundation you can use.

SEE THE UNITED STATES STEEL HOUR. It's a full-hour TV program presented every other week by United States Steel. Consult your local newspaper for time and station.

high load-carrying capacity of H-Beam Bearing Piles

All of the nine piles tested exceeded the requirements of the Chicago Building Code, except for the closed end, 14-inch H-beam bearing pile that failed by excessive net settlement at a load of 370 tons. This pile was not driven to hardpan inasmuch as the desired driving resistance was attained before hardpan was reached. Therefore, it seems logical to assume that for loads of the magnitude of those under discussion, firm seating in hard soil should be a requirement.

Here again is proof that USS Steel H-Beam Bearing Piles are capable of carrying heavy foundation loads into stable mediums lying at great depth. Their capacity for high unit loads, both vertical and horizontal, permits fewer piles and fewer driving operations for a given load. They are readily handled in the field by ordinary equipment, are easy to splice, eliminate jetting, and withstand rough handling.

If you would like to receive detailed information regarding your particular foundation problems, please contact the office nearest you.

Data* (In accordance with Chicago Code requirements—in addition B4, B2 and B3 were tested to failure.)

04	C4	B4	02	C2	B2	03	C3	B3
10" CBP 42#/'	10" CBP 42#/'	10" CBP 42#/'	12" CBP 53#/'	12" CBP 53#/'	12" CBP 53#/'	14" CBP 117#/'	14" CBP 117#/'	14" CBP 117#/'
Open	Closed	Open	Open	Closed	Open	Open	Closed	Open
75	75	75	100	100	100	200	200	200
150	150	150	200	200	200	400	400	400
10	10	31	7	7	Refusal	22	24	On Rock
151	151	228	124	124	.....	208	213	.....
0.317"	0.312"	0.168"	0.359"	0.338"	0.270"	0.378"	0.454"	0.293"
0.773"	0.976"	0.501"	2.147"	1.321"	0.637"	0.891"	See Below	0.695"
0.633"	0.730"	0.549"	0.754"	0.810"	0.670"	0.723"		0.657"
0.140"	0.246"	—0.048"	1.393"	0.511"	—0.033"	0.168"		0.038"
1.50"	1.50"	1.50"	2.00"	2.00"	2.00"	4.00"	4.00"	4.00"
		240			300			635
		34400 psi			38500 psi			36900 psi
		0.985"			1.079"			2.669"
		0.831"			0.932"			1.176"
		0.154"			0.147"			1.493"
		Local Flange Buckling Above Ground			Local Flange Buckling Above Ground			Yielding Over Cross Section of Pile



UNITED STATES STEEL CORPORATION, PITTSBURGH, PA. • COLUMBIA-GENEVA STEEL DIVISION, SAN FRANCISCO
TENNESSEE COAL & IRON DIVISION, FAIRFIELD, ALA. • UNITED STATES STEEL EXPORT COMPANY, NEW YORK

USS

UNITED STATES STEEL

GET THE JOB DONE

Faster . . . at Lower Cost

Air lines, water lines, dredging lines or vent lines — wherever there's a job for pipe, you'll be time and money ahead with dependable Naylor Spiralweld.

Because it is light in weight, this distinctive pipe is easier to handle and install. You don't have to "baby" it because Naylor pipe is stronger and safer due to the exclusive lock-seamed, spiralwelded structure.

Installation is further simplified and costs reduced when you use the one-piece Naylor Wedge-Lock coupling to connect Naylor lines.

Get the facts today on this proved, practical way to speed up pipe line operations in construction service. Ask for Bulletin No. 507.

NAYLOR PIPE

NAYLOR PIPE COMPANY
1248 East 92nd Street
Chicago 19, Illinois

Eastern U. S. and Foreign Sales Office: 350 Madison Avenue, New York 17, New York

Reader Comment

Previous Truss-Tied Arches

SIR—Like the self-anchored suspension bridge, the truss-tied arch was originated by the Austrian engineer, Josef Langer, in 1859. Photographs and data on truss-tied arch bridges built at the following locations were published:

Mur River, Graz, 1881; Ihme River, Hannover, 1889; Kurfurstendam Street, Berlin-Hallensee, 1892; Elbe-Trave Canal, 1898; Segroth Street, Essen, 3 spans, 1910; Kleinfeld Street, Mannheim, 2-span continuous pedestrian, 1920; Spree River, Wiedendammer, Berlin, 1924; Danube River, Győr, first with side spans, 1925; Traun River, Ebelsberg, 1928; Oder River, Glogau, two single-track railroad spans, 1928; Elbe River, Tetschen-Bodenbach, with side spans, 1930; Drava River, Maribor, with side spans, 1933; Oder River, Schwetig, double-track railroad, 1938; Zala River, Zalahidvég, 1948.

Double-deck truss-tied bridges larger than the Fort Pitt span (ENR Oct. 25, p. 23) were proposed in the U. S. (ENR June 10, 1937, p. 859) and also in Europe. It is possible that the Fort Pitt structure will be the first large bridge of this type with two decks.

LOUIS BALOG
Consulting Engineer
Binghamton, N. Y.

De-Salting Costs

SIR—In reading your issue of Sept. 6 I came across two statements in regard to the reclamation of sea water which I believe are somewhat erroneous and should be corrected. They are in an article, "Fresh-From-Salt", on p. 72. This statement is that small systems of the multistage flash evaporation type could turn out drinking water for $3 per million gal. This is a cost of approximately $1 per acre-ft and in our estimation is extremely low. According to an article by Mr. Gilliland in Industrial and Engineering Chemistry of December 1955, most distillation costs vary from 30 cents to $2 per thousand gal, which would bring the cost up to from $100 to over $600 per acre-ft.

Our Owens Valley Aqueduct supply

Engineering News-Record welcomes expression of opinions from its readers. Comment should be as brief as possible and pertinent to subjects of current construction importance. Letters should be addressed: Editor, Engineering News-Record, 330 W. 42nd St., New York 36, N. Y.



Rainproof, "see-through" Olin Polyethylene film helps prevent bad weather slow-downs. Low in cost . . . easy to handle, it makes an ideal "closing-in" material. Helps keep the job on schedule.

Builders build better at less cost with Olin Polyethylene



Curing with Olin Polyethylene saves time, saves money. Extra wettings are eliminated—moisture is "locked" in.



Olin Polyethylene protects materials and machines during wet, rainy periods. Its "see-through" quality makes supplies and equipment easy to locate.

Ideal for slab, full cellar, or crawl space construction, light, tough Olin Polyethylene makes a **permanent** moisture barrier. Comes in extra wide roll widths for additional time-saving.

Builders everywhere are turning to Olin Polyethylene film as the ideal moisture barrier with many varied uses. In bad weather especially, using Olin Polyethylene as a "closing-in" and protective covering material can save wasted days, keep the work on schedule. Light, easy to handle, and re-usable Olin Polyethylene saves on labor and material costs whether it's used for protection or in curing and slab construction work – gives you the kind of job you like to see, easier and faster.

And remember this, because it's unaffected by most acids, alkalies, bacteria, mold and temperature changes, Olin Polyethylene makes a permanent moisture, moisture vapor and draft barrier. Discover for yourself how much of a difference this multi-use film can make on your jobs. You'll find it will cost you less to build better with Olin Polyethylene. For more information and free booklet showing how Olin Polyethylene will save you time and money write: Olin Film Division, 655 Madison Avenue, New York 21, New York.

Meets FHA Minimum Property Requirements . . . Fed. Spec. UUP-147 pertaining to moisture vapor control.

Look us up in Sweet's Catalog! (1957 Edition)
- Industrial Construction File 5/OL
- Architectural File 9/OL
- Light Construction File 3a/OL

Also under . . . AIA File No. 24-D (NN)

Olin POLYETHYLENE®

OLIN MATHIESON CHEMICAL CORPORATION

Olin Film Division
655 Madison Avenue
New York 21, New York

Please send me full information on Olin Polyethylene.

Name _____ Title _____

Company _____

Address _____

ENR-11-56

The Euclid TC-12 gives you more work-ability than other Crawlers

The first really new tractor concept in years... with ALL the performance features you've wanted

Euclid's Model TC-12 Twin-Power Crawler establishes an entirely new standard of tractor performance. It's built to deliver unequalled drawbar horsepower, easy operation and a smooth, steady flow of power to meet any job requirement. It provides easy accessibility of all major components and all lubrication, check and adjustment points are located for maximum convenience. Unitized assemblies permit service or removal without a major tear-down of other parts.

Powered by two 194 h.p. engines at rated speed, 365 h.p. is delivered to the power train. Each of the tracks is driven independently through separate Torqmatic Drives giving the TC-12 faster, easier steering and greater drawbar pull at higher speed. There's no clutch—shifting from one of the three speed ranges to another is done under full power —top speed in forward or reverse is 8.3 mph.

Have your Euclid dealer give you all the facts on the TC-12—compare with your present big tractor equipment and you'll know why so many owners have proved that ***Euclids are your best investment.***

EUCLID DIVISION, GENERAL MOTORS CORPORATION, Cleveland 17, Ohio

Euclid Equipment

FOR MOVING EARTH, ROCK, COAL AND ORE

GM MORE POWER FOR YOU

for the city of Los Angeles costs about $16 to $18 per acre-ft. Raw Colorado River water supplied by the Metropolitan Water District costs about $10 per acre-ft, not counting tax assessment. Treated Colorado River water costs about $20 per acre-ft. Pumping water from local wells in the city of Los Angeles runs from $6 to $10 per acre-ft.

According to an article written last December in Industrial and Engineering Chemistry, costs of converting sea water to fresh water ran from over $100 per acre-ft to $300 or $400, depending on the process involved. Therefore we believe the statement that sea water could be turned into drinking water for $3 per million gal is not in accordance with water production costs at the present time, and that a correction should be noted so that readers will not get a wrong impression.

RAY L. DERBY
Principal Sanitary Engineer
Department of Water and Power
Los Angeles, Calif.

[EDITOR'S NOTE: Such a correction appeared in ENR Sept. 20, p. 12, but Mr. Derby's welcomed letter adds further information on the subject.]

Corpus Christi Builds too

SIR—We read with interest your article in the Oct. 18 issue of the Engineering News-Record on U. S. and Canadian Ports. However, we note that the article failed to mention Corpus Christi. I believe you will find that the Port of Corpus Christi has one of the largest construction programs underway of any port on the Gulf.

In addition to two bridges and a port freeway program, we will complete in November of this year the dredging of the Tule Lake Channel at an estimated cost of $1.4-million. This channel when completed will open up an additional nine miles of water frontage to development.

Bids will be opened on Oct. 31, 1956, to widen and deepen the La Quinta Channel at an estimated cost of $1.7-million. This project is to be completed about Apr. 1, 1957, to accommodate large bauxite ore carriers.

Plans are being prepared and it is contemplated that a continuing contract will be awarded in December of this year to begin widening and deepening the Port Aransas-Corpus Christi Waterway from the Gulf to Tule Lake. Under this program, the channel and basin will be dredged to a depth of 36 ft and a width of 400 ft with the work scheduled to be completed about the time the present bascule bridge is removed from the harbor entrance.

(Reader Comment continued on p. 14)

Only **LIPE** Factory-Exchange Clutches* are built the same as **NEW** Lipe Clutches

In Field-Rebuilt Clutch Sleeves All That Shines is Not New



SHINY CONTACT FACE on reground clutch sleeve indicates unprotected soft iron surface.



NEW LIPE CLUTCH sleeve easily identified by dark color resulted from rugged .007" case hardening and protective surface coating.

Ordinary clutch rebuilders just don't have the resources or the expensive equipment needed to recondition clutches the Lipe quality way. Some rebuilders even use unskilled labor, too few new parts and inadequate inspection methods: Practices that naturally lower the quality of the rebuilt clutch and shorten its service life.

At left is a typical example of inadequate reconditioning. Instead of replacing, as Lipe does, a worn or scored clutch sleeve with a new one, the rebuilder re-grinds the surface down through the case hardening to the soft metal beneath. That means the sleeve will wear quickly, and cause serious damage to the throwout bearing and a high rate of destructive slippage – *all greatly reducing the life of the clutch.* Such an improperly rebuilt clutch tested recently showed a total direct pressure loss of 120 lbs.!

Slipshod reconditioning always costs more in the long run. It pays to get genuine Lipe Factory-Exchange Tagged and Sealed Clutches. Contact your nearby authorized Lipe jobber for quick exchange service.

***Every Lipe Factory-Exchange Clutch is tagged and sealed at the factory—your guarantee of genuine Lipe parts and craftsmanship.**

Lipe-ROLLWAY CORPORATION SYRACUSE 1, N.Y.

Manufacturers of Automotive Clutches and Machine Tools

EXCLUSIVE...NEW...

International® Drott® TD-18

3-yd 4-in-1

Here's the big one of the famous International Drott Four-in-One Skid-Shovel family: the new 3-yard TD-18 Four-in-One! Its bucket of ½-inch new T-1 alloy steel equals ½-inch high tensile manganese steel in strength—saves a ton of weight—boosts your production! And like all Four-In-Ones, this one completely eliminates the need for switching attachments!



It's a 3-yd. Skid-Shovel...

with Drott's exclusive "concrete-shattering," triple-power pry-over-shoe break-out action—and 42" ground level bucket roll-back. Skid-Shovel position also gives you time-gaining, strain-saving load transport on the exclusive Skid-Shoes!

It's a 3-yd. Clamshell...

that "surrounds" loose materials and fills in one fast gulp. And the bottom-dumping clamshell gives you a 2½-foot dumping height advantage over ordinary roll-forward buckets—plus positive, clean-out action even when handling sticky materials!

"FLEET-BEATING PERFORMER"

"A new 3-yd. TD-18 4-In-1 Skid-Shovel proved able to do as much work as 3 power shovels and a dragline digging up and loading old concrete pavement on one of my recent highway jobs," reports Henry E. Berghuis, Prinsburg, Minn. "The 4-In-1 loaded up to 1,700 lineal feet of old pavement daily. Using 4-In-1 Clamshell bottom dumping, I also loaded out 4,500 yards of wet, sticky gumbo no other loader could tackle."

NOW.. big-scale four-machine utility!

It's a 3-yd. Bullclam...

that gives you regular "carry-type scraper" action to grade, strip or spread with inch-close accuracy, using clam lip control. *Plus* exclusive Drott Bullclam efficiency on all Sanitary Landfill operations including *positive fill compaction!*

It's a BIG-capacity Bulldozer



with clam lip up, and shoes on the ground, the blade rolls the earth with precision. You regulate dozing depth with ease and accuracy by hydraulic "radius control" of blade pitch (forward and backward).

Touch the new 3-yard TD-18 Four-In-One's machine-selector lever! See how you instantly get any material-moving action you need—from the seat, with finger-tip ease—and stopped or on-the-go. Prove you can beat a fleet of limited-duty rigs with this *versatility unlimited*—get big-income, tough jobs other rigs can't handle! Compare the capacity-adding advantages of Drott exclusives like shock-swallowing Hydro-Spring and heap-keeping, parallelogram raise action. See your nearby International Drott distributor for a TD-18 Four-In-One demonstration. Or try the 1-yd. TD-6, 1½-yd. TD-9, or 2¼-yd. TD-14 Four-In-One!

International Harvester Company, Chicago 1, Illinois
Drott Manufacturing Corp., Milwaukee 15, Wisconsin

INTERNATIONAL HARVESTER

INTERNATIONAL®
DROTT®

See you at the ROAD SHOW—CHICAGO Jan. 28-Feb. 2, 1957

Water Leakage Problems IN CONCRETE STRUCTURES ?

—Specify and use Servicised

RUBBER WATERSTOP

HOLLOW BULB—FOR EXPANSION JOINTS

Insures permanent, watertight seals in joints where considerable movement due to expansion and contraction is expected. Flexible and elastic with a very high degree of tensile strength to withstand both lateral and shearing movement. Widths—6" and 9" . . . lengths to order.



FLAT DUMBBELL—FOR CONTRACTION OR EXPANSION JOINTS

Made of durable, elastic cured rubber which has high tensile strength and flexibility for effective sealing of contraction and expansion joints against hydrostatic pressure. Carefully manufactured to insure dense, homogeneous cross section for greatest service life. Widths—6" and 9" . . . lengths to order.



SPLIT TYPE WATERSTOP

faster, easier installation

A new Servicised development already in wide use because it reduces installation time and cost by eliminating splitting of form. One half of width is split to permit fastening to inside of bulkhead in the form of a "T." After section is poured, form is removed and divided sections are joined together by stapling. Pat. Pend.

WATERSTOP UNION

simplifies Field Splicing

Permits a faster, simpler method of field splicing, using only rubber cement. The union is hollow and is made from rubber meeting the same specifications as the waterstop. Available for splicing 6" and 9" Dumbbell and 6" and 9" Hollow Bulb Waterstops. Pat. Pend.

Write for Special Waterstop Catalog.

SERVICISED PRODUCTS
CORPORATION
6051 WEST 65th STREET • CHICAGO 38, ILLINOIS

Reader Comment

A contract will also be let by the Navigation District to dredge the Chemical Turning Basin on the Tule Lake Channel before the end of the year. This project is estimated to cost $500,000. The public has voted port improvement bonds to construct the largest and most modern bulk unloading facility in the West Gulf. Studies and plans are under way, and it is expected that a contract for the construction of the dock and equipment will be awarded sometime near the middle of next year. This is estimated to cost $2-million.

It will be necessary to reconstruct all oil docks, both public and private, in the harbor and increase the loading facilities to accommodate super tankers which will load at Corpus Christi once the bascule bridge bottleneck is removed. This project will cost several million dollars.

Studies are under way to double the capacity of the public grain elevator and to extend deep water westward to the vicinity of Viola, Tex., and the new refinery of Suntide Refining Company.

This expansion program may not be as large as some of the programs at other ports, however, for the size of the community, we feel that these expenditures are of such magnitude as to justify mention. In 1955, this waterway, which ranked high among those of the nation, handled over 27-million tons of waterborne commerce.

DUANE ORR,
District Engineer
Nueces County
Navigation District

CALENDAR

American Municipal Association, Annual American Municipal Congress, Chase and Park Plaza Hotels, St. Louis, Nov. 25-28.

Wire Reinforcement Institute, Inc., The Jung Hotel, New Orleans, La., Nov. 26-27.

American Association of State Highway Officials, annual meeting, Hotel Traymore, Atlantic City, N. J., Nov. 27-30.

Fourth Illinois Structural Engineering Conference, discussions on steel and concrete specifications, one-story building foundations and high-strength structural steel, University of Illinois, Urbana, Dec. 3-5.

Illinois Institute of Technology, Modern Builders Conference, Prudential Building, Chicago, Ill., Dec. 6-7.

Highway Research Board, annual meeting, Sheraton-Park Hotel, Washington, D. C., Jan. 7-11.

American Road Builders Association, annual meeting and road show, Chicago Amphitheater, Jan. 28-Feb. 2.

"Maintenance alone has sold us on FORD POWER!"

"Our operation is particularly wearing on engines. But with Ford-powered equipment on the job, our maintenance problems and costs have been way below average. That's why in future purchases we'll consider, quite favorably, equipment that is powered by Ford Industrial Engines."

—EDWARD F. BRARMANN, JR.
Supt. of Parks and Shade Trees
Englewood, New Jersey

Again, Ford is first choice where economy counts

Englewood's Park Department now owns a total of six Ford-powered field units. Above, you see one of them in action—a 12″ Asplundh Brush Chipper.

Powered by a Ford "172" Heavy Duty Industrial Engine, this speedy worker takes on branches up to a half-foot in diameter. It eliminates double handling, does away with countless trips to dumping areas and steps up Englewood's brush removal program by an estimated *six times*.

You'll see Ford-powered equipment making short work of similar tasks *everywhere*. And with good reason. For only Ford—in a *full line* of modern overhead-valve 4-, 6- and 8-cylinder gasoline engines—offers the economy of Short Stroke design, the longer engine life of deep-block construction.

Ford Short Stroke design cuts friction, lessens engine wear and releases more *usable* power . . . power that goes to waste in ordinary engines. The benefits of deep-block construction (also available in Ford's new super-efficient 4-cylinder Diesel) are a smoother running, more durable engine—one that requires minimum maintenance even in the toughest going.

Little wonder efficiency-minded power users like Mr. Brarmann are swinging to dependable, low-cost Ford Power. Why not you?

And, to better serve industrial power users, a network of newly-appointed Ford Industrial Products Dealers has been set up across the nation. Now there's a Ford Industrial Power Headquarters in *your* area.

Ford
INDUSTRIAL ENGINES AND POWER UNITS

Phone or write for complete information:

INDUSTRIAL ENGINE DEPT. FORD Division of FORD MOTOR COMPANY P. O. BOX 598, DEARBORN, MICH.

Engineered Rubber Products



A Long Drink of Water... for San Diego

For some 70 miles, the San Jacinto-San Vincente Aqueduct climbs and plunges in its southward course to San Diego, carrying the city's water.

This liquid life-line uses over 28 miles of 48 and 54-inch reinforced concrete pressure pipe equipped with steel joint rings.

These steel joint rings—about 8,500 in all—are sealed with U. S. Rubber round gaskets, made by the unique process of *continuous molding*. This process is exclusive with U. S. Rubber. Continuous molding produces the only seals that provide minimum compression set, precise tolerances (down to .008 if needed), and long life—all at reasonable cost.

This continuous molded gasket is only one of thousands of examples of how "U. S." experts engineer rubber and plastic parts in mass-production—yet at exacting tolerances. For your next construction job, contact any of the 28 "U. S." District Offices or write us at Rockefeller Center, New York 20, N. Y. In Canada, contact Dominion Rubber Co., Ltd.

Mechanical Goods Division

United States Rubber

ENGINEERING NEWS-RECORD

Vol. 157, No. 20 November 15, 1956

Number of copies printed this issue: 76,799

CONTENTS

NATIONAL AFFAIRS
- The Boom in Public Works Will Continue 21
- Big Day for Public Works 22
- Wall Backup Panelized 23
- "Grand Plan" Gets Out of Low Gear 24
- Bay Crossing Is Financially Marginal 24
- Concrete Landing Deck Goes to Sea 25
- Liberal Rules for Federal Pollution Aid 26
- Moles Name 1957 Awardees 26
- Search for Sturdier Asphalt Runways 27
- Reservoir Tunnels Will Locate Water Leaks 27
- Michigan Airport to Cost $10.7 Million 29

FEATURES
- New Use for High-Strength Steel 33
- Corrugated Metal Sewers Go In Along the Raritan 34
- Abrasive Rock, Asphalt Facing for Water Supply Dam 44

NEW PRODUCTS
- Twin-Shaft Machine Trowel 49
- Direct-Drive Pump for Tractor-Mounted Ripper ... 49
- Reinforced Plastic for Ladder Side Rails 52
- Trailer-Mounted Portable Steam Plant 54
- Rotary Drill Uses Air and Water 54
- Publications 56

MEN AND JOBS
- Dean Steinberg to Head Brazilian School 58
- General Chorpening Joins Firm 58

INTERNATIONAL
- Largest Sewage Lagoon for Regina 64
- Mackinac Bridge Studies for European Application 64
- Metal Umbrella Shields Construction 69
- Slotted Windbreak Protects Ships at Piers 70

FIELD AND OFFICE
- Drawings Inserted as Windows in Computer Punch Cards 78
- How to Compute Reinforcing for Oversize Columns 80

BUSINESS AND FINANCE
- Photogrammetry: Fast-Growing Business 107
- Road Materials Plentiful in Key Cities 107
- Construction Outlays Set October Record 108
- $10-Million Co-op Apartment Planned 108
- Loan Fund Shortage Causes Housing Delays 108
- $250-Million Face-Lifting for Philadelphia 108
- Construction Market: Baltimore 110

LABOR
- Teamsters' Aim: Two Million Members 114
- How Labor Interprets Election Results 114
- Building Trades Oppose Atom Plant 114
- Labor Blamed for High Building Costs 115
- AFL-CIO Housing Proposals 117
- Labor Unity Shows Gains 117
- Organizing Agreement Reached in Hawaii 117
- Lathers and Employers End Dispute 117
- Carpenters Support Lumber Industry Promotion ... 117

Reader Comment	8	Unit Prices	82
Calendar	14	Materials Prices	84
Obituaries	59	Construction Reports	87
Books	73	Scoreboard	104
Legal	77	Editorials	132

Back issues of ENGINEERING NEWS-RECORD *are generally available for the previous six months. Price 35¢ each copy except Annual Cost Issue. Semi-annual indexes will be sent on request.* ENGINEERING NEWS-RECORD *is also indexed in Industrial Arts Index and Engineering Index.*

THE CONSTRUCTION WEEK

MISSISSIPPI WATER CRISIS—If St. Louis' low water situation becomes an emergency (ENR Nov. 1, p. 21), Army Engineers will release 400,000 acre-ft of Missouri River water to supplement the normal 7,500 cfs winter release. Over a two-week period the additional flow amounts to about 15,000 cfs, over four weeks 7,500 cfs. The decision followed an emergency meeting of the Coordinating Committee on Missouri River Main Stem Reservoir Operation, composed of seven states and seven federal agencies. The helping hand to the Mississippi may entail some hardship in the Missouri Basin if 1957 is another dry year. As of November 12, river stage was —3.

LEASE-PURCHASE ON STATE LEVEL?—Attempting to hold down expenses—and to satisfy Trenton businessmen who don't want to lose state business—New Jersey's legislature will consider this week whether to go into a lease-purchase arrangement as a means of getting needed state office space. Gov. Robert Meyner has proposed moving scattered state offices out of Trenton to new buildings in the city's suburbs. State Senator R. R. Stout, head of a legislative commission taking up the problem of new office space, suggested the lease-purchase plan instead. He commented that private capital then would build the structures, and the state could take them over at no greater cost than the $1 million yearly now spent for rental in the capital city area.

NEIGHBOR GETS JUMP—While Detroit continues to argue about what's to be done about its port facilities (ENR Oct. 18, p. 23), neighboring Windsor, Ontario, was on the move last week to get into the race to develop Detroit River facilities. Ojibway Development Co., Ltd., announced it had paid $10.5 million for a 1,400-acre plot just east of Windsor city limits on the river for the express purpose of pushing it as an industrial and port area. Said Philip F. Morand, general manager for Ojibway: "The area comprises one of the few sites on deep water suitable for a major industrial complex, to be served by lake and ocean shipping."

Added point: Part of the area could be made available for a Detroit-Windsor municipal airport.

SAUCE FOR THE GOOSE—The City of Columbus, eyeing a recently-granted increase of 20% in pay to state-employed engineers, has asked the Civil Service Commission for a similar increase for city engineering employees. City councilmen citing payments of $3.1 million in fees to outside consultants since 1952, commented that better pay for city engineers would attract more men, result in more work done by the city's forces and less outside payments.



Always replace a HYATT with a HYATT!

There are two good reasons why you're smart to replace with *exactly the same* bearing the manufacturer specified for the application:

FIRST..... you assure the same smooth, trouble-free bearing performance originally built into the equipment.

SECOND.. you save time and trouble, because HYATT Hy-Rolls are so precision-built they're *completely interchangeable* without fitting adjustments.

Insist on HYATT Hy-Rolls—*be sure of lowest bearing cost per hour of service!* Hyatt Bearings Division of General Motors, Harrison, N. J.

Watch "WIDE WIDE WORLD"
Sundays on NBC-TV

Always look for the familiar blue and yellow box —when it comes to quality, there's no substitute for

GM
GENERAL MOTORS

HYATT HY-ROLL BEARINGS FOR REPLACEMENT

WASHINGTON OBSERVER

The partnership policy on natural resources may be on the way out. Top GOP officials—including Vice-President Nixon—are telling Eisenhower that discontent over power development was responsible in large measure for the Administration's setbacks in Senate and House races throughout the West.

Already, Interior Secy. Fred A. Seaton is looking for a new approach. Thus far, it's all in the talking stage, but Seaton and his advisers will probably come up with something that amounts to more of a middle-road approach than that of partnership. Seaton never was particularly sold on partnership, a concept he inherited from Douglas McKay who was one of the foremost Republican casualties.

Rumors have it that Housing Chief Albert Cole may go, but don't bet on it. These were particularly rampant just before the election, when GOP National Chairman Leonard Hall felt that housing policies were hurting the party. Cole got his job through the committee's patronage setup, but he has influential friends inside the White House and probably can't be forced out easily.

•

The housing slump will continue far into 1957—That's the newest advice that top government and business leaders give in their first post-election look at the economy. The estimates come from the Commerce Dept.'s Business Advisory Council meeting last week. Some other forecasters see a drop from the present rate of just over a million starts a year, to 900,000. Dollar volume is going up because of increased materials prices, and because home buyers are wanting larger establishments.

Other construction is continuing to be healthy. Expansion of capital plant and equipment in 1957 will at least match this year's rate. The third quarter this year is estimated at a $36-billion annual rate, some $6-billions over 1955.

Steel production will be up in 1957 to meet rising demand, but the waiting time on deliveries of some types—structurals and plate—will continue to be on the long side.

Credit will continue to be tight. Administration officials hold out little hope of any easing soon. Indeed, there are significant hints that the Federal Reserve Board may tighten it even more by approving another rise in the discount rate that district reserve banks impose.

•

Bidding and contracting procedures on lease-purchase projects are being revised by the General Services Administration in an attempt to stir more interest among contractors and investors.

The new policy is the result of receiving non-matching bids under the original policy of permitting bidders to submit a combination bid covering both financing and construction, or financing alone, or construction alone. Bids received just didn't work out. So, the Council Bluffs, Iowa, Post Office-Court House and the Public Health Service Communicable Disease Center at Atlanta, Go. are being readvertised under the new terms:

Only "package bids" covering financing and construction will be asked from here on out. Separate bids will no longer be invited.

The government will now pay all real estate taxes directly to the taxing authorities involved.

Bids will be asked for either 10 or 25 year terms, with bidders having the option to bid on either or both bases. Other changes include limiting the government's right to pre-payment of unpaid balance to the last half of the term of the purchase contract.

The new terms will be applied to six other projects already out for bids: buildings at Abingdon, Va.; Albuquerque, N. M.; Burlington, Iowa; Green Bay, Wis.; Huntington, W. Va.; and Kansas City, Kan.

LOOK FOR THE
JENKINS DIAMOND

MADE BY THE ORIGINATORS OF RENEWABLE DISC VALVES

Jenkins Bros. has remained the leader in composition disc development and production since 1864, when the first renewable disc valve was introduced.

THE ONLY MANUFACTURER OF BOTH VALVES AND DISCS

Jenkins Bros. devotes continuous laboratory and field research to disc improvement through use of new compounds, and new production techniques.

NEW GUIDE FOR DISC SELECTION

Describes all Jenkins Discs, and their applications for steam, hot and cold water, air, gas, oil, gasoline . . . including the new TEFLON® DISC for lasting, dependable control of oxygen and other gases, solvents, acids, alkalies, and other chemicals,— and for liquid food and similar services.

Ask your Jenkins Valve Distributor for Disc Folder Form 203, or write: Jenkins Bros., 100 Park Ave., New York 17.



. . . for highest efficiency, use the time-proved combination . . . JENKINS DISCS in

JENKINS VALVES

TRADE JENKINS MARK
Jenkins Bros

Order from Your Local Jenkins Distributor

EISENHOWER IS WINNER IN 41 STATES

Last week's headlines indicate that . . .

The Boom in Federal Work Will Go On

Four more years of expanding federal construction can be counted on as a result of last week's elections.

The voters kept the old management on the job: Eisenhower and his Republican team running the executive branch and the Democrats holding the purse strings in Congress. This is the "partnership" that has consistently boosted federal construction spending during the last two years.

There will be no dip in the upward trend of government outlays for roads, dams, schools and hospitals in the next four years. Rather, the rising curve of federal construction—both for new project starts and for cash expenditures—is likely to go up even more rapidly.

Part of the predictable fast rise is made certain by laws already on the books. Federal payments to the states for highway construction will step up from $1 billion in the current fiscal year ending next June 30 to $1.5 billion in the following 12 months and to $2 billion the third year and $2.7 billion the fourth. At the same time, federal grant and loan programs for sewage treatment plants, nuclear power, urban renewal projects, local irrigation and watershed development works, low-rent public housing, airports and medical facilities will be taking hold in a big way.

Added to these programs—already enacted and in operation—are strong prospects for other live proposals that failed to pass in the last session but will come up again for legislative action as soon as the new Congress organizes on Jan. 3. Chief among the big construction possibilities is federal aid for new school buildings. The White House and the Democrats try to pin the blame on each other for defeat of this legislation in the last Congress, but integration, of course, is the derailing tool that opponents of the Kelley Bill used then and will attempt to use again.

This time, however, the opposition is less sure of success. The changed outlook stems largely from the tough job that faces the Republicans in building up party strength for the Congressional races of 1958 and the Presidential contest two years later. Their objective plainly is to prove themselves bigger, broader and more conscientious than the opposite party in promoting the public welfare.

Federal aid for school construction is a major plank in the welfare platform of both parties. Eisenhower swung over to full-powered support of the idea after his White House Conference on Education recommended it last December. But his team held out for distribution of federal funds on a basis of need and effort rather than on a school-enrollment basis as written into the Democratic bill.

When the next Congress convenes, the White House will bend more pliably toward a compromise that the Democrats can accept, just as it did on the highway bill during the last session. In the new spirit emanating from the President's office, school aid will stand a better chance. It remains to be seen, however, whether the White House can hold Rep. Adam Clayton Powell and other recalcitrants in line to permit passage without an anti-segregation fight.

Other construction programs, both operational and pending, will likewise benefit from the more expansive White House policy. Vice President Richard Nixon will share the spotlight on the liberalized approach.

Eisenhower recognizes that his Vice President is far from equalling the Commander-in-Chief as a public idol, and Republican strategists know they have to play some smart politics during Eisenhower's second term to build up Nixon's prestige as a Presidential candidate for 1960.

They count on little help from Congress on this big job. Democratic control of the legislative branch will continue, they fear, even after the House elections of 1958.

Accordingly, Administration policymakers aim to outdo Congressional Democrats in promoting sound development of national resources. All phases of federal construction will feel the effects of this generous and sympathetic attitude toward programs and projects.

Congress next year will be in the same hands that have run the two houses for the last couple of years. No changes are in prospect for House and Senate leaders or for committee chairmen, except on House Interstate and Foreign Commerce, where Rep. Oren Harris of Arkansas moves up to take the place of deceased J. Percy Priest.

Speaker Sam Rayburn will remain in charge of the House and Sen. Lyndon Johnson will continue as Democratic leader of the Senate. The powerful House Rules Committee still will be dominated by Chairman Howard Smith, stout Virginia conservative who almost smothered the 1956 housing legislation.

Chairmen of the last Congress will continue to head the important Appropriations, Public Works, Interior, Agriculture, Armed Services, Veterans, Banking and Judiciary Committees, as well as those dealing with taxes and with federal aid for schools.

Highways, housing and Administration credit policies are due for sweeping investigations as a result of the elections. Bertram D. Tallamy of New York is now sure to take the post of Federal Highway Administrator in January, succeeding the temporary head, John A. Volpe of Massachusetts. But the chairmen of the roads subcommittees in the House and Senate have promised thorough hearings on the progress being made by the Commerce Department in getting the $33-billion highway program started.

Neither Sen. Albert Gore nor Rep. George H. Fallon, heading the respective committees, is satisfied with the slow job done by Commerce Secretary Sinclair Weeks in obtaining a highway administrator. Both groups have searching questions to ask regarding the promised build-up of the bureau that handles the program and action taken to get the work rolling. Looming large is the possibility that Congress may get behind Gore's plan to set up an independent commission to take charge of public roads.

Voters Add 2 Billion to Local Debt But Bar $150,000,000 Projects

...Big day for public works

Christmas for the construction industry came on Nov. 6 this year as voters approved more than $2 billion worth of bond issues for scores of state and local public works projects.

A record total of $2,678 million was presented to the voters; 85% of the total was approved.

For statewide bond issues, California led the list. Voters there approved issuance of $800 million in state bonds. The total included $500 million to help veterans finance purchases of farms and homes and $300 million for construction of schools and colleges.

New York also boosted the bond issue total as Empire State voters approved a king-size $500-million issue for highways. A similar proposal, for $750 million, was defeated previously because of widespread opposition to a mandatory two-cent a gallon increase in the state gasoline tax incorporated into the bond issue proposal. This time, there was no provision for a tax increase, and the bond issue won handily.

New York voters did an about-face on another major bond issue. After voting $50 million to start a middle-income housing program in November, 1954, they rejected this year a proposal to extend the program to the tune of $100 million. This was the largest single bond issue defeated Nov. 6.

Texas voters approved a $100-million bond issue for a loan fund that will help ex-servicemen purchase homes and farms.

Kentucky's $100-millon bond issue for highways won, ensuring the state ample funds to match federal contributions that will be received under the new highway program.

• **Baltimore opens purse**—Aside from these $100-million-and-up statewide bond issues, the biggest eye-catcher was Baltimore's package. Voters agreed to spend some $94.8 million for a variety of public works programs.

Biggest item on the Baltimore ballot was a $45-million proposal to finance construction of a pipeline to the Susquehanna River and to expand the city's distribution system. The pipeline will cost $35 million. It will extend some 37 miles from the City of Baltimore to the Susquehanna River above Conowingo Dam. By adding this new water source to the city's system, authorities expect to have adequate supplies until the year 2000.

Two major school construction bond issues also were approved in Baltimore. One, for $14.5 million, will finance construction of three senior and junior high schools and four elementary schools during 1957.

The second school bond issue, for $15 million, will pay for construction of four high schools and two elementary schools in 1958.

Other major Baltimore bond issues approved included:

- $6 million for a civic center.
- $5 million for sewerage and storm water drainage systems.
- $5 million to continue the city's program of financial aid to private groups building parking garages and parking lots.

(For other developments in Baltimore, see page 110.)

San Francisco gave the go ahead to two bond issues that totaled $52 million.

The voters approved a $27 million bond issue for school construction. This will finance two new high schools, three new elementary schools and additions to existing schools, including buildings at San Francisco City College.

The other San Francisco bond issue, for $25 million, will finance improvements at San Francisco International Airport. These improvements include extensions to runways, helicopter facilities and additional concourses to handle passenger loading.

Elsewhere in California, Fresno voted $11.8 million for schools; Redding approved $3 million for schools; San Diego, $27 million; San Rafael, $7.5 million for roads; Los Angeles County, $15.4 million for the new Harbor Hospital and $15.5 million for a juvenile detention building.

• **Pays to publicize**—Proof that it pays municipalities to publicize public works bond issues was demonstrated in the emphatic manner as Philadelphia voters approved three proposals to borrow a total of $46.9 million for capital improvements.

The three passed by a margin of nearly 3 to 1. Yet, only three years ago, the same proposals were handed a thumping defeat, which set the city's proposed improvement program back on its heels.

Immediately after the initial setback, the mayor formed a citizens' committee to acquaint the voters with the projects and explain why they were needed. The three-year campaign worked, and the city will now be able to spend:

- $24.8 million for rehabilitation of the city's water and sewer system.
- $18.1 million for construction at the port, airport, commercial museum, exhibition and convention halls, police and fire stations, libraries, the Broad Street subway, redevelopment, streets, bridges and miscellaneous facilities.
- $4 million for construction of hangars at International Airport, these hangars will be leased to private operators.

Wichita, Kan., in approving a $40.1-million bond issue, charted new paths in city water department functions and financing. Of the total, $32.5 million is earmarked to enable the city to buy the privately-owned Wichita Water Co. This will consolidate the city-owned water supply and the privately-owned distribution systems. Slightly more than $7.6 million of the amount voted will finance construction of a pipeline to a proposed reservoir 25 miles distant on the Ninnescah River. (This reservoir is expected to be built soon as a federal flood control project.)

In Cincinnati, voters authorized expenditure of $15.5 million for expressways; $9 million for urban renewal; $6.5 million for street improvements. Hamilton County also voted $6 million for roads and $4 million for storm and sanitary sewers.

Seattle voted a total of $32.5 million in bond issues. One issue, for $25 million, was for King County School District No. 1. This issue will make it possible for work to start within two years on an extensive school-building program including two $3.3-million high schools; a $2.5-million junior high school and three $1-million additions.

The other major Seattle bond issue will finance a $5-million civic center.

While Seattle voters were generous on these propositions, they turned a deaf ear to a proposed constitutional amendment that would have permitted the state to take immediate possession of property being condemned for highway right-of-way.

Cook County, Ill., which includes Chicago and several populous suburbs, voted $25 million for hospital expansion program.

Chicago voters also authorized a $10-million bond issue for street lighting.

Aside from the bond issues, the ballots carried a number of constitutional amendments or other proposals in vari-

ous states that directly affected construction.

One of the most publicized, and one of the most controversial, was a California constitutional amendment that would have clarified the right of the state to hire private architects and engineers for public works design. The proposal was rejected by a large margin. The defeat generally was attributed to efforts of the California State Employees Association, which contended the proposal was a threat to civil service and an opening wedge for return of political spoils system. However, many leading civil engineering and contracting groups supported the measure. The vote means that design of state buildings, highways and water resources projects must be done by the state civil service employees. With bigger construction programs developing, the State of California apparently will be in the market for more engineers and architects.

Garbled Road Web?

Private group asks for a reappraisal and integration of state's highway system

Complete reclassification of Connecticut's highway system and integration of all important highways into one system has been urged by the Connecticut Public Expenditure Council, a privately financed group.

Stating that the 3,000-mile system is not continuous or logically planned, the council expressed concern that the haphazard results of more than 40 years of piecemeal legislation would affect the $1-billion program of construction scheduled under the new federal highway bill.

The report claimed that roads now under jurisdiction of the State Highway Department contain 116 separate system breaks, a total of 170 miles, that are under local jurisdiction. Many of them occur in metropolitan areas where state highways end at city lines and connecting urban routes are locally financed and locally maintained. Where such breaks occur, roads tend to be narrow and congested.

The council also said that there are an additional 20 sections of state highway completely disconnected from any other part of the state highway system. Maintenance of such sections, many of them less than a mile in length, is "needlessly expensive."

Besides the others, according to the group, there are about 200 state-maintained spurs that usually run for short distances off state highways and come to an abrupt end. These in the opinion of the council should not be a part of the designated state highway system.

FROM THE INSIDE of a new Minneapolis office building, prefabricated backup panels were attached to vertical mullions.

FROM THE OUTSIDE a colored glass facade was placed in front of the backup, which was left exposed temporarily, (arrow).



GLASS WALLS and windows enclose the four-story building above the first floor.

Wall Backup Panelized

For the exterior walls of the $4-million, 4-story headquarters office building being constructed for American Hardware Mutual Insurance Co. in Minneapolis, Minnesota, a rigid-insulation backup was assembled into a single unit for installation above and below each window.

The walls are only 3½ in. thick. They consist of an exterior facing of opaque, colored glass panels separated from the panelized backup by a 1-in. air space. The backup consists of 2-in.-thick cellular-glass units in a pan of galvanized sheet metal, with a double rubber gasket around the outer edge. Placed from inside, the pans were attached to mullions that extend the height of the building. The colored glass panels were installed from outside.

Thorshov & Cerny, Inc., Minneapolis, were the architects.

Under pressure from the White House . . .

The "Grand Plan" Gets Out of Low Gear

Under the spur of a Presidential directive, U.S. government sources reported last week that the nation's $33-billion interstate highway program is beginning to move with some speed.

John A. Volpe, Federal Highway Administrator, says that 31 states have contracted for 107 projects on the system in the period between June 29 (when President Eisenhower signed the highway bill) through Oct. 26. The contracts, covering costs of more than $100 million, involve 276 miles of road within the interstate system.

In addition, Volpe points out, plans have been approved and bid calls authorized for 40 additional projects to cost $120 million. Most of these jobs will be let within the next three weeks.

The work to date is still a small dent in the $7 billion that most sources confidently expect will be spent during 1957 for highway work of all kinds—including the interstate system, for which the federal government is putting up 90% of the funds. But it is taken as evidence that the program is beginning to move and soon will snowball into proper proportions.

• **States get busy**—Evidence of the increasing tempo of highway work is the information that California—moving into high gear on its own expanded highway program—has advertised $62.7 million worth of contracts within the last six weeks.

State Engineer G. T. McCoy reports that California has let or advertised some $163.5 million of road construction work out of its 1956-1957 fiscal year budget. Although only four months of that fiscal year actually have elapsed, the total represents about 87% of the major construction projects that are included in the budget. Much of the remaining $25 million in projects for the current fiscal year will be placed under contract or advertised by Jan. 1.

Another state moving fast is Montana, where the Highway Commission has awarded the largest block of contracts in the state's history—10 jobs worth $3.8 million. The latest award brings to $23.7 million, the total value of contracts awarded during 1956, and one more sizable letting is scheduled to take place before the end of the year.

North Carolina, meanwhile, announces it is "well into" a construction program aimed at bringing its 717-mile portion of the interstate system up to engineering standards for safety and for movement of large volumes of traffic. Chief Engineer W. H. Rogers reports that of the total mileage, locations have been decided upon for 350 miles, and 175 miles of road are in various stages of construction. A problem has cropped up, however, in the matter of width of right-of-way. In recent years, North Carolina has been building limited access highways with a 260-ft right-of-way. But now the state feels it should have 300-ft right-of-way available, and this change will cause further negotiation with many property owners.

And in Ohio, the State Highway Department reports it will spend an additional $83 million to convert the 84-mile segment of Ohio Route 7 between East Liverpool and Hannibal into a more modern highway. Much of the route will be made four-lane, and the rest will be two-lane with a four-lane right-of-way.

• **Other developments**—Other highway plans not directly connected with the federal interstate system are pushing ahead, according to reports to ENR's correspondents.

Missouri and Kansas highway officials have conferred with the U.S. Bureau of Public Roads on plans for a new bridge across the Missouri River to link the two Kansas City's—or a determination on expanding present connections via the Intercity Viaduct. The officials have agreed to employ a consulting engineer to make a feasibility report on the plans.

In Virginia, construction of a second tunnel under the Elizabeth River between the cities of Norfolk and Portsmouth moved a step nearer when the Elizabeth River Tunnel Commission authorized consulting engineers to execute a contract, for test borings.

Meanwhile, officials of four states—Wisconsin, Illinois, Iowa and Missouri—have been invited to Milwaukee Nov. 16 for an all-day meeting to push construction of an express highway linking Milwaukee's port area with industrial areas to the south and west. The proposed highway will be built south from Milwaukee through Janesville and Beloit in Wisconsin, Rockford, Rock Island and Moline in Illinois and Davenport, Ia.

And Kentucky, which already has paid a management firm $37,000 to look into its highway department's operations and administration, has agreed to pay another $50,000 for an extension of the survey. State officials look wryly at the report to date, which lists such inefficiencies as hand-kept records, an odd district-and-zone administrative setup, and a listing of political pressures on the department to the point where administration had bogged down.

Bay Crossing Called Financially Marginal

The $235.7-million version of the proposed southern crossing of San Francisco Bay—complete with approaches—cannot be built at a 25-cent basic toll, according to Smith, Barney & Co. in a financial feasibility report made for the California Department of Public Works.

A minimum-cost of $183.5-million crossing, without approaches, could be built at a 25-cent toll, the report said. But, it cautioned that the revenue bond issue must be considered "marginal as to financial feasibility" and added that an increase in tolls might be necessary later to maintain net revenues for debt service.

The report explained that "the projected $180 million of revenue bond financing necessary to finance its construction would not comply with all of the generally-accepted investment standards for such securities and the minimum $183.5-million southern crossing must, therefore, be considered marginal . . . particularly in view of the unfavorable money market conditions which exist today."

The 40-year issue also will have to bear a higher rate of interest than the Toll Bridge Authority has paid in the past, the report indicated. Probable interest rate would be 4¼% to 4½% with a substantial discount. The authority has sold previous issues at par.

The report that the Toll Bridge Authority authorized last June was limited to feasibility studies at the 25-cent toll. However, Smith, Barney urged the authority to give serious consideration to imposing higher tolls on the proposed crossing. This probably would mean an increase in the present 25-cent toll on the existing San Francisco-Oakland Bay Bridge. Revenue for repayment of the bond issue will come from combined tolls from the two spans.

Norman C. Raab, projects engineer and chief of the Division of San Francisco Bay Toll Crossings, has said he believes the entire project could be financed on a 35-cent toll because of the excellent financial record of the authority and the strong growth potential of the Bay Area. But, he is not urging such a toll.

Raab pointed out that if revenues would not permit financing of the approaches by revenue bonds, they could be built by the cities or by the state.





TENDERS converted from LSTs were fitted two at a time with 70x50-ft landing decks of precast concrete on steel framing.



RIBBED CONSTRUCTION of slabs, plus use of lightweight aggregate, kept down weight of the 7x10-ft by 8-in. thick units.

Seagoing heliport serves offshore oilmen as . . .

Concrete Landing Deck Goes to Sea

In a seagoing adaptation of construction materials ordinarily confined to use on land, four converted LSTs that service oil-drilling sites off the Texas and Louisiana coasts now are equipped with prestressed, precast concrete landing decks for helicopters.

In the past, steel and wood decks have been used for this purpose. The switch to concrete is an attempt to answer the petroleum navy's need for a low-maintenance deck with high resistance to fire, weather and salt water.

Measuring 70 x 50 ft, each deck comprises 50 ribbed slabs 7 x 10 ft by 8 in. thick, supported on steel framing erected above the ship's stern. The pretensioned slabs are made of lightweight concrete containing expanded-clay aggregate. Weighing 2,170 lb each, they have six longitudinal ribs (one along each side, four spaced between) and a transverse header beam at each end.

For positive anchorage of the deck, embedded steel plates in the slabs are welded to the supporting steel frame members. Rubberized mastic seals the joints between slabs. Also embedded in each slab, four galvanized steel lifting hooks served first to speed handling and erection, now provide tie-down points for helicopters.

The decks are designed to withstand the 8,400-lb impact loads (per wheel) of Sikorsky S-58 helicopters. These craft shuttle between shore and drilling stations as far as 100 miles out in the Gulf of Mexico, maintaining messenger, freight and passenger service.

Erection of the slabs went fast. It took the Rackle Co., of Houston, Tex., only a day to install the deck on each of the four tenders. The firm manufactured the slabs at its plant 110 miles from the shipyard of the Levingston Shipbuilding Co., Orange, Tex., where the slabs were to be installed on the tenders; then trucked the sections to shipside and transferred them from trailer to boat by barge crane.

Guy F. Atkinson . . .

Louis R. Perini . . .

President names advisory board, approves . . .

Broad Rules for Pollution Aid

Officials of the U. S. Public Health Service in Washington firmly believe the "propriety of federal aid" criteria (see box) recently approved for the sewage works construction grants program are liberal enough to include virtually every project certified by a state pollution control agency.

Although PHS views the criteria very broadly, it cautions that they are not meaningless, that the criteria were written to be utilized. Thus, in addition to guiding the Surgeon General in approving applications, they may also end up as an overall guide to state agencies in setting priorities. Municipalities are asked in the application form "how the project will meet criteria for determining the propriety of federal aid."

Approval of the criteria by the White House triggered the flow of paper work for the grants program under the new water pollution control act. Application forms should be in the hands of interested cities this week, mailed either from the PHS regional office or the state pollution agency, as desired by the latter. Regional PHS offices will apply the federal criteria initially.

Also available this week is a listing in the Federal Register (for Nov. 9) of some 10,000 cities, towns and sewerage districts and their sewage treatment needs. Being on the list constitutes a hunting license for a federal grant since unlisted projects cannot qualify. The list was compiled by state agencies and approved by PHS.

• **Advisory board**—President Eisenhower last week named the first Water Pollution Control Advisory Board, created last July by Congress to give policy guidance to Surgeon General Leroy Burney in administering the new pollution law.

The President reportedly is looking for another industry man to bring the Advisory Board to full strength authorized by Congress—nine appointees serving under the chairmanship of the Surgeon General.

The eight members named last week are: Charles R. Hook, board chairman of Armco Steel Corp., Middletown, Ohio; Milton P. Adams, executive secretary, Michigan Water Resources Commission; Daniel Bergsma, New Jersey Commissioner of Health; Morris B. Cunningham, Oklahoma City's Director of Public Works; Charles H. Elston, Cincinnati attorney who had led Republican support for the original federal water pollution act as a member of Congress in 1948; William A. Galbraith, director, Washington State Department of Conservation and Development; Howard P. Sawyer, a retired physician and prominent conservationist of Sanbornville, N. H.; and Carl D. Shoemaker, conservation consultant to the National Wildlife Federation, Washington, D. C.

Appointees will serve without pay, except for a per diem allowance when attending meetings. First meeting is expected in January.

1957 Moles Awards

Atkinson, Perini to be feted by dam and tunnel builders

Guy F. Atkinson, 81-year-old board chairman of Guy F. Atkinson Co. of San Francisco, and Louis R. Perini—almost as famous as a contractor as he is as a baseball club owner—will be recipients of the 1957 Moles Award.

Perini, president of B. Perini & Sons of Boston, is the member-awardee, while Atkinson will receive the non-member award.

The awards will be presented at the organization's annual awards dinner, to be held at the Waldorf-Astoria Hotel in New York City next Feb. 7.

Perini's company has figured in many large tunnel and dam jobs in the East over the last 20 years. He is also owner (with his two brothers) of the Milwaukee Braves baseball team. Atkinson has long been engaged in major construction work, including Grand Coulee Dam and McNary Dam and Powerhouse.

Criteria for Propriety of Federal Aid

The propriety of federal aid pursuant to Section 6 (c) of the pollution control act (P.L. 660) will be determined by the Surgeon General on the basis of one or more of the following criteria:

INTERSTATE, COASTAL AND GREAT LAKES WATERS—Whether the project is required to control pollution of interstate waters, coastal waters or waters of the Great Lakes (including tributaries of such waters contributing materially to the pollution of such waters), and such pollution is inimical to public water supplies, propagation of fish and aquatic life and wildlife, recreational purposes, or agricultural, industrial, or other legitimate water uses.

INTERNATIONAL TREATY OBLIGATIONS—Whether the project is required to control pollution in meeting international treaty obligations or agreements.

FEDERAL IMPACT—Whether the project involves a pollution problem substantially and adversely affected by (1) federal installations contributing to the total municipal waste loadings; (2) a water-use requirement involving national defense; (3) a federal water resource development; or (4) an influx of population to carry out federal activities.

PUBLIC HEALTH NECESSITY—Whether the project involves treatment works required to abate a serious public health hazard.

FINANCIAL BURDEN—Whether the municipality can demonstrate that the construction of needed sewage treatment works involves an extraordinary and excessive financial burden in relation to its economic resources.



TUNNELS drawn parallel to and . . .



BENEATH reservoir sides would . . .

Locate Water Leaks

A tunnel under each shore of the reservoir behind its proposed dam on the Pend Oreille River has been offered by City Light of Seattle as a safeguard to mining properties in the area against possible damage from water seepage.

Mining interests have threatened to oppose granting of a construction license by the Federal Power Commission for an as yet unnamed $140-million, 540,000-kw hydro project near the Canadian border. City Light hopes its scheme will overcome all objections to its license application.

The utility's plans call for a 7x10-ft tunnel on each side of the river, 100 ft below its bed and directly beneath the reservoir side. The tunnels would enable location and sealing of any faults through which reservoir water could drain off into adjacent or bodies. They would also serve as drains for mines of the area.

Initially, the tunnels would be two miles long, starting six miles above the dam. If mining operations continue northward, toward the damsite, City Light would extend the tunnels, always staying 3,000 ft ahead of the workings.

The dam itself would be 385 ft high and 975 ft long. Gross head would be 261 ft, utilized by six 90,000-kw generators at the outset. The reservoir would back water to the base of Box Canyon Dam.

Seattle officials are hopeful that construction can begin next summer. The project would require about six years for completion.

The search is on for . . .

Sturdier Asphalt Runways

Demonstration tests of heavy-duty pavements by the Corps of Engineers last summer are now said to have substantiated the judgment of the Air Force in barring use of flexible pavement—designed to Army Engineer specifications as modified up through December 1955—but the tests also prompted a new cooperative research program to develop asphaltic concrete mixes that will stand up under the most extreme conditions.

The advantages of having two acceptable materials—concrete and asphalt—are obviously too great to allow any other course.

At the invitation of the Flexible Pavement Branch, Waterways Experiment Station, Vicksburg, Miss., the Asphalt Institute is working with the Army Engineer laboratory on the decision of asphaltic concrete mixes that will meet the severest traffic and temperature requirements. Utilizing aggregates locally available in various parts of the country, the asphalt engineers aim to produce pavement mixes that will remain stable and rut-free in the hottest climates under repeated applications of maximum test loads by simulated aircraft landing gear, traveling in the narrow path that is typical of jet bomber traffic.

Answers to the problem have yet to be worked out, but the asphalt pavement people are confident they can produce mixes that will pass any test now contemplated.

• Changes Needed

Accelerated traffic tests with B-47 bomber loads on portland cement and asphaltic concrete pavements (in 200-ft tandem sections of taxiway at Kelly AFB in Texas last May and June) quickly demonstrated to the Army Engineers and the asphalt technologists of the country that design criteria now being used required immediate, drastic revision.

Asphaltic concrete pavement designed and constructed by the Corps of Engineers in accordance with its latest specifications began to show tire printing and slight lateral movement at about 5,600 applications of 100,000-lb single-axle load.

It rutted so baldly at about 36,000 applications—ruts about 1¼ in. deep—that testing of the asphaltic concrete portion was stopped.

By contrast, the rigid pavement section—likewise constructed to Corps standards in a slab 20 in. thick—took the whole prescribed test of 120,000 load repetitions without distress.

Both sections were traversed by a tandem hookup of two simulated B-47 dual-wheel landing gears, carrying 100,000 lb each on tires with a contact area of 267 sq in. The test gear traveled a lane 7.4 ft wide in the center of the taxiway and distributed its trips uniformly over this narrow center strip.

Under actual field conditions, 75% of B-47 aircraft traffic falls within a 7.5-ft lane. It was this concentrated channelizing of B-47 traffic in narrow central tracks that caused the Army Engineers to raise their test requirement from 20,000 single-axle load repetitions to 120,000.

Pavement design criteria had been stiffened in June and December of last year to require increased thickness for both types of pavement and higher stability value for the flexible type, plus greater compaction for all substructure materials, including a thicker base course immediately under the bottom lift of asphalt surfacing.

So far as the asphaltic concrete itself is concerned, the stepped-up criteria proved inadequate in the Kelly Field test. The overall construction requirements called for a 5-in. asphaltic concrete surface and a 53-in. substructure under it.

• Construction Good

In the words of the Vicksburg engineers who had charge of the test, the H. B. Zachry Construction Co. of San Antonio "did an excellent job of construction for both the rigid and flexible pavements and had no difficulties in meeting the design criteria." Zachry at the time was building both types of pavement under a construction contract for a runway, taxiway and large apron at Kelly AFB.

How well the asphaltic concrete in the pavement conformed to laboratory design—and how the same bituminous material behaved under test—can be determined by a reading of the accompanying table (see next page). Cores were taken from the asphaltic concrete at various coverages (round trips of the tandem rig, equivalent to four load applications per coverage) up to 8,605, for inspection and analysis. The table gives the data on stability, flow, density and voids, as derived from cores for each interval of traffic coverage.

Density of the asphaltic concrete increased rapidly under the accelerated traffic. The rig operated two ten-hour shifts for an average of about 500 coverages (2,000 load applications) per

(Continued on page 29)



Switch to wagon drills and TIMKEN® carbide insert bits cuts drilling and powder costs 1/3

. . . Reports Linwood Stone Products Co.

WHEN Linwood Stone Products Company switched from well drills to wagon drills, they also switched to Timken® DC and KC carbide insert bits. And they got extra depth before resharpening, fewer shattered inserts, and less binding in the small-diameter blast holes. The payoff: *drilling and powder costs were cut one-third.*

For small diameter blast holes, constant-gauge holes, and extremely deep holes—particularly in hard, abrasive ground—Timken carbide insert bits are your best investment.

But carbide insert bits may not be best for all your drilling jobs.

In ordinary ground, for instance, Timken multi-use rock bits are most economical. With correct and controlled reconditioning, they give you the lowest cost per foot of hole when full increments of steel can be drilled.

You can count on Timken rock bits to last longer because the special Timken shoulder union protects the threads from drilling impact. And both Timken carbide insert and multi-use rock bits are made from electric-furnace Timken fine alloy steel. No other rock bit manufacturer makes his own steel to give you extra quality control.

With Timken rock bits, you'll save time when you have to change from one bit type to another, because Timken carbide insert and multi-use rock bits are interchangeable in the same thread series. As the ground changes, you can change bits quickly and easily—right on the job.

For all your drilling jobs, profit from the more than twenty years of drilling experience you get when you call or write: Timken Rock Bit Engineering Service, The Timken Roller Bearing Company, Canton 6, Ohio. Cable address: "TIMROSCO".

Timken threaded multi-use rock bit

Timken threaded carbide insert rock bit

your best bet for the best bit . . . for every job

TIMKEN

TRADE-MARK REG. U. S. PAT. OFF.

. . . How runway paving materials reacted to accelerated tests

	Asphalt Content, %			Stability			Flow			Density, Lb/Cu Ft		
	Surface	Upper Binder	Lower Binder	Surface	Upper Binder	Lower Binder	Surface	Upper Binder	Lower Binder	Surface	Upper Binder	Lower Binder
Lab design	5.0	3.5	3.5	2200	2450	2450	14	13	13	148.2	149.2	149.2
Plant lab	5.0	3.5	3.5	1508	2268	1591	10	9	9	146.9	149.0	148.1
Specifications				1800 minimum			16 maximum			.....	.....	.....
0 Coverages	5.0	3.5	3.5	444	756	318	11	11	13	143.4	146.3	144.3
24 Coverages				808	1453	900	10	9	10	146.2	148.7	147.4
300 Coverages				1119	2123	966	10	9	8	146.7	149.4	148.0
1012 Coverages				1292	2035	1157	10	8	7	147.7	151.1	149.7
2820 Coverages				.....	.....	.....	..	..	..	149.3	153.3	152.6
4370 Coverages										149.2	153.2	151.0
8605 Coverages				1317	1994	1535	21	19	12	149.9	153.5	152.1

day. By 1,000 coverages, the pavement density exceeded 100% of design value; and, when round-trip coverages by the tandem rig reached 8,600, pavement density had climbed to the range of 102 to 103%. With the asphaltic concrete squeezing tighter in the pavement and voids decreasing, the mixture "flushed" and showed plastic flow, according to the Vicksburg laboratory.

Asphalt Institute engineers were interested observers of the Kelly test through all its phases of design, construction and traffic operation. The traffic was applied in warm weather when pavement temperatures were generally high, ranging from 80 to 140 F.

Failure of the asphaltic concrete was in no way related to faulty substructure, the Army Engineers say. Their Flexible Pavement Branch reports that the subgrade, subbase and base of the flexible pavement section performed satisfactorily and would probably have withstood 30,000 traffic coverages (120,000 load repetitions).

	Voids, %						% Plant Laboratory Density		
	Total Mix			Filled					
	Surface	Upper Binder	Lower Binder	Surface	Upper Binder	Lower Binder	Surface	Upper Binder	Lower Binder
Lab design	4.2	5.6	5.6	69.0	59.0	59.0	....	.....	.....
Plant lab	4.7	5.8	6.3	71.8	59.7	57.4	....	.....	.....
Specifications	3-5	5-7	5-7	70-80	50-70	50-70	....	.....	.....
0 Coverages	7.0	7.4	8.6	62.6	53.0	49.1	97.5	98.3	97.4
24 Coverages	5.2	6.2	6.7	70.0	59.4	56.2	99.5	99.6	99.3
300 Coverages	4.7	5.4	6.3	72.2	61.1	57.7	100.0	100.1	99.7
1012 Coverages	4.1	4.6	5.3	74.5	66.6	62.4	100.5	101.4	101.1
2820 Coverages	3.1	2.9	3.4	80.0	75.1	72.3	101.6	102.9	103.1
4370 Coverages	3.2	3.0	4.4	79.2	74.6	66.4	101.6	102.8	101.9
8605 Coverages	2.7	2.8	3.8	82.0	75.9	69.6	102.0	103.0	102.7

• Answer Sought

The Army Engineers have good reason to believe that the Kelly Field problem can be licked.

After the asphaltic concrete failure at Kelly, the Flexible Pavement Laboratory set up additional tests of small panels in an existing test section at Vicksburg. So far, the laboratory has experimented with leaner mixes, with lower penetration asphalt and with rubberized asphalt. All three have stood up satisfactorily under 30,000 traffic coverages, except for cracking of leaner mixtures containing hard (low penetration asphalt.

Accelerated traffic used in the tests at Kelly and Vicksburg is probably more severe than will occur in actual service, the laboratory says. Nevertheless, asphaltic concrete is barred for the present on new construction of taxiways, runways and other areas where channelized traffic may be expected. In addition, all field offices of the Corps have been told to reduce the bitumen content of asphalt pavement in areas of channelized traffic for contracts now under way.

Vicksburg is going ahead with its effort to develop mixtures that will hold up under any number of accelerated load applications with allowance for tires of even higher pressure. The flexible Pavement Laboratory and the Asphalt Institute think it will be only a matter of time until the problem is solved.

Michigan Airport Will Cost $10.7 Million

Wayne County, Mich., will start next spring on a $10.7-million construction program at its airport.

The program—to be financed by federal and state aid as well as from county funds—is designed to help take the squeeze off air facilities now servicing the Detroit area. Non-scheduled airlines along with Pan American World Airways already are using the county airport. And American Airlines is scheduled to begin operations there in January 1958 when the terminal is expected to be completed.

Bids for the project will be awarded in three sections.

• On Nov. 20 bids will open on the air-freight building. Estimated cost of the 15,000-sq-ft structure is $321,000. Completion date has been set for October, 1957.

• Also on Nov. 20, bids will be opened on a cantilever type hangar. Estimated cost $2.1 million, the hangar will be 160 ft x 400 ft.

• The $5-million terminal building is still in the design stage. But bids are expected to be awarded sometime next spring so that the 173,000-sq-ft building can be completed by January 1958.

Architect for the new facilities—which will feature some of the latest ideas in airport design—is Giffels & Vallet, Inc., L. Rossetti. The terminal building will include 48 single rooms with baths for layover passengers, plus conference rooms and facilities for meals on the same floor; a nursery, lounge, and space for concessions; several dining facilities; a paved parking area for 3,000 autos and a 600-ft-long heated "finger" with spaces six aircraft.



A QUARTER CENTURY OF

A CATERPILLAR FIRST
—the "Hi-Electro" hardened cylinder liner

A CATERPILLAR FIRST
—the chemically conditioned cylinder liner

A CATERPILLAR FIRST
—the stainless-steel piston protector

A CATERPILLAR FIRST
—the steel-backed aluminum bearing

A quarter of a century ago, Caterpillar created mobile diesel power. For the first time, the power of the diesel engine was unleashed from its bulky foundations and put to work in the field—compact, economical. Here was diesel power of simple design, with no need for experts to operate and maintain. Here was diesel power with the lugging ability to knuckle down to the tough jobs.

The introduction of mobile diesel power was a tremendous advance in many fields. It provided efficient diesel power for tractors, motor graders, earthmoving equipment . . . for the work boat, the gin, the locomotive, the oil rig, the municipal plant . . . for *any* application in which steady, low-cost power is crucial. And everywhere, CAT* Diesel Engines proved themselves durable and dependable. They established Caterpillar as the leader in diesel engineering.

Today, hundreds of thousands of modern heavy-duty Cat Diesels are on the job in every corner of the world. And still the research continues. Study and experiment go ahead constantly in Caterpillar laboratories. Special testing machines help point the way toward new advances. Manufacturing techniques improve, too, in the world's largest diesel engine factory—where the quality of workmanship is the standard for the industry.

A modern world must have modern power—more and more of it. It is coming, in ever increasing quantity, from the production lines of Caterpillar, the leader.

Caterpillar Tractor Co., Peoria, Illinois, U. S. A.

CATERPILLAR*

*Caterpillar and Cat are Registered Trademarks of Caterpillar Tractor Co.

DIESEL POWER FOR PROGRESS



DIESEL LEADERSHIP

A CATERPILLAR FIRST
—interchangeable, adjustment-free fuel injection equipment

A CATERPILLAR FIRST
—the capsule-type injection valve

A CATERPILLAR FIRST
—the service meter

A CATERPILLAR FIRST
—superior lubricants (detergent oils)










about

CEN-VI-RO CONCRETE

The CEN-VI-RO, dry, zero slump mix is used to produce an extremely dense impervious concrete with even distribution of coarse aggregate and cement mortar during short spinning and curing cycles.

High quality concrete is one of several factors making it possible to state that . . .

"CEN-VI-RO PRODUCES THE WORLD'S FINEST CONCRETE PIPE"

The following data are presented as verification and are the result of actual documented tests made by independent laboratories on job-spun pipe.

Comparative Table

CONCRETE CHARACTERISTICS OF SPUN PIPE	CEN-VI-RO PROCESS	USUAL METHODS
Compressive Strength	8000-13,500 psi	3000-6500 psi
Modulus of Elasticity	7×10^6 psi	5×10^6 psi
Slump	ZERO	More than 1"
Water Cement Ratio	Less than 0.30	More than 0.35
Moisture Absorption	Less than 3%	More than 4%
Distribution of Aggregate	Uniform	Segregated
Slurry on Inside Wall	Trace	Up to ½"
Dimensional Stability	Good (Low w/c ratio)	.....
Molding of Bells and Spigots in Forms	True in Detail With Base Mix	Special Treatment required

Please Write Us
For The Name Of The
Nearest Cen-Vi-Ro Plant

CEN-VI-RO
PIPE CORPORATION
8610 Atlantic Blvd. South Gate, California



All-welded turbine scroll cases show promise for . . .

New Use of High-Strength Steel

Use of high-strength alloy steel in the fabrication of scroll cases at three current hydro projects marks a new application of a material that is relatively new in construction.

Developed three years ago by U. S. Steel Corp., "T-1" steel has been used in bridges, pressure vessels, dredge pipelines, and truck bodies. Early this year, the high-strength alloy was specified for four turbine casings at Idaho Power Company's Brownlee Dam on the Snake River. Then in rapid succession it was called for in scroll cases at Noxon Rapids Dam on Clark Fork in Montana and Swift Dam on the Lewis River in Washington.

Evidently, the agencies involved are satisfied that the higher cost of T-1, and special welding requirements are more than balanced by the greater thicknesses of the usual flange-quality carbon steel employed for turbine casings.

For comparison, T-1 has a minimum yield point of 90,000 psi, minimum elongation of 18% and an ASME working stress of 26,250 psi. Corresponding figures for A285 flange grade C steel are 30,000 psi, 28%, and 13,750 psi. Scroll-case plate thicknesses can be reduced by about 50% with the alloy steel, making the net material cost run about equal to flange-quality steel.

Because T-1 is a quenched and tempered steel, special welding techniques are required. Electrodes must match the qualities of the plate. Transition sections between other materials and T-1 are necessary to minimize stress concentrations. There must be a higher degree of forming than with normal carbon steel. And in the actual fabrication, the use of torch heating to assist fitting at joints and preheating is not permitted.

But because of its reduced thickness, the alloy steel saves considerable deposited weld material, which results in an overall welding saving, despite the special considerations required in using the new material.

Field welding under varied temperature conditions is practicable and stress relieving is not necessary. The Brownlee scroll casings, to have an inlet diameter of 18 ft, will be site welded and not stress relieved. On the other hand, the Swift casings, with their 11 ft diameters, will be shop-welded and stress-relieved.

In place, the tough alloy offers superior abrasion resistance.

The next application of high strength steel in the hydro field will probably be in penstocks. It is understood that designers of several projects are seriously considering this use.

S. Morgan Smith Co. is manufacturing the turbines and scroll casings for Brownlee and Swift powerhouses, while Allis-Chalmers Mfg. Co. is doing this work for the Noxon project.

T-1 steel is produced by the developer and the Lukens Steel Co., the latter company being more active in the hydro applications.

Overpass Is Made of Prefabricated Steel

Michigan's first prefabricated highway pedestrian overpass in Lansing, Mich., is a 10-ton, 81-foot low-cost steel structure recently erected over state highway M-78 just west of the Lansing city limits. It will permit pupils of the school there to cross the busy four-lane thoroughfare near two large industrial plants.

After the concrete footings were placed, it took a six-man crew of the Planet Corporation, which built the structure, to put the bridge in place.

Ronald Reed, Planet corporation engineer, said the cost of the steel overpass, stairways and footings was less than half that of a reinforced concrete overpass for the same roadway.

Strictly for school purposes, the overpass is protected by gates at either end and a 4-ft, 6-in. railing.

Clearance is a minimum of 14 ft 5 in. above the roadway. Students climb a gently inclining stairway from one highway shoulder, walk along a 5-ft-wide pathway and down another stairway into the school playground. An industrial-type deck provides safe footing under winter conditions.

Frank Groeneveld, president of the Planet Corporation, said the structure cost approximately $12,000.

Spotlight on the joint

Pipelayer tightens up two steel hoops securing neoprene gaskets and curved metal collar as . . .

Corrugated Metal Sewers Go In Along the

The first really large-scale use of corrugated metal pipe in interceptor sewer construction highlights the Middlesex County Sewerage Authority's $27-million clean-up of the lower end of New Jersey's Raritan River.

Over 37,000 ft of bituminous lined and coated metal pipe, ranging in diameter from 60 to 84 in., are being laid at a cost of $3.8 million. Metal pipe has not been used exclusively on the interceptor—switches to concrete pipe have been made, where high groundwater and questionable support conditions have been encountered, when corrugated metal pipe meeting specifications could not be obtained and when a contractor installed concrete after he had low-bidded on metal pipe.

The overall abatement plan, shown on the accompanying map, consists of 16.3 mi of corrugated metal and concrete interceptor, a 120-mgd pumping station, 3.6 mi of concrete force main, a 52-mgd (immediate capacity) chemical treatment plant and a 3.3-mi concrete and corrugated metal outfall, discharging into Raritan Bay. Construction began in September of last year and now stands about 45% complete; operation of the treatment plant is expected by October 1957.

• **Study pipe carefully**—Before allowing corrugated metal pipe as an alternate in the specifications, the consultants, Metcalf & Eddy of Boston (with E. Sherman Chase as partner in charge) and C. J. Kupper, engineer for the main trunk, examined the proposition critically. While not the first use of metal pipe for sanitary sewers (Middletown, Ohio—home of Armco Drainage & Metal Products Co. which supplied the Raritan job—has an extensive collecting system using corrugated pipe in diameters up to 108 in.), the Raritan Valley interceptor marks the first extensive use of large diameter corrugated-metal pipe under completely competitive conditions.

Corrugated pipe was allowed as an alternate on Contracts 9, 9A, 10 and 12. Bids for the first three contracts had unit prices for metal pipe of $75 to $85 per lin ft.

All four contracts were awarded on the basis of the lower—by an average $10 a ft—metal pipe prices. Metal pipe totaled $1.2 million less than concrete over 19.6 mi of interceptor and outfall. However, the construction picture wound up somewhat differently.

At the outset, the low bidder for metal pipe on Contract 10 asked and received permission to substitute concrete pipe at the lower metal pipe price. He was awarded the job on this basis.

• **Recent switches**—Then just recently, after Contract 9 in metal pipe was well along, the contractor on Contract 9A requested permission to change to concrete pipe, stating that he was unable to obtain 84-in. metal pipe to meet job specifications. The switch was approved by the engineers and MCSA, and concrete is being installed at the price originally bid for concrete pipe.

A revision was made on the outfall, too. Instead of using metal pipe throughout, Contract 12 has been changed to concrete pipe for the inland portion. The balance of the outfall, which will be installed in a dredged channel along the bottom of the bay, will go in as originally awarded.

The outfall change was requested by the contractor, who felt that concrete pipe might give a better job in the face of great depths of cover and high groundwater. But another factor made the switch necessary. The outfall was designed to reach its capacity by about 1995, but revised flow estimates indicate capacity will be reached in 1975. Faced with the prospect of the outfall

Raritan

But before work started

Middlesex County Sewerage Authority spent several stormy years beset by legal, financial and organizational difficulties.



Location of project and . . .

What it took to get started

1948	Middlesex County Planning Board receives report from Consultant Elson T. Killam suggesting formation of sewerage authority.
August, 1950	Middlesex County Sewerage Authority brought into existence.
April, 1951	Freeholders advance $60,000 interest free money for planning, which initially includes parts of upper Raritan Valley (Somerset County).
May, 1952	MCSA tells its consultants to refigure cost of project, excluding Somerset firms and others who failed to meet a May 1 deadline for signing up as participants. (ENR May 15, 1952, p. 22)
June, 1952	Unique public relations program begins to rally public support behind MCSA program—sentiment against non-participants runs high. (ENR June 5, 1952 p. 40)
October, 1952	Raritan Valley clean-up is split in two sections as Somerset County group is organized upstream. Governor Driscoll declares that no controversy will be allowed to delay the stop-pollution plans. (ENR Oct. 16, 1952 p. 26)
May, 1953	Middlesex still stymied for lack of 90% of potential backing—3 communities and one industry still out of the fold, but wavering. (ENR May 29, 1953 p. 26)
July, 1953	Downstream clean-up assured as MCSA gains required 90% support with New Brunswick signing. (ENR July 16, 1953 p. 27)
November, 1953	MCSA retains Metcalf & Eddy, Charles J. Kupper, Elson T. Killam and Bogert & Childs to prepare detailed plans—to be ready within 10 months. (ENR Nov. 19, 1953, p. 28)
September, 1955	Design stage finished, construction begins with letting of $18.7 million worth of contracts.
October, 1957	Plant expected to be in operation.

being outgrown, MCSA and its engineers had three alternatives:

- Plan future construction of a second gravity line using metal pipe, with the line parallel to its earlier counterpart.
- Build the outfall so that its initial capacity would be equal to ultimate needs, employing metal pipe of larger diameter.
- Employ concrete pipe on the outfall, adding about $70,000 to its cost. This could be a pressure line to take increased flows with the aid of pumps—installed in the future—at the treatment plant or could be paralleled with a second concrete pipe.

With limited 50-ft right-of-way, the first alternative was viewed as a dubious solution—installing a pair of large-diameter metal lines so close together would require extensive use of permanent steel sheeting and special backfill for proper side support. An alternate route for a second gravity line was not economically feasible.

The second possibility, larger diameter, was judged unsound on several counts. With no need for the increased capacity for almost twenty years, the capital cost and debt service which would be placed on the MCSA ledger 20 years before it was necessary would constitute an expensive insurance policy.

This and the uncertain availability

. . . Interest focuses on the pipelaying



CLOSE-UP OF JOINT shows neoprene gaskets, half of the curved metal collar and the stainless steel hoops. Joint can be made with one gasket; contractor played safe with two.

of metal pipe in sizes considerably larger than the original 84 in. led engineers to choose the third alternative—concrete pressure pipe for the landward portion of the outfall.

• **Pipelaying sequence**—Laying of the corrugated metal pipe is the most interesting aspect of the job. Twenty-foot lengths, elongated 5% in vertical diameter, are delivered with shape-maintaining guy wires at each end. In addition to a smooth inner lining that is a minimum .125 in. thick, the asbestos-bonded pipe has a uniform bituminous outer coating .05 in. thick, over which is applied white wash to prevent injurious softening effects of the sun's rays before the pipe is laid.

Metal brackets are riveted to the pipe lengths—one at each third point—so that sections can be handled easily by a sling suspended from a crane boom. A stone blanket is placed and checked for proper grade before the pipe goes into trenches where rock or unstable bottom is encountered.

However, material from most trenches has been judged good enough for backfill on most of the line. Field control has kept one of its many eyes on clay content. Where clay exceeds 30%, granular material has been brought in for support and backfill, in addition to the normal stone blanket.

In the laying, adjacent pipe ends are butt jointed, the joints are made and the guy wires are snipped. Each joint consists of a neoprene band, 6 in. wide and ⅜ in. thick covered with two halves of an asphalt-coated steel collar shaped to fit the corrugations in the pipe. The assembly is secured by a pair of high-strength stainless steel hoops. With the approval of the project engineer, the contractor elected to use two neoprene bands to provide a better seal.

To insure that any breaks in the pipe lining or loosened rivets near the lifting brackets caused by handling will not result in leakage, bracket points are recoated inside and out, with a bitumen compound. Where used, stone bedding is carried up to 60 deg below the horizontal axis of symmetry to insure firm support. Backfill is then placed by a clamshell bucket and tamped in 6-in. layers to the top of the pipe. Under this load the pipe becomes near circular.

• **Early laying troubles**—As would be expected on a pioneering job of this type, a number of bugs were encountered. The first sections of metal pipe that were laid were not oblated, or were near circular when they were backfilled. Several weeks later heavy rains saturated the ground and caused excessive deformation of several sections. The 5% elongation of the vertical diameter has eliminated any problem caused by imperfectly tamped backfill.

The contractor has experienced difficulties in jointing the corrugated metal pipe, this job being the first use of the gasket-collar-hoop joint. In many instances, after the contractor felt he had tightened the nuts on the steel hoops sufficiently, he has had to return and re-tighten. On other occasions the steel hoop has been sheared apart when tightening the nut. Initially, the contractor appeared to be spending an excessive amount of time in making this seven-piece joint (1 gasket, 2 half collars, 2 hoops, 2 nuts—eight pieces counting the extra gasket used on this job), but the contractor now has the time per joint down to about 30 minutes.

• **Tough concrete line**—On Contract 10 covering the South River interceptor, a concrete line, the pipelayers met some tough going. Where the line intersects the South River, a 200-ft inverted siphon was required. Digging a 16-ft wide path for sewer pipe isn't much of a job ordinarily, but along the mud bottom of a murky river, the task takes on a different aspect. Working with diving equipment and a dragline supported on a specially constructed trestle, the crossing was made without the use of diversion structures.

Ground and water conditions along this line were such that much of the trench had to be unwatered by a well-point system. And sudden changes of stratification among the silts, clays and shales encountered have made progress irregular in spots. The portions of this line receiving industrial wastes containing acids that adversely affect concrete are lined with a bituminous coating.

• **Big hole in dry**—The high watertable has been a thorn in the contractor's side at the Sayreville pumping station, meeting point of the two collection trunks. The structure, much of which will lie well below the level of the nearby river, required an excavation roughly 250 ft square and 43 ft deep. And it looks even bigger to the contractor, who keeps it in the dry with two lines of wellpoints around the entire perimeter.

The station, now 50% complete, contains considerable concrete which had to be placed at levels quite a bit below the most accessible delivery point for ready mix trucks. To do the job, 80 ft of 12-in. steel pipe was slung from a crane boom and used as a delivery chute. The mix, with slump ranging from 3 to 4 in., showed little separation in its trip down a 1 on 2 slope. Tests indicated an average 28-day compressive strength of 4,000 psi, some cylinders testing as high as 7,000 psi. Biggest day's pour so far was 390 cu yd.

To provide the 120-mgd ultimate design capacity of the station, 4 non-clog centrifugal pumps will be installed, each capable of 35 mgd. The pumps, whose full capacity is not expected to be needed for some time, will push the entire district's flow through a con-

$8,269.02 (Hartford File #HM53-2037)

$850.67 (Hartford File #61474)

$4,000.00 (Hartford File #18217)

Many contractors are protected against equipment losses like these... *are you?*

No matter how well your men know their jobs ... no matter how rugged your machines are ... your major financial investment in equipment demands adequate insurance against loss.

That's why you need the protection offered by a Hartford Contractors' Equipment policy. This insurance is available for all of your equipment. It protects it against loss by fire, theft, explosion, landslide, overturn, collision, windstorm and other specific hazards. Covers them on the job ... in transit ... in storage.

And with Hartford protection, you know that in case of accident help will be there fast! For we're set up to save you costly delays ... to work with you to get equipment back on the job in short order ... to pay your claim promptly.

Make sure *you'll* have this satisfying protection and service when you need it. *The first step?* Write for more information ... and a copy of our useful booklet, *Your Machinery and its Actual Cash Value.* Better yet, call your Hartford Group Fire Insurance Agent or your insurance broker!

Year in and year out
you'll do well with the

Hartford

Hartford Fire Insurance Company Group
Hartford Fire Insurance Company
Hartford Accident and Indemnity Company
Hartford Live Stock Insurance Company
Citizens Insurance Company of New Jersey ...
Hartford 15, Connecticut
New York Underwriters Insurance Company ...
New York 38, New York
Northwestern Fire & Marine Insurance Company
Twin City Fire Insurance Company ...
Minneapolis 2, Minnesota

MAIL THIS COUPON — TODAY

HARTFORD Fire Insurance Company Group
Hartford 15, Conn.

Please send me more information about the advantages of a Hartford Contractors' Equipment Policy. Also include a free copy of *Your Equipment and its Actual Cash Value.*

Name_____

Firm_____

Street_____

City_____ Zone_____ State_____

YEOMANS

1999-1 N. Ruby St., Melrose Park, Ill.

Please send literature checked below:

☐ catalog 3007
☐ manual 1114
☐ manual 2000

name _____

company _____

street _____

city _____ zone ____ state ____

Mr. Specification Writer:

Use this coupon..for free literature on sump pumps and sewage ejectors

Catalog 3007.. describes Yeomans Heavy-Duty Wet Pit Pumps for drainage, flood water, effluent boiler blowoff, hot wells, alkalis, and acids, etc.

Manual 1114.. describes sewage ejectors, bilge pumps, and "Drain-Dri" sump pumps. Includes fixture rating table, fixture capacity estimating curve, and water friction table.

Handbook for care of centrifugal pumps (Manual 2000)..applies to pumps of *all* makes..tells how to diagnose pump ills.. suggests maintenance timetable.

YEOMANS

. . manufacturers of: centrifugal pumps . pneumatic sewage ejectors . distributors . clarifiers . mechanical aerators . digesters.

. . . Water and mud make problems

CONCRETE PIPE sections of job run through some difficult country. Here well-points are used to dry trench. Parts of concrete force main are supported on pile bents in turn protected from shifting mud strata by steel sheet piling.

crete force main to the treatment plant 3.6 mi downstream.

• **Mud causes extras**—The 72 in. force main is the source of many of the current construction headaches. Mud strata extend in from Raritan River and underlie a layer of sandy loam. In many cases, the layer of unstable material extends down 30 or 40 ft, making excavation and backfill with stone prohibitive in cost.

While the job was set up on a lineal foot basis, unit prices for necessary excavation greater than 1 ft below grade, for steel sheetpiling, and for stone bedding greater than 1 ft in depth were included as separate items. The unit price for additional trench excavation with stone backfill was $8 per cu yd. Creosoted timber piles for pipe support were priced at $5 per lineal ft. Since the depth of unsuitable material determined the economic choice between pile support and stone backfill accurate determination of the limits of poor material was important.

Toward this end, E. T. Killam's resident engineer, Peter Homack, had borings taken at 50-ft intervals along doubtful stretches. Original explorations, taken at much greater spacing, did not give sufficient information.

On most sections of the force main, a 1-ft stone blanket—extending one-quarter of the pipe diameter on each side of the trench—provides ample support for 16-ft lengths of concrete pipe.

• **Chemical treatment**—Treatment plant construction is on schedule and according to Sol Seid, MCSA's chief engineer, the plant should be in operation by October, 1957. When the $4 million plant starts up it is expected to utilize nearly all of its initial design capacity—52 mgd of average daily flow. Future expansion, in the form of two additional clarifiers, will boost the capacity to 78 mgd. Hydraulic capacity of both plant and sewers is 115 mgd.

Chemical treatment, sometimes called intermediate treatment, will be employed for the composite industrial and domestic flows of the district. Grit chambers, a pair of 35 by 35-ft detritus-type units, are designed for removal of particles down to No. 50 mesh at peak flow of 117 mgd. Next unit, the distribution chamber, has a surface area of 330 sq ft and is 18 ft deep, providing a detention of 1¼ min at average flow.

Combination flocculation sedimentation tanks—4 of them—are the key units in the process. The inner 55-ft, the flocculation compartment, is 10 ft 3 in. deep, provides 20-min average flow detention. Effluent passes to an annular sedimentation compartment surrounding the floc chamber, 12 ft 6 in. deep and providing 2.1 hr detention. Weir

faster form removal

with

DEHYDRATINE 80

or your money back

You can remove forms faster with Dehydratine 80 because it accelerates both the initial and final set. Here's why:

- Early strength is greater—liquid Dehydratine 80 mixed with cement can increase the 1 day strength by 300%, saves time at low temperatures—requires shorter protection period, permits quicker finishing, cuts delays between operations. Furthermore, Dehydratine 80:
- Provides water repellency through increased density.
- Increases the workability of concrete and masonry mortar.
- Reduces shrinkage, particularly at the start.
- Makes a harder, non-dusting surface.
- Improves curing.

You owe it to yourself to take advantage of this money back guarantee today!

We'll send you a five gallon pail of Dehydratine 80 FREE with every fifty-five gallon drum ordered from your Building Supply Dealer or direct from one of our conveniently located warehouses. Try the five gallon pail and if you are not completely satisfied that it meets *all our claims* when used as directed, return the drum freight collect and we'll completely refund your money.

Subsidiary of Sun Chemical Corporation

A. C. Horn Co., Inc.

DIVISIONS OF SUN CHEMICAL CORPORATION

HORN (paints, maintenance and construction materials, industrial coatings) • WARWICK (textile and industrial chemicals) • WARWICK WAX (refiners of specialty waxes) • RUTHERFORD (lithographic equipment) • SUN SUPPLY (lithographic supplies) • GENERAL PRINTING INK (Sigmund Ullman • Fuchs & Lang • Eagle • American • Kelly • Chemical Color & Supply Inks) • MORRILL (news inks) • ELECTRO TECHNICAL PRODUCTS (coatings and plastics) • PIGMENTS DIVISION (pigments for paints, plastics, printing inks of all kinds) • OVERSEAS DIVISION (export) • A. C. HORN COMPANY, LIMITED (Canada) • GENERAL PRINTING INK CORPORATION OF CANADA, LIMITED • FUCHS & LANG de MEXICO, S.A. de C.V.

—MAIL THIS COUPON—

A. C. Horn Co., Inc., Dept. H29-119
10th Street and 44th Avenue
Long Island City 1, N. Y.

☐ Please send me _____ 55 gallon drums Dehydratine 80 and _____ free 5 gallon pails.
☐ Please send 8 page descriptive technical bulletin.
☐ I want to see a salesman.

Name _____

Title _____

Company _____

Street _____ City _____

State _____

. . . Outfall to be laid like cable

PLANT OUTFALL will run through this big cut (for plant access road), beneath Garden State Parkway and into Raritan Bay just beyond.

takeoff rate is 31,800 gpd per lineal ft of weir at average flow, increasing to 71,500 at 117 mgd peak flow. Outside diameter of the combination units is 130 ft.

• **Good neighbor policy**—Inflow to the plant, containing a high percentage of industrial wastes, will have a suspended solids content of 450 ppm and a 5-day BOD of 487. These conditions led Metcalf & Eddy to the use of chlorinated copperas and lime in the chemical process. The ferric hydroxide floc formed gave good results in laboratory studies—suspended solids removal equaled secondary treatment caliber and BOD reduction was of better-than-primary order. Dosage, both of lime and copperas, is 100 ppm in aqueous solution. Copperas, though normally too expensive for such use, is readily available from the plant's next door neighbor, National Lead Co.

The plant design also provides for prechlorination before grit removal and postchlorination at the outfall. Under peak flow, effluent will require 62 min to traverse this line.

Sludge will be handled in a pair of 80-ft-dia thickeners 16 ft deep, and 4 sludge storage tanks of the same diameter and 19 ft deep, giving a storage capacity of 11 days at average flow. Undigested sludge will be barged 25 mi out to sea.

A neat bit of doubling-up was accomplished in the lay-out of roads into the plant. Faced with a sizable excavation necessary to obtain reasonable access grades, engineers saw a chance to make double use of the cut by running the outfall close to the edge of the road.

• **Big show at outfall**—Dredging operations have been completed on the outfall's off-shore portion. Laying of the submerged part of the outfall will soon be under way. The contractor plans to join the 20-ft sections of metal pipe at the surface on a barge and pay them off as they are assembled. Outriggers will support the pipe between the barge and bed except for about 80 ft nearest the bed.

One construction difficulty to be overcome on the landward part of the outfall is that of tunneling under the Garden State Parkway. Having considered several possible methods, the contractor has decided to drive an air tunnel through the 50-ft high parkway embankment.

• **Knocking at the gate**—On the administrative side, MCSA director Chester A. Lydecker is busy settling the matter of new participants. A would-be complicated problem was settled in a very simple manner. Recognizing that the authority is chargeable by statute with preventing pollution of the waters within its boundaries and that greater plant volume will result in lower unit cost of treatment, the authority on June 19 decided to accept new participants within the district, on the same basis as original MCSA signers participate on.

There are two conditions which new members must meet. First, the sewage must meet the approval of the authority as far as pH and other characteristics are concerned. Further, the new participants must make the connection to existing collection facilities. These qualifications do not seem to pose any serious obstacles—MCSA now has eight interested groups seeking to join its clean-up scheme.

With the opening of the Raritan plant, the long, long tale of a valley's clean-up will be half finished, pending action of the upstream Somerset-Raritan Valley Sewer Authority. The future for a clean Raritan looks bright, as Director Lydecker, expressing the newly formed policy on latecomers, voiced the authority's intentions: "We'll take all we can get, clean up from Bound Brook (upper limit of MCSA activity) down, and then press hard to have up-river pollution stopped."

A. A. Thomas is resident engineer for Metcalf & Eddy which in addition to its own contracts has responsibility for design approval and coordination of construction of the entire project. Other residents are Peter Homack, Howard Patton and R. Von Wagner for Elson T. Killam, C. J. Kupper and Bogert-Childs, respectively.

Job Breakdown by Contract

Contract	Contract Price	Contractor	Engineer
9—Main Trunk Sewer	$2,264,000	Berlanti Const. Co.	C. J. Kupper
9A—Main Trunk Sewer	4,176,308	Verona Const. Co., Inc.	C. J. Kupper
10—South River Intereceptor	1,677,251	Elmhurst Cont. Co. & Charles E. Vacheris, Inc.	Bogert-Childs Assoc.
11—Force Main	1,729,030	Verona Const. Co., Inc.	Elson T. Killam
12—Outfall	3,468,000	J. Rich Steers, Inc.	Metcalf & Eddy
14—Pumping Station (General)	597,170	Wallace J. Wilck, Inc.	Bogert-Childs
14B—Pumping Station (Plumbing)	422,237	Charles Simkin & Sons	Bogert-Childs
14D—Pumping Station (Electrical)	102,281	Ernest Jarvis & Co.	Bogert-Childs
15—Treatment Plant (General)	1,999,912	Thompson-Starrett Co., Inc.	Metcalf & Eddy
15A—Treatment Plant (Structural Steel)	470,711	Olliver Iron Works	Metcalf & Eddy
15B—Treatment Plant (Plumbing, pumps etc.)	1,290,118	Municipal Service Co.	Metcalf & Eddy
15D—Treatment Plant (Electrical)	355,310	Standard Electric Const. Co.	Metcalf & Eddy



K&M Corrugated Asbestos Sheets, used as siding on the Operations Center of a southeastern utility company, complement the clean, modern lines of the building. These sheets are also used on a pitched roof, not shown in the photograph. Engineering and supervision of construction: Stone and Webster Engineering Corporation. Applicator: Whatley Roofing and Sheet Metal Works, Tampa, Florida.

Attractive, weather-proof, fire-proof, maintenance-free

K&M Corrugated Asbestos

Building a new plant? Modernizing your present one? In either case, you'll gain important cost and other advantages with K&M Corrugated Asbestos-Cement Sheets. They cannot burn, can't rot or corrode—withstand the ravages of time and weather year after year. Because K&M Corrugated Asbestos-Cement Sheets rarely require maintenance, *never* need protective painting, their upkeep is held to the barest minimum.

Easy to apply. These corrugated sheets offer big savings in application costs. They go on quickly, are easily sawed, drilled, and fitted on the job.

Write for complete details on K&M Corrugated Asbestos Roofing and Siding.

KEASBEY & MATTISON
COMPANY • AMBLER • PENNSYLVANIA

K&M best in asbestos

Jacksonville Branch of Federal Reserve Bank of Atlanta is typical example of top-notch work consistently turned out by The George D. Auchter Company. By pre-planning all jobs for safety, this contractor assures completion of work on time . . . helps bring in more "repeat business."

HOW SAFETY SAVES MONEY FOR FLORIDA'S THE GEORGE



St. Vincent's Hospital Nurses Home, Jacksonville, Florida, is another construction job on which constant safety supervision by The George D. Auchter Company kept accidents to a minimum . . . profits to a maximum. Contractor's enviable safety record permits substantial savings on insurance premiums . . . lower competitive bidding!



Duval County Court House, Jacksonville, Florida. Close cooperation between The George D. Auchter management and American Mutual Safety Engineers helped protect employees and public alike . . . assured getting the job done on schedule.

. KEEPS DISPOSITIONS SUNNY

D. AUCHTER COMPANY

BY MR. FRIENDLY

Close cooperation with American Mutual Safety Engineers for the past 20 years has cut accidents... upped profits for this top Jacksonville contractor!

One sure way to make accidents take a vacation—boost employee morale and savings, too—is to work hand in hand with American Mutual safety experts. And The George D. Auchter Company, of Jacksonville, Florida, has been doing just that for the past 20 years!

Specializing in the construction of office buildings, power plants, paper mills, hospitals, churches, markets and other commercial structures, and also bridges and marine construction, this leading contracting firm realizes that safety first is safety best—and keeps American Mutual's accident-prevention "know-how" on the job at all times. As a result, The George D. Auchter Company is able to save on lower insurance premiums and hold bids down for a greater competitive advantage.

If you're interested in a service that can help *you* save lives, limbs and dollars, too, write: American Mutual Liability Insurance Company, Dept. EN-4, 142 Berkeley Street, Boston 16, Massachusetts.

AMERICAN MUTUAL

Service from 76 fully staffed offices!
Savings opportunity from substantial dividends!

Equipment met a tough job in placing . . .

Abrasive Rock, Asphalt Facing for Wate

When Colorado Springs, Colo., launched its $18-million water expansion program two years ago, it resulted in the building of a dam (Montgomery Dam) incorporating several unique features of design and construction.

For one thing, its spillway crest—at El. 10,861 ft above sea level—is believed to be at a higher elevation than any other dam in this country. Designs called for a waterproof asphaltic concrete membrane on the upstream face. This, in turn, required special construction methods in screening and placing rock in the main embankment. The fact that the available stone was extremely abrasive added to the contractors' problems.

• **Scope of program**—Basically, the need for the water expansion program resulted from increased domestic demand stemming from a 50% rise in Colorado Springs' population within the past ten years. With the capacity of the existing Pike's Peak supply exceeded, the city was forced to undertake an $18-million expansion program to develop additional water supply 75 miles away on the western slope of the Continental Divide.

The project includes diversion dams, collecting pipelines and tunnels to bring the water to the Hoosier Tunnel piercing the Divide, a storage reservoir on the eastern slope below the tunnel in the watershed of the North Platte River, and a 30-in. steel pipeline to carry the water to the city.

Flow will be at the rate of 11 mgd to 12 mgd, although the line is designed for a maximum flow of 18 mgd.

• **Key unit**—Montgomery Dam, the key unit in the project, will form a storage reservoir below Hoosier Tunnel. It is a rock-fill structure 113 ft high at the stream channel. The reservoir is comparatively small. It will have an initial storage capacity of 5,100 acre-ft, with provisions for increasing it later to provide storage for a total of 10,000 acre-ft.

The dam is located on the middle Fork of the South Platte River about ten miles northwest of Fairplay, Colo. Its crest will carry a 20-ft roadway. The slopes of the upstream and downstream faces of the embankment are 1.7 on 1 and 1.5 on 1, respectively.



MONTGOMERY DAM on the western slope of the Rockies 2 miles above sea level is the key unit in Colorado Springs' $18-million water expansion program.



UPSTREAM FACE of dam will have a 12-in. thick blanket of asphaltic concrete to be applied on Zone II material during next year's construction season.



DAMMING the Middle Fork of South Platte River at crest elevation 10,861 ft above sea level, Montgomery Dam will store 5,100-acre ft of additional water for Colorado Springs.

Supply Dam

The structure contains a total of 654,000 cu yd of rock. It is 400 ft wide at the base and has a crest length of about 1,900 ft.

• **Tough granite**—Construction problems of first were indicated as mere quarrying and placing of the rock. But the granite encountered was extremely abrasive and contained more fines than anticipated, necessitating some middle-of-the-project re-engineering.

Because the dam will have an asphaltic concrete membrane facing on its upstream slope, it required a support base which can provide maximum drainage. Consequently, the main portion of the rock-fill embankment (Zone I) was required to be relatively free of sand, dirt or other fines which might

SHORT HAUL but a rugged one put rock trucks to a tough test as they are loaded with granite and quartzite boulders by a feeder-scalper which removes the fine material from the quarried rock by a wobbling action.



HOW THE WOBBLER WORKS: Its elliptical shaped bars, mounted alternately vertical and horizontal, have chain sprockets at

retain water and cause winter rupturing of the membrane facing.

The amount of fines in Zone I of the rock-fill embankment (see drawing) was limited to not more than 10%, while no fines less than 3 in. in size were permitted in Zone II. A special screen was used to remove the fines from the quarried material. These fines were then classified and material from ¾- to 3-in. in size was used to provide a layer, 9- to 12-in. thick, which serves as a base for the asphaltic concrete, waterproof blanket on the upstream face of the main embankment.

• **Rough equipment wear**—The problem of equipment wear was met through stepped-up maintenance. Shovel teeth were good for only two shifts—20 hours. Grousers of the track-type tractors on the job were at an accelerated rate, and tire wear on the big off-the-road rock trucks was rapid.

About one half of the quarried rock was clean enough to be placed directly in the embankment. The remainder, however, had to be processed to remove the excess fines.

The problem of separating the fines was whipped through installation of a so-called "Wobbler" screen. This combination feeder-scalper was developed by Universal Engineering Corp., primarily for heavy duty taconite mining on the Mesabi Range in Minnesota. On Montgomery Dam is was a contract-saver for the contractor.

Without the wobbler the job would have been much more complicated, according to Ken Willis, job superintendent: "It cut to one-sixth the time we might ordinarily require to complete our rock fill with specified rock."

Originally the contractor had planned to use a rotating cylinder called a trommell screen to sift out the fines for Zone II aggregate. But when he ran into a situation where 70% of the material had to be run through the trommell, the machine was incapable of carrying the load.

But the wobbler handled tremendous chunks—its special manganese steel construction permitting continuous operation. Its oval-shaped rollers fed tonnage at a steady rate, screening rejects (which went to the dam) and fines over a ¾ in. screen and washer. There was little clogging.

ROCK FILL in Zone I of the main embankment was washed free of clay pockets by hydraulic jets delivering water at 1,500 gpm under a pressure of 75 psi.

• **How it works**—This is the way the wobbler screen works: A set of bars in the bottom of a hopper gives a rocking, tumbling motion to the quarry material dumped on them. The bars are elliptical in cross-section and set alternately vertical and horizontal. They maintain the same relative positions as they turn. The effect is a thorough churning that separates the fines which fall through the bars and are carried away on an endless belt conveyor. The oversize feeds to the end of the unit and is chuted into trucks and carried to the dam.

Material carried away on the belt by the separating action of the machine is carried to a shaker screen which sifts it through ¾-in. slots. About 30% of the rock handled by this feeder is fine material. About half the fines are sal-


1. Alternate vertical and horizontal bed bars in this position permit some of fines to drop through by gravity
2. As bars turn big rocks are wobbled forward shaking more fines loose to drop on a conveyor belt below
3. Continued rotation of bars keeps big rocks moving to point of discharge

either end, which are turned in the feeding direction through a gear box connected to an electric motor. The log chain (left view) looped around the bars keep long, thin rocks from dropping through.

vaged as ¾ in. material for use in the rock-fill, so the total waste from the quarry was only about 7½%. During a peak 20-hr day the wobbler handled an average of 250 cu yd or nearly 500 tons of rock and fines per hour.

• **Hydraulic sluices**—All material placed on the dam was high-pressure sluiced with two hydraulic monitors carrying a nozzle pressure of 75 psi, at the rate of 1,500 gpm. Water for the guns was brought by gravity flow through a 16-in. pipeline from the Platte River channel.

The rock was hauled from the quarry just upstream from the dam in 5- and 6-cu yd trucks. It was dumped in lifts up to 30 ft in height. The hydraulic jets, playing on the active face of the fill as the rock was placed, prevented pockets of fines from forming supporting pads between the larger rock. After the ¾- to 3-in. blanket of material was placed on the upstream face, it was smoothed by a shovel and then with a heavy steel drag. It was compacted by a vibratory roller, operated on a cable from a dragline working along on the crest of the dam.

Depth of the rock quarry was 200 ft at completion. About 900,000 cu yd of dirt and rock was moved to get the 730,000 cu yd of usable material required for the dam.

During good working weather the contractor employed a crew of 140 men on the job, working two shifts per day 6 days per week.

• **Grout curtain needed**—The dam is located on igneous and metamorphic rocks containing numerous seams and fissures. A grout curtain was developed along the heel of the dam under a concrete cut-off wall that extends 8 ft into solid rock.

The deeper holes for the grouting operations extended 150 ft into the foundation material throughout the major portion of the dam. Other holes at lesser depth, with a minimum of 50 ft, completed the drilling pattern.

In general, the holes are 8 ft apart, but in some cases the spacing is limited to 4 ft. Grouting pressures of 200 psi were used in the deeper sections, and 35 to 50 psi—or as high as practicable—directly below the cut-off wall. Grouting operations required more than 25,000 sacks of cement.

The waterproof asphaltic concrete facing on the upstream face will be placed next summer. It will require 26,500 sq yd of material 12 in. thick. The aggregate can be obtained from glacier deposits in the vicinity of the dam.

Fisher Contracting Co., Phoenix, Ariz., was the contractor on the rock-fill embankment and allied work. The total cost of this work was $2,260,000, and the estimated cost of the asphaltic concrete facing is $350,000. Fisher's contract was started in August 1954 and completed in late September this year.

Engineering and supervision work, in connection with the development of the supply on the western slope and Hoosier Tunnel, was done by the Department of Public Utilities of Colorado Springs. R. D. Nixon is general manager of the department and J. S. Nichols, superintendent of the Water Division. Black & Veatch, consulting engineers, Kansas City, Mo., were the engineers for the design and construction of Montgomery Dam and the 30-in. pipeline to the city. D. B. Gould, then with Colorado College, was employed by Blank & Veatch as consulting geologist, and F. W. Scheidenhelm, consulting engineer, New York City, as consultant on the design of the dam.

UPSTREAM FACE of rock fill dam has 10-ft layer of Zone II material placed by dragline, smoothed by heavy steel drag and compacted to serve as base for asphalt layer.

Consulting Engineer:
Howard, Needles,
Tammen & Bergendoff

Contractor:
Union Construction Company

Construction crew is assembling an Armco Bin-Type Retaining Wall for the new Kansas City Expressway. Face of wall totals 73,247 square feet.

A MILE OF ARMCO BIN-WALL

is used on Kansas City Expressway

Exactly 5,230 lineal feet of Armco Bin-Type Retaining Wall is being used for a single installation on the Kansas City Expressway to gain maximum elevated roadway width without encroaching on the adjacent railroad right-of-way. Eleven different wall heights were required, ranging from 5⅓ feet to 18⅔ feet.

Where Are Armco Walls Used?

With the new and wider highways of today, engineers are continually faced with the problem of making full use of right-of-ways without encroaching on adjacent property. To do this, it is often necessary to hold back fills or stabilize steep embankments. Armco Bin-Walls are ideal for such jobs.

Why Are Armco Walls Better?

Armco Bin-Walls are of all-metal cellular construction, tightly bolted together to make an integral unit. Earth is backfilled into the bins to provide the necessary strength and stability. Dangers of cracking, breaking, bulging or overturning are minimized. Assembly is easy and fast.

For more data on sizes, engineering details and standard designs of Armco Retaining Walls, write us. Armco Drainage & Metal Products, Inc., 4716 Curtis Street, Middletown, Ohio. Subsidiary of Armco Steel Corporation. In Canada: write Guelph, Ontario. Export: The Armco International Corporation.

ARMCO BIN-TYPE RETAINING WALLS

ARMCO

New Products



Twin-Shaft Finishing Machine Trowels Wide Concrete Area

One pass with the Whiteman "Twin" floating-finishing machine trowels a concrete area 5 ft wide. Two sets of trowels rotate in opposite directions side by side, each balancing the torque generated by the other. This makes for smooth easy operation, according to the manufacturer.

Equipped with combination trowels for either floating or finishing, the machine has a knob at the top of the handle for changing trowel pitch. WHITEMAN MFG. CO., 13020 PIERCE ST., PACOIMA, CALIF.

Vinyl Window Won't Burn, Shatter or Corrode

Seiberling Rubber is now marketing a plastic window claimed to be shatterproof and nonflammable. It is a polyvinyl chloride, made in clear and colored panes. Tradename of the product is Seilon. According to Seiberling, oil, grease, corrosive fumes and most acids do not affect the material. It is described also as self-extinguishing.

The manufacturer says Seilon can be machined, planed, sawed, nailed, cemented and welded—features expected eventually to sell the product in the do-



Direct-Drive Pump for Tractor-Mounted Ripper

Constant hydraulic control pressure is the package sold for a new direct-drive pump for the American's tractor-mounted rock ripper, now available for Caterpillar D-9 trailers.

Mounted at the engine power take-off, just ahead of the clutch and transmission assembly, it receives constant power while the engine is running. Hydraulic pressure is thus maintained without interruptions due to clutch action or to speed reduction through the torque converter. Use of flexible high-pressure piping eliminates joint leakage due to vibration, and permits easy access for tractor clutch readjustment without disassembly. The ATECO direct-drive pump is offered as optional equipment on all new HR-D9 rock rippers, and will be available in kit form for conversion of units now in use. American Tractor Equipment Corp., 9131 San Leandro Blvd., Oakland 3, Calif.

WHY
Kensington track
LASTS SO LONG

There are two reasons why these tracks give you longer service, even under severest working conditions: (1) KENSINGTON's new, improved design, and (2) superior, wear-resisting alloyed manganese steel.

New Design. Rigidity and near-perfect alignment are made possible by one-piece rail design and special heat-treated alloy pins pressed tightly in place under high pressure. Anti-shear lugs on grouser plate fit snugly over tie bar of link to eliminate loose plates, elongated bolt holes, twisting, weaving, and side-sway . . . the most common causes of bolt loosening and track trouble. Grousers are heavied-up at all critical points to better resist bending and breaking.

Yet, despite all these improvements, KENSINGTON *Track Assemblies fit all standard, popular make crawler tractors.*

Steel with Stamina. Special, hard, tough, KENSINGTON-developed alloyed manganese steels actually fight back against wear! They constantly develop extra surface hardness when exposed to friction, abrasion, and impact.

KENSINGTON tracks come from the factory ready-assembled, easy to install.

Discover for yourself how much KENSINGTON tracks will lower your maintenance costs and improve your operating efficiency. Coupon will bring details.

Kensington
STEEL COMPANY
SUBSIDIARY OF POOR & CO., CHICAGO

KENSINGTON STEEL CO.
Dept. E, 505 Kensington Ave., Chicago 28, Ill.
● Please send information on crawler tracks for tractor described below. I understand I will be under no obligation.

Make of tractor_____
Model_____ No. links per belt_____
Width of grouser_____
NAME_____
COMPANY_____
ADDRESS_____
CITY_____ ZONE_____
STATE_____



THE PERMANENT ANSWER TO AN OBJECTIONABLE DRAINAGE PROBLEM:

Manufacturers of Toncan Drainage Products

BARK RIVER CULVERT & EQUIPMENT CO.
Escanaba, Mich. • Ironwood, Mich.

BEALL PIPE & TANK CORPORATION
Portland, Ore. • Boise, Idaho

BERGER METAL CULVERT CO., INC.
Westminster Station, Vermont

BLUEGRASS PIPE & CULVERT CO.
Louisville, Kentucky

THE BOARDMAN CO.
Oklahoma City, Okla. • Tulsa, Okla.

CENTRAL CULVERT CORPORATION
Alexandria, La.

CHOCTAW, INC.
Memphis, Tenn. • Birmingham, Ala.

DOMINION CULVERT & METAL CORP.
Roanoke, Va.

EATON METAL PRODUCTS CORP.
Omaha, Neb. • Hutchinson, Kan.

EATON METAL PRODUCTS COMPANY
Billings, Mont.

EMPIRE STATE CULVERT CORP.
Groton, N. Y.

ILLINOIS CORRUGATED CULVERT CO.
Peoria, Ill.

JENSEN BRIDGE & SUPPLY COMPANY
Sandusky, Mich.

H. V. JOHNSTON CULVERT CO.
Minneapolis, Minn.

LOGANSPORT METAL CULVERT CO.
Logansport, Ind.

M & M HIWAY MATERIALS CO.
Columbia, Mo.

NORTH DAKOTA METAL CULVERT CO.
Fargo, N. D.

PACIFIC CORRUGATED CULVERT CO.
Temple City, Calif.

THE PEDLAR PEOPLE, LTD.
Oshawa, Ont.

REPUBLIC STEEL CORPORATION
Culvert Division
Canton, Ohio • Harrisburg, Pa.

SPOKANE CULVERT & FABRICATING CO.
Spokane, Wash.

THOMPSON PIPE & STEEL COMPANY
Denver, Colo.

TRI-STATE CULVERT & MFG. CO.
Tampa, Fla. • Decatur, Ga.

UTAH CULVERT COMPANY
Ogden, Utah

WISCONSIN CULVERT COMPANY
Madison, Wis.

WYATT METAL & BOILER WORKS
Dallas, Tex. • Houston, Tex.

REPUBLIC

REPUBLIC STEEL

World's Widest Range of Standard Steels

REPUBLIC SECTIONAL PLATE ARCH

When Big Creek in western Cleveland became contaminated and objectionable due to community expansion, protection of both health and property value demanded its permanent enclosure. In addition, the drainage structure needed would be called on to handle occasional heavy run-offs but could not exceed practical headroom limits.

To meet all requirements, twin Toncan® Iron Sectional Plate Arches with vitrified pavements were selected. Each provided a 12-foot, 6-inch span with only a 6-foot, 5½-inch rise. Each was 1677 feet long.

Of particular interest in the Big Creek enclosure was the use of salvaged Republic Sectional Plates. While the first 927 feet of each structure used new 8-gage plates, the remaining 750 feet were constructed of 900 3-gage plates, removed when an earlier job was enlarged. *These Toncan Iron Sectional Plates, which had been in underground service for 19 years, were still in excellent condition.* Speaking of the entire job, the erection superintendent said, "The fabrication was perfect."

Republic, and the drainage products manufacturers listed on the opposite page, offer a complete line of drainage products designed to give long-lasting service under all conditions. Resilient and flexible, they won't crack, crumble or spall . . . and are unaffected by impact, vibration or shifting fill. Various types include Corrugated Metal Pipe, Perforated Corrugated Metal Pipe, Sectional Plate Pipe, Corrugated Metal Pipe Arch, Sectional Plate Pipe Arch and Sectional Plate Arch . . . available in Toncan Iron and Republic Copper Steel.

Contact the Drainage Products Manufacturer nearest you for complete information. Or mail the coupon.



ECONOMY AND DURABILITY are key features of this Corrugated Metal Pipe Arch bridge which allows street to cross drainage arroyo—serving a large area. By using three parallel pipe arches, each with a 72-inch span and 44-inch rise, the city was able to handle the necessary volume within very low headroom. Cost was a fraction of that required for a steel and concrete structure.

FOR MAXIMUM SERVICE in heavy-duty handling operations, like the railroad car repair shop use shown here, insist on Republic Chain Products. As a basic steel producer, Republic controls quality from ore to finished product, assuring long-term dependability. Whatever your problem; hauling, hoisting, holding or towing, your Republic Chain Distributor can furnish the chain and accessories required.

LONG-LASTING, TROUBLE-FREE performance is yours when you use Republic Flexible Plastic Pipe to bring in construction water . . . or drain flooded excavations. Made of tough polyethylene, it resists abrasion and the effects of acids and alkalies. In addition, it is immune to electrolytic action. Lightweight and easy to cut or join, it can be used on job after job. For literature, mail coupon.

STEEL

and Steel Products

REPUBLIC STEEL CORPORATION
Dept. C-1329
3114 East 45th Street
Cleveland 27, Ohio

Please send me further information on:

☐ Republic Drainage Products
☐ Chain Products ☐ Republic Plastic Pipe

Name _____ Title _____

Company _____

Address _____

City _____ Zone _____ State _____

Don't stunt your business growth

Build with Butler —the building that is easy to expand



Business expansion can be expensive—if it's not planned for. But when you choose a Butler building, you get "built-in" provision for expansion . . . fast . . . in any direction . . . usually at lower cost than initial construction.



Butler all-bolted construction cures growing pains. You unbolt the end or sidewall, move it out, intact, as far as you need, add the necessary structurals and tight-fitting cover panels, and bolt the wall back on.



Neat . . . fast . . . no strain . . . no waste. A minimum of new materials required. Need more space later? Do it again. There's no limit. It's just one of the reasons why Butler is your best building buy. Your Butler Builder can give you many others.

Consult the yellow pages of your telephone directory for name of your Butler Builder, or write on your company letterhead for informative brochure.

BUTLER STEEL PRODUCTS

BUTLER MANUFACTURING COMPANY

7418 East 13th Street, Kansas City 26, Missouri

Manufacturers of Steel Buildings • Oil Equipment
Farm Equipment • Dry Cleaners Equipment
Outdoor Advertising Equipment • Special Products

Sales Offices in Los Angeles, Richmond, Calif. Houston, Tex. • Birmingham, Ala. • Minneapolis, Minn. Chicago, Ill. • Detroit, Mich. • New York, N. Y. Burlington, Ont., Can.

it-yourself market. For now, limited production is for commercial users. Thicknesses are 1¼, 1½ and 1¾ in. SEIBERLING RUBBER CO., NEWCOMERSTOWN, OHIO.

Bond-Breaking Agent Aids Concrete Appearance

A concrete-curing and bond-breaking compound introduced under the tradename Tux is said to contain no oil, wax or paraffin. As a result, paint is reputed to adhere well to the concrete surface. Tux-treated units also "break clean," free of stains and uniform in color, according to the manufacturer. HUNT PROCESS CO., INC., 7012 STANFORD AVE., LOS ANGELES, CALIF.

Handtruck Has Hand Brakes Also Locks in Tilted Position

A new handtruck, designed primarily to handle grain, fertilizer, cement and other bagged materials stored on pallets, is said to have several unusual features. It is equipped with a special shoe that automatically locks it in a tilted position with a full load. The shoe also allows easy tipping action after the truck has been moved into the load in a vertical position.

An unusual fork design to the loading shoe allows use of an inexpensive pallet with a reinforcing center cleat.

The truck is so designed that when the load is tilted to approximately 45 deg, it reaches a balance point at which the load will rest. It is available with two-wheel brakes for safe handling, on ramps. VALLEY CRAFT PRODUCTS, INC., 770 JEFFERSON AVE., LAKE CITY, MINN.



Reinforced Plastic Used For Ladder Side Rails

Laminated plastic construction similar to that used for automobile and boat bodies is now applied in making ladders.

Putnam Rolling Ladder Co. has developed a model with reinforced plastic side rails and lightweight metal rungs.

The sandwich construction of the side rails is glass-fiber-reinforced polyester resin (American Cyanamid's Laminac), which is molded over a core made of balsa wood. Either aluminum or magnesium rungs are plastic-welded to the rails.

Qualities claimed for the ladders include lightness (2 lb per ft), nonconductance (120 kv failed to break down resistance between rungs), and immunity to corrosion (the same plastic is used to line tank cars carrying active chemicals).

The ladders are made with either straight or tapered rails. Available types and sizes are: standard or heavy-duty single ladder, 8-20 ft; standard extension, 16-28 ft; heavy-duty extension, 16-40 ft. PUTNAM ROLLING LADDER CO., 32 HOWARD ST., NEW YORK 13, N. Y.

(*New Products continued on page 54*)

"KAISER ALUMINUM ROOFING SAVED US TIME AND MONEY"

—says Mr. Dan C. Sill, Kern Rock Co., Bakersfield, California

"Our building made with Kaiser Aluminum Industrial Roofing sheets gives us outstanding service at remarkably low cost," says Mr. Sill.

"We are especially pleased with the savings in both material and labor that these Kaiser Aluminum sheets made possible. The sheets are 48 inches wide and .024 inch thick by 7/8 inch depth of corrugation. Those specifications allowed us to use five-foot purlin spacing spans, figuring 35 pounds per square foot uniform loading based on a safety factor of two.

"Also, our maintenance costs are way down because the aluminum will never rust. Our 80,000 square foot building will never need painting or expensive maintenance of any kind.

"We are so completely satisfied with this building that we are now putting up a similar, 68,000 square foot building. Of course, we will use Kaiser Aluminum Industrial Roofing.

"For quality roofing at low cost, we recommend Kaiser Aluminum."

The experience of the Kern Rock Co. is typical. Whatever you are building, figure first in Kaiser Aluminum for better value at lower cost.

For A.I.A. File and complete information, contact any Kaiser Aluminum sales office listed in your telephone directory. Or write Kaiser Aluminum & Chemical Sales, Inc., *General Sales Office,* Palmolive Bldg., Chicago 11, Illinois; *Executive Office,* Kaiser Bldg., Oakland 12, California.

Kaiser Aluminum

Industrial Roofing and Siding

See "THE KAISER ALUMINUM HOUR." Alternate Tuesdays, NBC Network. Consult your local TV listing.

HOW TO HANDLE WET JOBS

NEW SEA LIFE HOME FOR MARINE STUDIOS

Marineland, Fla.

Contractor: Arthur Perry, Inc.



50 POINTS, 240-ft header: What volume could be handled by a well-point system of such size, working in very coarse water-bearing sand just a few ft from the ocean? Answer below.

3,960,000 GALS per day were pumped round-the-clock for the life of the job—this entire flow handled by one Griffin Vac-u-matic wellpoint pump.

SUCH exceptional drainage volume—it's 55 gals per minute for each point—will surprise many contractors. Others know from repeated experience the superiority and efficiency of the Griffin system.

GRIFFIN

WELLPOINT CORP.

881 East 141st Street, New York 54, N. Y.
Hammond, Ind. Houston, Tex. Jacksonville, Fla.

In Canada: Construction Equipment Co., Ltd.
Toronto Montreal Halifax



Trailer-Mounted Portable Steam Plant

A trailer-mounted steam generator that offers closest control for pile driving applications, according to its manufacturers, provides fully modulating control from low-fire to high-fire with a single control mechanism.

The PS-125 portable steamer delivers 4,300 lb per hr of dry steam in 30 minutes from a cold start making it especially useful for pile driving, because it gives single and double-acting hammers full rating in maximum number of blows through the pile-driving cycle. Versatile in application, the PS-125 provides steam for heating asphalt, winter thawing, cleaning of equipment or heating buildings.

Fire-tested at the factory, the unit is insulated with glass fiber and fully weather protected. The tractor-mounted model is readily mobile, but it comes on skids, as well. It carries its own fuel supply—132 gal of No. 2 fuel oil in two fenders—and its air-atomized burner has been field tested in thousands of applications, according to a report from the producers.

The engine is rated at 22 hp continuous duty at 1,800 rpm, with hand throttle control at speeds below 1,800. CLEAVER-BROOKS CO., 326 E. KEEFE AVE., MILWAUKEE 12, WIS.

Flush Joist Hanger Line Gets Double-Width Model

The F. D. Kees line of flush-type joist hangers is now augmented by double-width hangers for two 2-in. joists or one 4-in. joist. Recommended long-term loading per hanger is 1,200 lb. Made of 14-ga galvanized steel, the hangers are packed 25 in a case—shipping weight 26 lb. F. D. Kees Mfg. Co., Beatrice, Neb.

Rotary Drill Uses Air And Water for Operation

A new unit in the Davey Compressor rotary drill line is the Model M-SAL, which can drill 24-ft ledges without changing steels. Suitable for mounting on any standard truck, the unit uses both compressed air and high-pressure water for drilling. It has a rated capacity of 6¼-in. holes up to 600 ft with air, and 1,500 ft with mud. In operation, it is said to affect substantial savings in drilling costs.

The new drill is recommended for shot- and blast-holes, structural testing, core drilling and water-well operations. Weight of the complete unit is about 26,000 lb. ROTARY DRILL DIV., DAVEY COMPRESSOR CO., KENT, OHIO.

Why buy more machine than you need ?



THE 3/4-YD. LORAIN 25A

gets your job done and makes you money!

There are many ¾-yd. shovel-cranes on the market. Some are "light weight"—at a price. Some are "heavy-duty," deluxe, more costly. The Lorain-25A is neither. It is a true, full-value, ¾-yd. *general-purpose* machine that will surprise and satisfy you with its ability to handle a wide range of tough jobs. It is an all-around, fast, serviceable machine—not over-priced, not over-engineered, but containing many quality features that give you plenty of pep and power, plenty of long-life endurance.

If you want a real ¾-yd. machine that will handle all of your day-to-day requirements with ease and still have enough "stuff" to handle your occasional "extra tough" jobs—the Lorain-25A is your machine. You don't have to pay the deluxe, heavy-duty price to get most of the big-machine features. You don't have to buy more machine than you really need to get the design and quality construction you know you must have to get long life, profitable operation.

Feature for feature—value for value—dollar for dollar—you'll find the Lorain-25A gives you the most for your money in the general-purpose ¾-yd. class. It is available as a ¾-yd. shovel—as a hoe with 16' and 19' boom, with 30" or 40" dippers, or as a dragline, clamshell or crane. You owe it to yourself to check the "25A" in operation. Call your Thew-Lorain Distributor and ask him for a job-visit demonstration!

THE THEW SHOVEL CO.
LORAIN, OHIO, U.S.A.

EVERY DAY . . . these "25A" features make money

Here are important features that pay dividends the minute your operator takes over the control of a Lorain-25A. They mean easier operation, faster cycles, reduced operator fatigue, higher production. Ask your operator to check them, too.

- Big, 18" swing clutches—20% larger, fewer adjustments, longer life
- "E-Z" operating controls—effortless action, fast response
- "Hydra-Ease" control of crawler steering, tread lock, house lock and shifting of swing-travel jaw clutches
- 2 crawler speeds in both directions
- 12' 6" crawler—stable, no "nosing-in"
- 4-way position tread and travel lock, hydraulically operated
- Independent travel available, a big advantage on dragline and hoe operations
- New, square-tubular-chord clamshell and dragline boom—lighter, stronger; greater lifting capacities; greater bucket operating ranges
- Steel shell lagging for bigger cable on drag-in drum
- Power load lowering is standard

OVER MANY YEARS . . . these features mean long life

Consider these features in terms of a long-term investment—features that keep your Lorain on the job more hours over more years.

- One-piece, all-welded, truss-reinforced, rigid turntable bed—assures lifetime alignment of mechanism
- 19 anti-friction bearings on clutch shaft
- Hoist drums on anti-friction bearings
- Oil-enclosed cut gears on turntable
- Oil-enclosed crawler travel mechanism
- Dragline fairlead sheaves on anti-friction bearings
- Sealed idler rollers on anti-friction bearings available for crawler
- Treads with replaceable tread pin bushings available for crawler
- Choice of 22" or 29" crawler treads
- Fully convertible to shovel, crane, clamshell, dragline or hoe—extra job and profit possibilities
- Choice of 16' and 19' hoe booms
- Hoe dippers available in 30" to 40" widths

THEW LORAIN®

THE NEW BARCO VIBRA-TAMP*

* Companion Tool to the Barco Rammer, Famous for Deep, Penetrating Soil Compaction!

A Versatile Tool for MAXIMUM COMPACTION of

1. Granular Base Materials
2. Bituminous Surfacing

EFFICIENT—one man does the work of many with VIBRA-TAMP. Operates in any weather. Works flush against curbs, foundations, and walls.

ECONOMICAL—to buy, operate, and maintain! No special tools required. Saves your bigger, costlier equipment. Tamp up to 750 sq. yds. per hour.

SAFE—moving parts fully enclosed. Special vibration dampers reduce operator fatigue. Simple controls. Handle adjustable to comfortable height.

DURABLE—simple design and quality construction keep VIBRA-TAMP on the job day in and day out. Carburetor unaffected by vibration.

VERSATILE—use VIBRA-TAMP for all kinds of work—wherever low cost is a prime consideration. Take VIBRA-TAMP on the big jobs for hard-to-reach areas. Use it for patching streets, driveways, and roads. VIBRA-TAMP has no economy equal—a real work-horse on sand, gravel, soil, chippings! *Ask for new catalog No. 630.*

Worldwide Sales and Service

BARCO *Serving Industry Since 1908*
MANUFACTURING COMPANY, 514M Hough St., Barrington, Ill.

Publications

Steel products—This 4-page folder is a catalog of bulletins. Along with photos and brief descriptions of various steel products for construction, it identifies by number more inclusive bulletins available on the various individual products. Listed items include guard rail, forms, flooring, pipe and pipe arch, steel buildings, and sectional plate. United Steel Fabricators, Inc., Wooster, Ohio.

Roof construction—Insulation clips, Koroseal vapor barriers and a nonflammable adhesive for securing the barrier to the deck are described in an 8-page booklet on Lexsuco roof construction. Photos, drawings and cutaway sketches illustrate the products and their application. Included are 4 pages of suggested specifications. Lexsuco, Inc., 4815 Lexington Ave., Cleveland 3, Ohio.

Clay products—Designed for quick reference, a new four-page bulletin, "Vitrified Clay Products", has recently been published. Fully illustrated, the bulletin contains complete data specifications and dimensions on a wide variety of clay products. Robinson Clay Product Co., 65 W. State St., Akron 9, Ohio.

Steel forms—Milcor Ribform, a permanet steel form product for short-span concrete floor and roof slabs, is described and pictured in a 4-page brochure. Physical properties, span and floor-load tables and suggested specifications are included. Catalog 325. Inland Steel Products Co., Box 393, Milwaukee, Wis.

Turbidity in fluids—Data sheet contains specifications and applications of the Kaye Development Company's Turbistat, an instrument that provides continuous monitoring of turbidity in fluids. Baird Associates-Atomic Instrument Co., 33 University Rd, Cambridge 38, Mass.

Core drilling—Detailed description of its model 30 core drilling machine has been offered by Sprague & Henwood, Inc., in its new 8-page Bulletin #350. Major machine features described are four types of power units, its machined cast steel hoist, a three-speed transmission, its oil circulation system and optional features such as a two-cylinder water pump and a single-pole derrick that can be furnished for use on skid, trailer or truck mounted machines. Sprague & Henwood, Inc., Scranton 2, Pa.

"And I Said I'd Never Use a Drafting Machine"



"That Was Before I Tried a Bruning Equipoise Drafter!"

Bruning Counterbalanced Drafters and Bruning Track Drafters provide fast, easy, accurate drafting on vertical boards and on extra-large drawings.



Bruning Equipoise Drafters are available with either the Civil Engineer protractor head, shown here, with its special azimuth scale, or the Standard protractor head.

Take a tip from an increasing number of draftsmen who, perhaps like yourself, were reluctant to try any drafting machine or had been disappointed in a conventional type drafter. These men now report: Bruning Equipoise Drafters cut drafting time over conventional equipment up to 40% on most jobs, up to 50% on some structural drawings — beat any other drafting machine they ever tried.

But prove it to yourself! See how fast you'll work with one precision instrument combining T-square, straightedge, triangle, protractor, and scales. Feel how the patented Equipoise mechanism eliminates any drift from gravity, literally makes the drafter "float" into place. Find how easy it is to rotate, turn, and lift this drafter — all with the left hand. At the same time, operate the Touch Control button with your left thumb to set the drafter automatically at any of 24 commonly used 15-degree increment angles. Don't overlook the special scale lock that makes it easy to change the scales, holds the scales rigid.

Your own test will convince you of the superiority of a Bruning Equipoise Drafter. Mail coupon today!

BRUNING

America's Largest Supplier of Engineering and Drafting Equipment.

CHARLES BRUNING COMPANY, INC., 4700 MONTROSE AVE., CHICAGO 41, ILL.

Charles Bruning Company, Inc., Dept. 114-M
4700 Montrose Ave., Chicago 41, Illinois
Please send me the free booklet on Bruning Drafting Machines.

Name_____ Title_____

Company_____

Address_____

City_____ County_____ State_____

THREE-GANG TAMPER does more work than three single tampers, yet requires only one man to operate. The Schramm 125 cfm Standard Pneumatractor moves right along with the work and furnishes full rated air at tool—enough to operate the three-gang tamper and another tamper.

CONSTRUCTION MEN AGREE:

There's no end to the jobs this tractor-compressor can do

What can you do with Pneumatractor? Drill rock or break out concrete. Load, unload and haul materials. Dig, grade, backfill and tamp. Plow snow or sweep concrete pavement. Cut brush and briars. Do mudjacking and under-sealing. Operate all kinds of compressed air tools—from chipping hammers and paint sprayers to paving breakers and post-hole diggers.

You've never seen any other machine do so many things so well. It's a complete, self-propelled, air compressing plant and tractor combined. It delivers 125 cfm at 100 pounds gauge pressure. Goes anywhere under its own power and converts, in an instant, right from the instrument panel.

What will you save with Pneumatractor? Plenty! The expense of a portable air compressor *and* a truck or individual tractor, plus its driver. The cost of maintaining two separate machines. The time and manpower involved in moving a portable compressor from one job to another. And, finally, idle time. Catalog 5540 gives full details. Write for your copy.

Your local Schramm Dealer is listed in the Yellow Pages of your telephone directory.

FORM PIN DRIVING is only one of the many jobs handled faster and cheaper by a self-propelled Schramm Pneumatractor. The compressor has capacity enough for more than one driver and needs no "stand-by" operator to watch it.

ROTARY BRUSH, mounted on Pneumatractor, is used to sweep concrete pavement so that surface can be inspected. Brush is hydraulically operated, so its rotation is entirely independent of the road speed of the Pneumatractor.

Schramm, Inc.

MANUFACTURERS OF AIR COMPRESSORS

620 North Garfield Ave. West Chester, Pa.

Men and Jobs

Maryland's Dean Steinberg To Head Brazilian School

Samuel Sidney Steinberg, dean of the University of Maryland's College of Engineering since 1936, will become head of a government-operated aeronautical engineering school in Brazil next month.

During 38 years at Maryland, Steinberg has helped build the university into the position it holds today.

Steinberg calls his new school "the MIT of Brazil, with a distinguished faculty of professors from that country, North America, and other places." He will be furnished a home and a private airplane with pilot, in addition to his salary, reported to be tax-free.

Steinberg plans to fly from New York Dec. 27 to take his post at the Brazilian school—50 miles from Sao Paulo—which has grown to 500 students since its start in 1950.

General Chorpening Joins Firm

Maj. Gen. C. H. Chorpening (Ret.) one-time Assistant Chief of Engineers for Civil Works and recently on duty with U. S. forces in Japan has joined the firm of Herbert Voelcker and Associates, Houston, Tex., architects and engineers for public buildings and public works. The firm name has been changed to Herbert Voelcker, C. H. Chorpening and Associates, and General Chorpening will maintain an office in Centreville, Md., for part-time service with the firm.

Men and Jobs Briefs . . .

• **Associations**—The Dartmouth Society of Engineers elects as president, **Howard A. Schroedel,** vice president and director of the Turner Construction Co. of New York City.

The newly formed National Association of Distributors and Dealers of Structural Clay Products elects as president **Harry M. Spaulding** of the Spaulding Brick Co. of Boston, Mass.

• **Careers**—The director of the Memphis and Shelby County (Tenn.) Planning Commission, **Charles A. Phelan, Jr.,** resigns effective Dec. 31 . . . **Robert R. Baker** of the firm of Palmer & Baker, Inc., consulting engineers in Mobile, Ala. resigns for reasons of health.

Charles Crull, city engineer of Oceanside, Calif., resigns effective Oct. 31 to enter private practice in San Diego, Calif., as a registered civil engineer.

• **Business**—Victor W. Buhr Associates, engineers and architects of Salisbury, Md., announces that **William B. Miles, Jr.**, is joining the staff . . . **Rosaire J. Laporte**, and **Harold W. Penn** open offices as Consultants and structural engineers in Detroit, Mich. . . . **A. R. Todd** forms his own consulting engineering practice after resigning from the city of Wheeling, W. Va. The firm will be known as A. R. Todd Associates, Inc., Engineers in Wheeling, W. Va.

August S. Gehrels, who until recently was executive vice president of the Cuban Electric Co., is elected vice president of Ebasco International Corp. . . . The engineering firm of Tippetts-Abbett-McCarthy-Stratton of New York admits the following as general partners: **Frank Lilien, Leonard A. Lovell** and **Thomas J. Fratar.**

• **Retirements**—**Alfred C. Musson**, head of the Maintenance Division, Public Works Department, Brooklyn Navy Yard, after 37 years of service with the Navy. . . . **Bert Lund**, maintenance engineer for District X of the California State Division of Highways, after 28 years of service with the state.

Obituaries

Joseph Salzman, 63, junior partner in the New York City firm of consulting engineers Strobel & Salzman, died Oct. 30 at Flushing, N. Y. Born in what is now a section of Czechoslovakia, Salzman came to the U.S. in 1920 after receiving, the same year, a civil engineering degree from the Technical University of Budapest (Hungary). He acquired U.S. citizenship in 1929.

Prior to forming his present partnership with Peter Strobel in 1944, Salzman was chief engineer for Skidmore, Owings & Merrill, New York architects and engineers. While serving with this firm, he participated in the World War II Manhattan Project, the atomic energy development at Oak Ridge, Tenn. During his career, he was also associated with Shreve, Lamb & Harmon Associates, architects; Hegeman-Harris Co., Inc., builders; and Lockwood Greene Engineers, Inc.; all of New York City.

Among his recent projects was the Albert Einstein College of Medicine, at Yeshiva University, New York. At the time of his death he was engaged in design work on a project to be built at Lexington, Ky., for International Business Machines Corp.

(*Continued on page 63*)

Q-FLOOR helps make Ford's new office building as modern as its cars



Ford Motor Company . . . . . Dearborn, Michigan
Skidmore, Owings and Merrill . . . . . Architects
Bryant & Detwiler Company . . . General Contractors
Weiskopf & Pickworth . . . . . Structural Engineers

Shown above is the Ford Motor Company's magnificent new administration building which occupies a 90-acre site in Dearborn. It provides nearly 950,000 square feet of floor space, approximately 500,000 square feet of which is Q-Floor and on which 3,000 employees are working in the comfort of the latest in modern lighting and air conditioning.

Architects Skidmore, Owings and Merrill carefully designed the building to prevent obsolescence due to changing conditions in the years to come. Interior partitions are movable to provide maximum flexibility in floor arrangements, and Robertson Q-Floor construction has been used to permit complete freedom of power and telephone outlet changes and additions at minimum cost. Only with this weight-saving, cellular steel structural floor can every exposed 6" square area be the potential location of a convenience outlet.

Robertson Q-Floor construction also saves time and money. Its weight-saving factor means lower cost of foundation and structural steel. It immediately becomes a safe storage and working platform for the benefit of all trades. And because no combustible forms and falsework are required for the concrete fill, there has never been a construction fire on a Q-Floor job.

With all these features, it is easy to see why Q-Floor will help keep this fine new building as modern as the Ford of tomorrow.

Robertson

Q-Floor

a product of **H. H. Robertson Company**

World Wide Building Service

2420 Farmers Bank Building • Pittsburgh 22, Pennsylvania

Please send a free copy of your "Q-Floor" catalog.

Name _____

Address _____

Here Now! NEW CHEVROLET

FIRST with the MOST

They're out to save you hours and dollars on any hauling job . . . and they've got big new power plus the modern features that make it a sure thing! They put you way ahead with time- and work-saving advantages you won't find in any other truck today!

Year after year—first with the most modern features! And again, for 1957, Chevrolet brings you the industry's most advanced truck features—new developments that have already been proved in a history-making preannouncement test run! (See below.)

For '57 there's bold new styling—rugged good looks to match Chevy's remarkable stamina and dependability. There's new

---

Alcan Highway Test Run Proves Chevrolet Ruggedness!

In an AAA-certified endurance run, 6 new Task-Force trucks roared up the 1,520-mile Alcan Highway (normally a 72-hour run) in less than 45 hours! In dramatic fashion, new Chevy trucks conquered one of the world's most challenging roads and proved their greatness!

AAA

A

TASK·FORCE 57 TRUCKS!

modern features

fleet-action power in Chevy's outstanding new engine line-up—with the 195-h.p. Loadmaster V8 standard in all 9000 and 10000 series trucks; and the sensational new 283-cu.-in. Taskmaster V8 (160 h.p.) standard in 5000, 7000 and 8000 series models. All told: *five* high-efficiency V8's and *three* economy leader 6's in the truck line alone!

Many models are equipped with bigger, brawnier rear axles. And there's a load of heavy-duty options for '57 — including Chevy's revolutionary 6-speed Powermatic transmission, designed especially for heavy-load, high-mileage hauling.

Your Chevy dealer has all the details. When you see him, be sure to check the new cab features, too. . . . Chevrolet Division of General Motors, Detroit 2, Michigan.

The "Big Wheel" in trucks!

B

C

A. Cameo Carrier covered entire distance without stopping engine; averaged 18.17 miles per gallon!

B. New Super Taskmaster 283 V8 stole the power show, flattening an obstacle course of mud, gravel and grades!

C. 1,520 miles without shifting gears! Powermatic equipped heavyweight went all the way in a single forward-speed range!

No costly maintenance problem here



For year-in, year-out durability and minimum maintenance, Olympic Portland Cement Co. selected Johns-Manville Corrugated Transite for its Bellingham, Washington, plant. Transite Erector: The E. J. Bartells Company.

build with Johns-Manville Corrugated Asbestos Transite

For maintenance-free exterior walls and roofs, plus protection from fire, rot and weather

YOU SAVE MONEY on construction and maintenance when you build with Johns-Manville Corrugated Transite®. Corrugated Transite comes in large sheets that require a minimum of framing . . . permit fast, economical construction of industrial, commercial, institutional and agricultural buildings.

Made of asbestos and cement, Corrugated Transite is practically indestructible. It never needs paint or special treatment to preserve it . . . it's fireproof and rotproof. Corrugated Transite is also used increasingly for interiors. The streamlined corrugations and attractive shadow lines offer interesting design possibilities.

Investigate Johns-Manville Corrugated Asbestos Transite and learn how you can build quickly and easily . . . have an attractive, long-lasting, trouble-free structure regardless of size or purpose. For complete details, write Johns-Manville, Box 158, Dept. EN, New York 16, New York. In Canada write 565 Lakeshore Road East, Port Credit, Ontario.



- Large sheets go up quickly
- Easy to fasten to steel
- Easy to nail to wood
- Easy to saw
- Easy to drill

See "MEET THE PRESS" Sundays on TV, sponsored by Johns-Manville. Consult your newspaper for time and station.

JOHNS MANVILLE PRODUCTS

Johns-Manville

. . . Obituaries

Adolph Wehner, 68, retired engineer for the City of San Francisco, died Oct. 26 in Fresno, Calif. He retired at 65 after 36 years with the San Francisco Public Utilities Commission's Bureau of Engineering. Mr. Wehner played an active role in developing San Francisco's water supply from the Sierras (the Hetch Hetchy project) and in preparation of the tideland site for San Francisco International Airport.

J. Stanley Donahue, 65, president of the Lally Column Co., Cambridge, Mass., died Oct. 30 at White Sulphur Springs, Va. Mr. Donahue was a past president of Metal Fabricators and had been active in the American Institute of Steel Construction, the Massachusetts Building Congress and the Master Builders Association.

James A. Broadbent, 61, an engineer with the M. W. Kellogg Co., of New York, died Oct. 30 in South Africa. The firm is constructing an oil refinery there. A native of Scotland, Mr. Broadbent studied mining engineering at Glasgow University. He had been with Kellogg for 35 years and also had engaged in construction work during the 1930's for Hercules Powder Corp. and the Lummus Co. He became a citizen of the U.S. in 1928.

Farrand Northrop Benedict, 76, died Nov. 3 at Parsippany, N. J. after a short illness. Mr. Benedict was for 46 years vice president and chief engineer of the Thomas Crimmins Contracting Co., of New York City. He was a graduate of the Columbia University School of Engineering.

Color Film Stimulates Interest In Engineering as a Profession

The type of training necessary for the engineering profession, and the engineer's role in planning the world of tomorrow, are subjects of a nontechnical, color movie by the College of Engineering of Ohio State University.

The 20-min sound film is designed to serve as a guide to youngsters and their parents, in evaluating the educational requirements and practical applications of engineering training. It attempts to answer four questions: What is an engineer? Why is he needed? What does he need to know? How does he become an engineer?

The film centers around the world of a young boy and is called "Engineering for Eddie". It is available on a free-loan basis or purchase from the Department of Photography, Motion Picture Division, Ohio State University, Columbus 10, Ohio.

WIRE ROPE TALKS

SUBJECT:

STORING WIRE ROPE OUTDOORS

Practical hints on the use and care of wire rope by Robert M. Kilian, Chief Engineer of Leschen Wire Rope Division, H. K. Porter Company, Inc.

QUESTION:

What is the best method of storing wire rope outdoors?

ANSWER:

If you think of wire rope as a machine of many parts built to close tolerances, you quickly understand why it should be protected from outside exposure, particularly from dampness or humidity. Extended exposure under severe conditions will impair wire rope to the point of substantially reducing its effectiveness. After idleness and lack of care it may be of little use.

For example, rust tends to bind wires together so they are not free to move back and forth. Then they fail to adjust themselves when lifting or pulling a load. They do not move properly in operation around sheaves.

Lubrication and Cleaning

The outer layer of new wire rope to be stored on its shipping reel should be covered with a heavy protective lubricant. A generous application will tend to protect the entire length. "LePro" Wire Rope Protector, a Leschen product, is especially formulated for this purpose. You apply it cold, and it goes on quickly with a brush or by pouring slowly from a can.

Wire rope that has been used should be cleaned thoroughly with a wire brush, compressed air, or superheated steam. Then lubricate it with a penetrating lubricant that will coat all strand wires, internally as well as externally. Next coat the rope with "LePro" to seal in the other lubricant and repel penetration of moisture and fumes. Finally, wind the used rope on a reel.

Following lubrication with "LePro" it is advisable to cover the rope on the reel with waterproof or tar paper. Seal the paper at the flange with "LePro."

Taking proper care of high-quality products like HERCULES Red-Strand wire rope is as important as selecting them in the beginning. You are money ahead on both counts.

Storing and Re-Use

Select a storage area that is clean and dry, and as well protected from the weather as possible. Avoid nearby acid fumes or other corrosive agents. They can cause embrittlement of the surface of the wires. Place reels on wood or metal supports.

When rope is returned to service, excess lubricant can be wiped off as the equipment is run slowly. Lubricants may pick up some dirt later, but this will cause far less damage than would the leaching effect resulting from the use of a solvent for cleaning.

High quality and performance built into Leschen wire rope is well worth preserving by proper storage methods. To obtain this quality in the first place remember to specify the rope with a RED STRAND—the symbol of highest quality wire rope for seventy-five years.

A Leschen district warehouse or distributor is nearby. See your Leschen man for other rope-saving suggestions—and for HERCULES Red-Strand Wire Rope.

Reprints of this "Wire Rope Talks" are available on request

LESCHEN
HERCULES Red-Strand® WIRE ROPE

LESCHEN WIRE ROPE DIVISION
H. K. PORTER COMPANY, INC.
St. Louis 12, Missouri

HKP

POWER
BY
HERCULES...!

BAKER Industrial Trucks rely on . . . POWER BY HERCULES. These rugged trucks demand a compact, heavy-duty power plant. That's why Hercules Gasoline and Diesel Engines were selected as standard in Baker equipment.

The wide selection of Hercules Engines—over 90 models from 3 to 500 H.P.— provides a proper size of engine to meet your power requirements.

For power "tailored" to your needs, specify . . . POWER BY HERCULES.

HERCULES MOTORS CORP. • CANTON, OHIO

International

Largest Lagoon

Sewage lagoon recommended for city of 90,000

If it carries out the recommendations of its consultants, Regina, Saskatchewan, will have the largest sewage lagoon installation to date, and will be the largest city served by the process.

Confronted with the need to expand an overloaded trickling-filter plant, Regina will find it most economical to build eight sewage lagoons over a 2,400-acre site, say D. R. Stanley and Associates, Edmonton, and James MacLaren Associates, Toronto. Otherwise, Regina will have to convert the existing plant to an activated sludge operation.

The main difficulty with expanding the existing trickling-filter plant is an unusually strong sewage, 422 ppm of suspended solids, 570 ppm of BOD and 87 ppm of grease. Better than 90% reduction in solids and BOD would be achieved by the lagoons, state the consultants.

Regina is a prairie city of 90,000 population, expected to reach 130,000 by 1975. It has the windswept climate of many of the smaller towns and villages in Saskatchewan, the Dakotas, and Montana wher sewage lagoons are growing ever more popular. At this time, the consultants state the largest town in North America served by lagoons has a population of 11,000.

Regina's pending involvement with sewage lagoons is not to be confused with its present problem with sludge lagoon odors (ENR Nov. 1, p. 76).

Mackinac Bridge Studied For European Application

The Straits of Mackinac bridge, the world's longest single suspension span when it is completed in November, 1957, may become the model for a bridge connecting Sweden and Denmark.

Karl-Gustaf Hjort, director of Sweden's royal board of roads and waterways, recently visited the bridge which will span the straits between Michigan's upper and lower peninsulas.

He studied the similarity of the problem Swedish and Danish engineers may have in bridging the Oresund Strait between the North and Baltic seas.

He said the strait in Europe varies from four to seven miles at the points where it may eventually be bridged.

"We are developing long range pro-

(Continued on page 69)

ALL OF IT STARTED
WHEN ICHABOD MET BEN

ICHABOD WASHBURN

Ichabod, Ichabod, how did you ken
The need for wire when you met Ben?
How did you know you'd not lose your shirts;
That ladies of fashion would hoop their skirts?

BENJAMIN GODDARD

Ichabod, Benjamin Goddard and you
Together made some products new.
How did you know that when sales took a drop
Washburn & Goddard would still be on top?

Ichabod. Benjamin. You made some dough
And finally merged with a worthy foe.
A. S. and W. now it became,
With products and sales, and world-wide fame.

Times have changed—wire uses, too,
But venerable A. S. and W.
Still remains foremost and best
In wire and wire products from Worcester, west.

READER: *If you would like information on steel reinforcement for concrete, you might find some on the next page. . . .*

AMERICAN STEEL & WIRE DIVISION

UNITED STATES STEEL

ODE TO A ROAD...AND



When Ichabod and Ben used to ride through towns

They bounced and they jounced and they wore big frowns.

Today, they'd be happy, and free of all ire

On roads made of concrete, reinforced with wire.



A skyscraper builder by the name of Peter Grim

Forgot wire fabric and learned to his chagrin

That there's not a building tenant who doesn't deplore

An office that's built with a disappearing floor.

Quality American Welded Wire Fabric reinforcement controls cracking, and the longer reinforced concrete slabs provide a smoother riding pavement. Reinforced concrete pavements are 30% stronger than plain concrete pavements of equal thickness. Reinforced concrete pavements therefore last longer. You will find American Welded Wire Fabric adding strength to superhighways in Pennsylvania, Ohio, Indiana, and the City of Detroit. It is used with excellent results in asphaltic as well as Portland cement concrete. It comes in any size and style you need.

You need the extra strength of American Welded Wire Fabric reinforcement in any concrete floor. In beam and slab floors, like those in the Socony-Mobil Building shown above, and in pan and joint floors, American Welded Wire Fabric can be rolled into place quickly and easily . . . comes in any size or style you need.

USS AMERICAN
WELDED WIRE
FABRIC

USS

OTHER THINGS

There once was a bridge and it didn't need paint,
But collapsed in the river in a plain dead faint;
And so did the builder, all damp and distressed,
His bridge would have stayed if he'd had it prestressed.

Prestressed concrete now is being used in building floors, roofs, and beams, as well as in bridges. And in the Lincoln Tunnel Retaining Wall, shown at right, prestressed concrete panels form the wall. These panels were pretensioned with American High Strength Stress-Relieved Strand. American Steel & Wire also manufactures Super-Tens Stress-Relieved Wire for prestressing systems that use wire. American Steel & Wire was the first to manufacture a high strength strand for pretensioned, prestressed concrete. We make a complete line of sizes and types in both wire and strand.

OUR POINT IS THIS, *if you can stand some more*
When it comes to wire, we're a general store. For roads, for bridges, no matter what,
Of wire and wire products we've got a lot — So send the coupon without delay;
Just turn this page, and send it today.

AMERICAN STEEL & WIRE DIVISION, UNITED STATES STEEL · GENERAL OFFICES: CLEVELAND, OHIO

COLUMBIA-GENEVA STEEL DIVISION, SAN FRANCISCO, PACIFIC COAST DISTRIBUTORS
TENNESSEE COAL & IRON DIVISION, FAIRFIELD, ALA., SOUTHERN DISTRIBUTORS · UNITED STATES STEEL EXPORT COMPANY

USS AMERICAN Super-Tens Stress-Relieved WIRE
and
AMERICAN HIGH STRENGTH STRESS-RELIEVED STRAND



Accidents are no joke! Like you we'd like to stop them all. Failing that, here's help for you —

Multisafty Cable Guard



SEND THIS COUPON for complete information about any of the construction materials manufactured by American Steel & Wire

HOW TO STRENGTHEN AND PROTECT HIGHWAYS

American Steel & Wire
Room 842, Rockefeller Bldg., Cleveland 13, Ohio
Please send complete information on the following products:

- ☐ Multisafty Cable Highway Guard
- ☐ American Beam-type Highway Guard
- ☐ American Welded Wire Fabric for Portland Cement Concrete
- ☐ American Road Joints
- ☐ American Welded Wire Fabric for Asphaltic Concrete
- ☐ American Welded Wire Fabric for Airport Runways
- ☐ American Wire and Strand for Prestressed Concrete
- ☐ General Catalog on Welded Wire Fabric
- ☐ Have your representative call

Name.....

Firm.....

Address.....

City.....State.....

American Multisafty Cable Highway Guard is made from resilient steel cables, mounted on resilient spring-steel offset brackets. The combination gives vehicles two-way protection: it restrains a vehicle from plummeting off the berm, and cushions the shock of impact between vehicle and guard. It is easy to install, easy to maintain, and lasts a long time. It is the only guard rail that can be designed to provide definite miles-per-hour protection to the automobile driver. American Steel & Wire beam-type guard is also available for highway and parking lot installations.

AMERICAN STEEL & WIRE DIVISION
UNITED STATES STEEL, GENERAL OFFICES
CLEVELAND, OHIO
COLUMBIA-GENEVA DIVISION, SAN FRANCISCO,
PACIFIC COAST DISTRIBUTORS
TENNESSEE COAL & IRON DIVISION, FAIRFIELD, ALA.,
SOUTHERN DISTRIBUTORS
UNITED STATES STEEL EXPORT COMPANY, NEW YORK

USS MULTISAFTY HIGHWAY GUARD

UNITED STATES STEEL

gramming for all our highways and a bridge between Denmark and Sweden is being considered," said Hjort.

Hjort was particularly impressed with the foundation structure of the Michigan bridge. He said the Oresund project probably would require a similar foundation system.

Hjort came to the United States as a member of a six-man delegation of Swedish engineers to attend a meeting of the International Road Federation. They also investigated the design and operation of the New Jersey and Pennsylvania turnpikes and Hjort studied Michigan's system of roadways.

U. S. Firms to Build Reactor For Venezuelan Research

Two U. S. firms have been selected to design, manufacture, and furnish consulting engineering services for Venezuela's first atomic reactor—largely for medical research.

Humberto Fernandez-Moran, director of IVNIC, the Venezuelan biophysics and nuclear physics research center, said in a recent announcement that the General Electric Co. will design and manufacture a research reactor rated at 3,000 kw, and General Nuclear Engineering Corp., of Dunedin, Fla., will act as consulting engineers for experimental requirements and design of housing for the reactor.

Argentina Plans Port Work

A new port to bring agricultural produce from a large section of the Province of Misiones to market, will be built on the left bank of the Alto Parana River at a town known as Puerto Viejo.

Government plans call for four piers to permit direct loading from trucks. The piers will be built with varying levels connected by ramps to permit loading during the widely fluctuating stages of the river.

(*International continued on page 70*)



Metal Umbrella Shields Construction

A Dutch building contractor has found a way to beat the weather. He erects an aluminum umbrella over his job and raises it with the building. Plastic sides complete the enclosure, while infra-red ray heaters warm the interior when necessary.

N. V. Haagsche Bouwmaatschappij, The Hague, on a current project is maintaining a 230x45-ft aluminum cover 10 ft above construction level. Openings in the light-gage corrugated aluminum sheets that form the movable gable roof are glazed with transparent plastic to admit light. The metal sheets are supported on steelpipe rafters, which are tied to form a truss. The whole umbrella is carried on steel-pipe scaffolding and is guyed to deadmen at grade along the edges and ends, to resist wind pressure.

The plastic sheets forming the walls of the enclosure are transparent. They rise with the umbrella.

Experience with this enclosure last winter proved that building operations can proceed in spite of rain and snow.

MAKES BETTER— MORE WORKABLE MORTAR!

Get snug, tight, neat joints!

Use MORTITE in *any* mortar, *anywhere*, under *any* conditions. It produces a smooth "buttery" mix with a minimum of water.

Dry mortars are frequently too stiff to be workable. Poor compactness and poor adhesion can result. Truscon MORTITE improves the workability without the addition of detrimental excessive mixing water!

Truscon MORTITE provides greater plasticity which allows time for smooth positive trowelling and "striking-off" of the joints. Less time and effort and lower costs result.

Specify and use MORTITE for better mortar at lower initial cost and long range savings in repointing costs!

Send coupon below to Truscon Laboratories. Learn how MORTITE has produced results for leading engineers and contractors on major projects all over America and the world.

TRUSCON Laboratories
Industrial Maintenance Division of Devoe & Raynolds Co. Inc.

TRUSCON LABORATORIES
1700 Conliff, Dept. E-36, Detroit 11, Mich.

SEND FULL INFORMATION

Name_____
Firm_____
Address_____
City_____ Zone____ State____

these jobs were done at a lower cost with the

SAUERMAN METHOD



Silt Removal by Slackline Cableway keeps channel clear for irrigation project. Bucket digs, then conveys spoil to downstream side of dam. (*Sauerman News 146*).

Digging Gravel for a plant supplying aggregate for 82 miles of turnpike, this 5-yd. DragScraper often operates around the clock. It has excavated over a million tons. (*Sauerman News 145*).

Reclaiming Material to hopper from all sections of a 500-ft. warehouse, the estimated operating cost of this DragScraper Machine is 2.1 cents per ton. (*Sauerman News 145*).

•

You'll find a complete description of the Sauerman Method in Catalog A, DragScrapers; Catalog C, Slackline Cableways; and Catalog E, Bulk Storage by Scraper.

SAUERMAN BROS., Inc. 632 S. 28th STREET BELLWOOD, ILLINOIS

Iraq Irrigation Project Gets $22.4-Million Grant

The Iraq Development Board last week allocated the U. S. equivalent of $22.4 million for the construction of the second and third parts of the Greater Mussaiyab irrigation project. The first part was completed recently at a cost of $11.2 million.

The Greater Mussaiyab project is designed to irrigate about 216,529 acres of government-owned land between the Tigris and Euphrates rivers in the central part of the country.

The total land area will be distributed among small-holding farmers. Each family will receive a total of 41 acres free and a government grant of about $260 to help start the new farms.

The Mussaiyab project is designed so that farmers can cultivate their land intensively year round rather than having to rotate their crops as has been the custom in this area for centuries.

Atomic Energy Reactor Scheduled For India

The Foundation Company of Canada has been awarded a contract by the Atomic Energy of Canada, Ltd., to erect the first atomic energy reactor to be built in India.

Financed jointly by India and Canada, the reactor, for research and experimental work, will be built about seven miles from Bombay.

Scheduled for completion in 1958, work has already begun on site clearance for the plant. The reactor is being designed by the Shawinigan Engineering Co., Ltd., of Montreal.



Slotted Windbreak Protects Ships at Piers

Shipping in several French harbors is seriously inconvenienced and sometimes damaged by the high winds which periodically blow from the south. As a consequence various types of windbreaks have been tried to protect ships as they lie at the piers, and to shield the unloading cranes from the overturning forces. At Le Havre, following the capsizing of the old German passenger liner, "Europa" as it was being converted into the present "Liberte", a reinforced concrete wall, with a sloping face (suggestive of a dam spillway) was built alongside a slip where ships tie up (ENR Aug. 19, 1948, p. 98). Now, at Marseilles, a completely different, much less expensive type of windbreak has been installed along the roof of a pier shed, and is claimed to be equally effective.

The particular characteristic of the Marseilles windbreak is that it is slotted, permitting some of the wind to pass through, but at reduced velocity; the wind striking the windward face at 70 mph is said to have only a 15-mph velocity on the leeward side. The structure is built up of steel plates 15 in. wide and 18 ft long set horizontally with 36-in. openings between. The supporting framework, anchored to the roof of the pier shed, is so arranged as to make every alternate 18-ft length of wall into a buttress, the better to resist overturning. The total length of the windbreak is 380 ft and it is 65 ft high.

Apartment Building, Pittsburgh, Pa.

401 Shady Avenue

Contractor: Larson Construction Company,
300 Mt. Lebanon Blvd., Pittsburgh 34, Pa.

Structural steel and standard steel joists by American Bridge

AMBRIDGE STEEL JOISTS

save time

and money

for everyone!

The handsome new apartment building shown in the rendering above is another good example of steel-frame construction in combination with AmBridge Standard Steel Joists for all floor and roof supports.

Fabricated and erected by American Bridge for this strong, fireproof structure were 710 tons of structural steel and 809 tons of AmBridge Standard Steel Joists with accessories.

USS AmBridge Standard Steel Joists provide rigid, lightweight and economical construction suitable for any type of floor, roof and ceiling. The underslung and open-web design provides for maximum headroom and allows passage of pipes, ducts and conduits in any direction.

In floor construction, the ease and simplicity of handling this new-design steel joist reduce installation time to a minimum and permit other trades to begin work promptly. And for roof construction, it cuts the time required to put your structure under cover.

Fabricated and assembled on a modern production line basis to assure you a better product in faster time, USS Ambridge Steel Joists will enable you to build an economical structure without interruption of your schedule. For detailed information about the time- and money-saving advantages of these superior products on your next job, get in touch with our nearest office.

AMERICAN BRIDGE DIVISION, UNITED STATES STEEL CORPORATION • GENERAL OFFICES: 525 WILLIAM PENN PLACE, PITTSBURGH, PA.

Contracting Offices in: AMBRIDGE • ATLANTA • BALTIMORE • BIRMINGHAM • BOSTON • CHICAGO • CINCINNATI • CLEVELAND • DALLAS • DENVER • DETROIT • ELMIRA • GARY HOUSTON • LOS ANGELES • MEMPHIS • MINNEAPOLIS • NEW YORK • ORANGE, TEXAS • PHILADELPHIA • PITTSBURGH • PORTLAND, ORE. • ROANOKE • ST. LOUIS • SAN FRANCISCO • TRENTON

UNITED STATES STEEL EXPORT COMPANY, NEW YORK

AMBRIDGE STEEL JOISTS

USS

UNITED STATES STEEL



A NEW USF PRODUCT... *Leave-In-Place*

STEEL FORMS

FOR CONCRETE BRIDGE FLOORS

Bridge on U. S. Route 13 over Pennsylvania R.R. Tracks near Morrisville, Bucks County, Penna.

Investigate this new USF Leave-In-Place steel form for concrete bridge floors. Made of galvanized steel, trapezoidally corrugated in laying widths approximating 24" for clamping direct to structural flanges, it particularly adapts itself to structures involving high or hazardous conditions. Permits all form work from top-side and eliminates shoring and stripping of old-fashioned wood forms. Once in, you leave-in-place. Low cost—to be sure!

- **Erect fast—Leave-In-Place**
- **Eliminate shoring and removal expenses**
- **No warping, cracking, shrinking, or swelling**
- **Save manhours and material waste**
- **Speed-up schedules—save dollars and penalties**

Write for data sheet now

USF UNITED STEEL FABRICATORS, INC.

WOOSTER, OHIO

USS STEEL

PRODUCTS | Hollow Metal Doors • Prefabricated Metal Buildings • Window Wells
Highway Guard Rail • Bridge Flooring • Corrugated Metal Pipe
Sectional Plate Pipe and Pipe Arches

Books

Miscellaneous Notes

• **Asphalt**—Out of the first Western Conference on Asphalt in Hydraulics, held last year at the University of Utah, comes a booklet for engineers and contractors containing research information and practical applications of asphalt in hydraulic installations.

The 247-page bulletin can be obtained from the College of Engineering Department of Civil Engineering, University of Utah, Salt Lake City, Utah. Price is $2.75.

• **Waste water**—A 90-page report covering the second year of studies of reclamation and utilization of waste waters for the State of California has been released. The studies were carried out by the Sanitary Engineering Research Laboratory of the University of Southern California for the State Water Pollution Board. Copies of the report, Publication 15, may be had for $1.45 by writing the State Printing Division, Documents Section, Sacramento 14, Calif.

• **ASTM standards**—This compilation of ASTM Standards includes the latest editions of standard and tentative specifications, test methods, and definitions of terms pertaining to mineral aggregates, concrete and selected highway materials. The publication is sponsored by Committee C-9 on Concrete and Concrete Aggregates and Committee D-4 on Road and Paving Materials, and includes all standards for concrete and concrete aggregates prepared by Committee C-9, but only those for selected nonbituminous highway materials or those involving aggregate gradings or tests developed by Committee D-4. It also contains pertinent specifications for cement under the jurisdiction of Committee C-1 on Cement.

This 360-page book contains 98 standards in their latest forms. Copies may be obtained from ASTM Headquarters, 1916 Race St. Philadelphia 3, Pa. at $3.75 each.

New Engineering Books

SURVEYING INSTRUMENTS AND METHODS—by Philip Kissam. 482 pp. Second Edition. McGraw-Hill Book Co., 330 West 42nd St., New York 36. $5.75.

THE THEORY OF SOUND—Volume I—by Lord Rayleigh. 480 pp. Dover Publications, Inc., 920 Broadway, New York 10. $1.95.

THE THEORY OF SOUND—Volume II—by Lord Rayleigh. 504 pp. Dover Publications, Inc., 920 Broadway, New York 10. $1.95.

Rome 14 hrs. 15 min.
Johannesburg 53 hrs. 55 min.
Tokyo via North Pole 32 hrs.
Fairbanks (Alaska) 14 hrs. 30 min.
6 hrs.
Los Angeles Arctic routing 22 hrs.
Los Angeles via New York 36 hrs. 20 min.
New York 22 hrs. 55 min.
Santiago de Chile 74 hrs. 25 min.
Madrid 14 hrs.
London 8 hrs.
Paris 12 hrs.

distance makes no difference...

Remote as your overseas business may be, its insurance protection through AFIA is serviced by a nearby office whose personnel know local conditions, laws and regulations and apply them for your security.

It's one of the big pluses you get when you insure through AFIA. Then you have more than 600 offices and agencies in 63 foreign lands constantly ready and willing to help you with your foreign insurance problems and the settlement of claims—the same type of service you expect on "Main St., U.S.A.".

Ask your local insurance agent or broker to consult AFIA on all foreign insurance problems.

AFIA

AMERICAN FOREIGN INSURANCE ASSOCIATION

161 William Street • New York 38, New York

CHICAGO OFFICE . Insurance Exchange Building, 175 West Jackson Blvd., Chicago 4, Illinois
DALLAS OFFICE . . . . . Vaughn Building, 1710 Commerce Street, Dallas 1, Texas
LOS ANGELES OFFICE . . . . . 3277 Wilshire Boulevard, Los Angeles 5, California
SAN FRANCISCO OFFICE . Russ Building, 235 Montgomery Street, San Francisco 4, California
WASHINGTON OFFICE . . Woodward Building, 733 15th Street, N.W., Washington 5, D.C.

An association of 22 American capital stock fire, marine, casualty and surety insurance companies providing insurance protection in foreign lands

Heltzel Portable Batchmaster

Every

JOB SITE *combination plants, designed to give you every batching advantage at the job location. They will cut truck time and wear enough to pay for themselves.*

READY-MIX *plants ideal for decentralization —spotting at new housing developments, etc.*

PIPE OR BLOCK *plants for job size concrete products manufacture; new business or auxiliary production.*

Plants for...

Purpose

***PAVING** plants — both aggregate and cement —that have proved themselves to be the finest yet engineered. True portability, plus unmatched speed and accuracy.*

HELTZEL PORTABLE BATCHMASTERS ARE SETTING PRODUCTION, ECONOMY RECORDS WHEREVER CONCRETE IS BATCHED

● Heltzel designs and builds the most complete line of portable plants in the industry. There's a plant of every size for every type batching. From the small 30 ton Highway Plant to the big 200 ton Paving Plants—for straight cement, straight aggregate or combinations—every Heltzel Batchmaster Portable is designed to go up fast and dismantle easily, with a minimum crew. They are sectionalized to be carried over the roads on standard carry-all equipment.

Don't buy any plant until you have talked with the owner of one of these new Batchmasters, for true portability is but one of many new features that make the Heltzel 1956 Line the fastest, most accurate and flexible plants on the market. And remember Batchmasters cost no more—so why not operate with the finest.

HELTZEL

BATCHING PLANTS

THE HELTZEL STEEL FORM AND IRON COMPANY
89812 THOMAS ROAD
WARREN, OHIO

9896



Tractair, equipped with front-end loader, provides air power for Le Roi-Cleveland paving breakers.

Combination Tractor-Compressor Unit Works 8-hour Day, All Year Long

One Le Roi Tractair (combination tractor-compressor unit) can do the work of several specialized machines — plus supplying 125-cfm air power for a wide variety of air tools. Because Tractair is a combination 42-hp wheel tractor and a dependable air compressor, here's what can happen on your jobs — in one day — using just one of the many Tractair attachments available:



Broken concrete is loaded out by the Tractair with front-end loader attachment.

Backfill blade easily replaces Tractair front-end loader bucket for light-grading work.

7:00 A. M. Tractair, equipped with a front-end loader, arrives at the job site. Le Roi-Cleveland pavement breaker powered by the Tractair's 125-cfm air compressor breaks concrete.

7:56 A. M. With the front-end loader attachment, the Tractair loads out broken concrete from the trench site.

8:39 A. M. Le Roi-Cleveland clay spades, powered by the Tractair compressor, trim up the excavation for pipe laying.

9:58 A. M. The operator drives the Tractair to another job to provide power for pumping out a water-filled trench.

11:00 A. M. Returning to the first job, the Tractair fills in the trench with its front-end loader.

11:30 A. M. The Tractair compressor provides air power for Le Roi-Cleveland tampers to compact the trench fill.

1:00 P. M. Using the front-end loader attachment, the Tractair loads out excess dirt into a truck.

1:20 P. M. The self-propelled Tractair proceeds to another job site and provides air power for rock drilling.

2:42 P. M. After rock has been blasted out, the Tractair 125-cfm air compressor provides air power for Le Roi-Cleveland breakers to trim up the hole.

4:05 P. M. With the crane boom on the front-end loader, the Tractair lifts and lowers heavy pipe into the trench.

4:45 P. M. The Tractair loads out debris to leave the work area clean and safe.

Yes, the Le Roi Tractair can give you performance like this around the clock — on all of your jobs. Applications are unlimited with Le Roi Tractair attachments. For example, the front-end loader attachment has many quick-change accessories — utility platform, fork lift, straight backfill blade, combination bucket and crane boom, crane lift, and several snow removal tools. Other attachments for the Le Roi Tractair are the backhoe, earth auger, rotary sweeper, backfill blade, snow blades, and many more.

Le Roi Division of Westinghouse Air Brake Co., Milwaukee 1, Wis. also manufactures portable and stationary air compressors, air tools, and heavy-duty engines. Write today for information about any of these products.

Local Custom and Usage May Be Part of Contract

Contracts are governed by the law of the state in which performed even though executed in another state. The custom and usage of the state of performance may be used to explain the intent of a contract but not to vary its terms.

The point is illustrated by a federal case that arose in Texas over the method of measuring, for the purposes of payment, the quantity of crushed rock used on a job.

In that case Edward E. Morgan Co., Inc. and Jones & Gillis, Inc., prime contractors, entered into a contract with the United States Government for construction of a runway, taxiway and parking lot extensions at an air base located in Texas. The work was to be performed on a unit price basis. Included in the work was the installation of a crushed stone base course requiring an estimated 30,500 cubic yards of crushed stone.

The prime contract contained the following provision: "The unit of measurement for base course shall be the cubic yard, measured in place and computed by the average end-area method, for the quantity of completed and accepted base course as determined by the contracting officer."

W. O. Pelphrey, a subcontractor, submitted an offer by letter, whereby he agreed to furnish in accordance with the specifications all equipment, tools, labor, and incidentals necessary to excavate and crush a minimum of 40,000 cubic yards of Edwards Limestone.

The offer was accepted by the prime contractors. The letter of acceptance contained the following notation: "You will also be governed by the same regulations as to wages, etc., that we are under the terms of our contract."

Although not mentioned in either the letter of offer by the subcontractor or in the letter of acceptance by the prime contractors, some of the rock crushed by the subcontractor was used for extra work. The prime contractors employed another subcontractor to haul the rock crushed by Pelphrey to the site in dump trucks. The amount of rock so hauled amounted to 47,980 cubic yards. The hauling subcontractor was paid on this basis.

The work of the subcontractor was completed on July 11, 1953. On July 24, 1953, he billed the prime contractors with mining and crushing 47,980 cubic yards. The army engineers estimated that the total amount of crushed stone in place, which was the basis of payment to the prime contractor, amounted to 33,602 cubic yards. The prime contractors contended that the subcontractor who had furnished the crushed stone was entitled to payment for only that amount. Payment was tendered on this basis. Subsequently, the prime contractors offered payment based on 40,000 cubic yards of crushed stone, the minimum quantity specified in the letter of agreement. The tender was refused by the subcontractor who brought an action to recover the balance he claimed was due. The subcontractor obtained a judgment at the trial and the judgment was affirmed on appeal.[1]

The contract in question was entered into in Mississippi but was to be performed in Texas. The court held that where a contract is made in one state and is to be performed wholly in another state, the law of the state where the contract is to be performed governs.

The court held that the contract provision to the effect that the work would be performed in accordance with the specifications, related solely to the manner of the performance of the work, and not the manner of measuring the quantity of rock delivered by the subcontractor, nor the basis for computing the amount to be paid him, and did not incorporate into the subcontract the prime contract provisions for measurement of the crushed rock.

The prime contractors at the trial objected to the admission of testimony to show the usage or custom of measuring rock. The court held that while custom or usage will not be permitted to vary the terms of a written contract, in the instant case, where neither the letter of proposal nor the letter of acceptance specifically provided that the quantity of crushed stone should be determined by measurement in place by the United States engineers, it was proper to permit the subcontractor to offer evidence to show that in Texas it was the usual custom and usage to pay for rock by loose truck measurements.

(1) Edward E. Morgan Co., Inc. et al. v. United States, 230 F. 2d 896, U.S. District Court of Texas, Feb. 23, 1956.

(These summaries of court decisions are prepared by I. Vernon Werbin, New York attorney and civil engineer.)

construction
STEEL
EVERY KIND IN STOCK
IMMEDIATE SHIPMENT
REINFORCING BARS and accessories
STRUCTURALS—channels, angles, beams, etc.
PLATES—many types including Inland 4-Way Safety Plate
SHEETS—many types & coatings
TUBING—incl. welded structural
WIRE MESH—all standard sizes
EXPANDED METAL—std. & flattened
STEEL SPIRALS, CAISSON RINGS, ETC.
RYERSON
Joseph T. Ryerson & Son, Inc. Plants at:
New York • Boston • Wallingford, Conn.
Philadelphia • Charlotte, N. C. • Cincinnati
Cleveland • Detroit • Pittsburgh • Buffalo
Chicago • Milwaukee • St. Louis • Los Angeles • San Francisco • Spokane • Seattle





RIVERS? Nothing to 'em!

with

CLOW CAST IRON
Ball-and-Socket
RIVER-CROSSING PIPE

Faster, Simpler Installation



Longer laying lengths, fewer joints. Shorter lengths to exact dimension.

Full Flow at Full Deflection



Full 15° turning deflection. No restriction of the waterway.

Fewer Parts No Split Parts

Needs only a ratchet wrench for fast, firm assembly.



Clow Ball-and-Socket River-Crossing Cast Iron Pipe makes crossing rivers a "snap." It is as easy to lay as standard flange joint pipe, and longer laying lengths—with no split parts—reduce time, labor, costs.

There is absolutely no reduction in the full internal opening area . . . no abnormal pressure-drops at deflected joints. Deflected stresses are evenly distributed among all the bolts.

Write today for complete information. No obligation, of course.

JAMES B. CLOW & SONS Inc.
201-299 North Talman Ave. • Chicago 80, Illinois

SINCE 1878

Subsidiaries: Eddy Valve Company, Waterford, New York • Iowa Valve Company, Oskaloosa, Iowa

Field and Office



Drawings Inserted as Windows In Computer Punch Cards

The Army's Signal Corps has embarked on a program of microfilming all of its engineering drawings and then inserting them as "windows" in regular electronic computer punch cards. Sets of the cards are then distributed to the various Signal Corps installations throughout the world and can be used directly for reproduction of full- or reduced-size drawings.

The punch cards are produced using special reading and transparency mounting machines and standard electronic duplicators and verifiers. Filing is accomplished by standard punch card sorters.

The Signal Corps has already microfilmed more than 300,000 engineering drawings and anticipates making 5 million cards to provide the necessary duplicate sets. Drawings are generally used for equipment procurement purposes. Previously, Signal Corps installations



Big Slag Pot Casting

One of the largest slag pots ever made, a 480-cu-ft-capacity 47,000-lb pot has been cast by the Blaw-Knox Co., in Pittsburgh. It is a single casting that includes the flat bottom and three trunnions on either side. Most flat-bottom pots in service have bottom plates bolted to the cast steel body of the pot. Trunnions are normally found on slag pot cradles, rather than on the pot itself.

Light aluminum overcoat for industrial buildings . . . laughs at weather . . . jeers at high costs

The sides and roof of your building may never have to support 1,200 pounds of ice, a five-foot snowman and a pretty girl in an area of 61½ square feet. But that will give you some idea as to the remarkable load-bearing capacity of Alcoa's exclusive new Aluminum V-Beam Industrial Roofing and Siding.

This unusual strength of Alcoa® V-Beam, plus its 18-foot length, means major savings in industrial construction. Why? Because less structural steel is needed. Because erection is faster. Because fewer of these bigger sheets are needed. Because there is less waste in side and end laps.

Warehouses, factories, storage sheds . . . any buildings . . . can be roofed or sided for as little as 65 cents a square foot . . . and with all of the long-term advantages only aluminum offers.

You get lower maintenance costs . . . so low they almost vanish! No painting. No rotting. No red rusting. No damage from salt air, industrial fumes or other harmful conditions. Twenty-five years of application in industrial areas proves this.

When new plant recommendations are called for, make certain that use of Alcoa's new 18-foot V-Beam sheet has been investigated. Aluminum Company of America, 860-L Alcoa Building, Pittsburgh 19, Pennsylvania.

THE ALCOA HOUR
TELEVISION'S FINEST LIVE DRAMA
ALTERNATE SUNDAY EVENINGS

Your Guide to the Best in Aluminum Value

WE CHOSE
ALCOA
ALUMINUM
BUILDING SHEET



New office building of General Telephone Company of the Southwest, San Angelo, Texas. Pace Associates, Architects; Evans & Taylor, General Contractor; Bollinger & Sames, Plumbing & Heating Contractor.

SMOOTH EFFICIENCY IN AIR HANDLING!

Inlet side of one of the five "Buffalo" Type BL Fans in the new building. Note the smoothly curving inlet bell and directional inlet vanes for quiet, efficient entry of air. Rotor has curved flange matching inlet, and backward curved blades for matchless performance. For full details, write for Bulletin F-100.

8 "BUFFALO" FANS MOVE THE AIR IN THIS PRIZE-WINNING TELEPHONE BUILDING

It is no coincidence that this new General Telephone Company of the Southwest Building was a prizewinner in the American Institute of Architects competition for 1955 — its low, sweeping lines blend well with the finest residential style. And it is no coincidence that "Buffalo" Fans were selected for its air moving jobs — and that complete satisfaction is reported by owner and contractors alike.

For ventilation and air conditioning supply, two "Buffalo" Belted Vent Sets, and five "Buffalo" Type BL Ventilating Fans are giving quiet, efficient service. Dependable induced draft is supplied by a "Buffalo" Type MW Industrial Exhauster.

Assure the greatest satisfaction on your next job by specifying "Buffalo", the fans with the "Q" Factor* — as leading contractors, engineers and owners have been doing for the past 79 years.

**The "Q" Factor — the built-in Quality which provides trouble-free satisfaction and long life.*

"Buffalo"

BUFFALO FORGE COMPANY

BUFFALO, N. Y.

Canadian Blower & Forge Co., Ltd., Kitchener, Ont.

VENTILATING AIR CLEANING AIR TEMPERING INDUCED DRAFT EXHAUSTING
FORCED DRAFT COOLING HEATING PRESSURE BLOWING

often had to send to central headquarters for drawings, thereby delaying the purchasing procedure.

The Recordak Corp., New York, supplied the microfilm machines, the reading machines which enable punch card operators to produce master cards, and the mounting machines for attaching the microfilmed drawings to the punch cards.

How to Compute Reinforcing For Oversize Columns

For architectural reasons, reinforced concrete tied columns in buildings must often be larger in cross section than required by structural and loading considerations. For such cases the American Concrete Institute building code (ACI 318-56), which was approved last April, allows the vertical reinforcement, p_s, to be less than 1% of the gross column area, A_g, but not less than four No. 5 bars.

Section 1104 (d) of that code states: "In a tied column which for architectural reasons has a larger cross section than required for considerations of loading, a reduced effective area, A_g, not less than one-half of the total area may be used in applying the provisions of Section 1104 (a)." Since, in the writer's experience, this section often causes confusion among practicing engineers and students, the design requirements can be expressed in simple algebraic terms as follows:

$$P = A_g (0.18 f'_c + 0.80 f_s p_g) \qquad (1)$$

where P is the allowable axial load on a column whose length does not exceed ten times its least cross-section dimension, f'_c the 28-day compressive strength of the concrete and f_s the allowable tensile unit stress in the steel.

If P_u is the load actually applied to the column and A_{gc}, the gross area of the column that would be theoretically sufficient to take P_u if $p_s = 0$, then when P_u is equal to or less than $A_g (0.18 f'_c)$:

$$A_{gc} = \frac{P_u}{0.18 f'_c} \qquad (2)$$

The minimum required vertical column reinforcement is therefore:

$$A_s = 0.01 A_{gc} = \frac{P_u}{18 f'_c} \qquad (3)$$

or

$$A_s = 0.01 \left(\frac{A_g}{2} \right) \qquad (4)$$

or four No. 5 bars, whichever is greater.

When P_u exceeds $A_g (0.18 f'_c)$, use Eq. 1 in which p_s shall not be less than 1%, nor more than 4% of A_g.— ZACHARY SHERMAN, ASSOCIATE PROFESSOR OF CIVIL ENGINEERING, UNIVERSITY OF MISSISSIPPI.

UNIVERSAL PRODUCTS
for highway construction





DOWEL BASKET ASSEMBLIES

Universal Dowel Basket Assemblies are designed and fabricated to specifications. Special equipment and fixtures guarantee accurate spacing and positive alignment of dowels. High speed production equipment and modern facilities insure prompt delivery of your requirements. Universal Baskets are approved by Federal, State and private authorities for highway and airport construction.

Let us quote on your requirements. Write for complete details today.

INDIVIDUAL DOWEL CHAIRS

Two-legged dowel chair holds dowel in 2 positions. Easily pushed into sub-grade—won't turn after installation. Wide range of heights.

Single Leg Dowel Chair permits quick snap-in of Dowel. Sizes to support Dowel from 3" to 6" above sub-grade.

STAKE PINS

Keep Dowel Bar Assemblies in place during the pour. Lengths from 4" to 15" in ¼" increments.

DOWEL SLEEVES

Metal Dowel Sleeves for covering ¾" Dowel Bars; overall length covers 2½" or 3" Dowel. Special sizes and lengths available.

HOOK BOLT ASSEMBLY

For providing required tie-ing element along longitudinal joint. Eliminates necessity of bending tie bars or drilling road forms.

UNIVERSAL FORM CLAMP CO.

GENERAL OFFICES AND FACTORY: 1238 N. KOSTNER • CHICAGO 51, ILLINOIS

OFFICES AND WAREHOUSES:
CLEVELAND, OHIO, 24901 Lakeland Blvd. • BALTIMORE, MD., 1020 N. Kresson St.
HOUSTON, TEXAS, 2314 Preston Ave. • SAN LEANDRO, CALIF., 2051-9 Williams St.
LOS ANGELES, CALIF., 5855 South Western Ave. • ATLANTA, GA., 1401 Howell Mill Rd.
DISTRIBUTORS IN PRINCIPAL CITIES

Service Wherever You Build... Coast to Coast

Copyright 1955 by UNIVERSAL FORM CLAMP CO., Chicago 51, Ill.

EASY, PROVEN WAY
to PERMANENTLY BOND
CONCRETE TO CONCRETE
WELD-CRETE®

Weld-Crete is the amazing liquid bonding agent which enables you to *permanently* bond new concrete *directly* to old concrete . . . or to most any other structurally sound surface . . . *without need for costly, time-consuming chipping, drilling, roughening, acid washing or scarifying of concrete base.*

Weld-Crete has equal bonding permanence all climates, all surfaces, all sorts of conditions. When used with quick setting cement topping you can lay new floors, ramps, driveways, etc. one day and run heavy truck traffic over them the next. Get facts from your building materials supply dealer or write Larsen Products Corp., Box 5756-I, Bethesda, Md.

TYPICAL **WELD-CRETE** APPLICATION

National Brick Co., Terra Cotta, D.C.

Here Weld-Crete was used to bond new ¾" concrete topping directly to old, badly chipped and spalled floor slab which had been subjected to ceaseless heavy truck traffic. Plant shut-down time eliminated as Weld-Crete enabled National's own mechanics to do job over week end.

From our
50th Anniversary Album

1st NATIONAL BANK, Allentown
Shored up old bldg., lowered foundation 6' while doing foundation work for new bldg.

UNDERPINNING AND FOUNDATION CO.
Service Experience

✓PILING ✓FOUNDATIONS
✓SHORING ✓UNDERPINNING
✓CONSULTATION & DESIGN

UNDERPINNING & FOUNDATION CO., INC.
155 E. 44th St., New York 17, N. Y.
General Contractors for 50 Years
Inquiries are invited—no obligation

Unit Prices

Wyoming I-Beam Bridge and Highway Cost $631,452

A new 444-ft six-span steel I-beam bridge with 1.583 miles of approaches and highway will replace an old structure over Snake River in Grand Teton National Park near Moose, Wyoming. The contract let by the Bureau of Public Roads, Denver, Colorado, requires that the substructure be completed before spring runoff. Otto T. Kuehster of the BPR, Moran, Wyo., is engineer.

Two 50-ft spans, two of 75 ft and two of 95 ft carry a 28-ft roadway, a 10-ft bridle path and a 4-ft 7-in. sidewalk. The 4-in. to 5½-in. bituminous stabilized surfacing on highway and approaches is placed on a crushed gravel or stone base. The graded width is 32 to 36 ft and the base width 20 to 24 ft.

The $631,452 contract awarded to Etlin E. Peterson, Casper, Wyo., breaks down like this: 24.5% for concrete, 21.5% for structural steel, 17.5% for excavation, and the remaining 36.5% for paving, topsoil, culverts, railing, the removal of the old bridge and miscellaneous work. The contract price is 10% above the engineer's estimate, but the low bids on excavation and structural steel pushed the total down to 2.6% below the second low of four bids.

Structural steel drew bids from a low of $0.24 to a high of $0.312 per lb. Concrete was bid $76 to $90 per cu yd of class A concrete with a minimum of 6.5 bags of cement and $52 to $82 per cu yd of class S concrete with a minimum of seven bags of cement per cu yd. The contractor bid $82 on both classes. Bid prices on excavation ranged from $0.675 to $1.00 per cu yd of unclassified and from $12 to $15.50 for unclassified excavation for structures.

Minimum wage rates are $1.80 for common labor, $1.90 to $2.25 for semi-skilled and $2.25 to $3.05 for skilled labor.

The bidders include:

1C	Etlin E. Peterson, Casper, Wyo	$631,452
2	Chas. M. Smith, Thermopolis, Wyo	648,408
4	Long Const. Co., Inc., Billings, Mont	775,937
EE	Otto T. Kuehster, c/o BPR, Moran, Wyo	574,226

Bids: 9-13-56 Items	Unit	Quantity	Unit Prices 1C	2
Force, account wk, misc	cs	job	$3,000	$3,000
Topsoil, strip & store	cy	13,000	0.65	0.70
Exc, unclassif	cy	55,000	0.675	1.00
for struct	cy	3,000	12.00	15.50
for borrow, case 1	cy	55,000	0.675	1.00
Overhaul, 1,000 ft free haul	stay	340,000	0.02	0.01
special borrow, 1,000 ft free haul	cymi	45,000	0.20	0.15
Topsoil, replace	cy	73,000	0.80	0.80
Obliteration of old rdys to be paid as earned	cs	job	2,000	2,000
Water, embankment	unit	1,000	1.50	1.00
Water base course	unit	600	2.00	2.00
Water plant or plants, prov maint	ls	job	1,000	1,000
Roll, embankment	hr	500	13.00	9.00
base crse	hr	160	10.00	7.00
Subbase matl	t	19,000	0.95	1.50
Base crse, cr grav or cr stone, cl 2, grad d-1	t	18,500	1.40	2.00
Bit base, process	sy	84,000	0.16	0.25
Cutback, asph, MC, gr 0, 1, 2, or 3	gal	65,000	0.23	0.20
RC, gr 1 or 2	gal	7,000	0.30	0.23
Conc cl A, air-entrained conc, low-alkali cmt	cy	1,567	82.00	76.00
cl S, low-alkali cmt	cy	331	82.00	52.00
Steel, reinforc	lb	161,100	0.16	0.17
struct furn, fabr, erect railing	lb	564,700	0.24	0.24
Railing	lf	1,482	10.00	10.50
CMP, galv, culv, 18"	lf	300	7.00	7.00
24"	lf	224	8.00	9.00
Pipe end sect, met, 24"	ea	8	60.00	40.00
Curb & gutter, combn conc	lf	1,620	4.50	3.00
Curb, log, treat, 12"	lf	1,400	6.00	3.00
Sidewalk, conc	sy	650	7.00	7.00
bit	sy	1,300	3.00	2.00
Gd posts, timber, with reflect strips, treat, type 1	ea	40	10.00	10.00
Barrier posts, treated	ea	80	10.00	5.00
Topsoil, loamy, f & p	cy	4,800	3.00	1.00
Turf shoulders	unit	160	54.00	25.00
Remov Old Snake River bridge	ls	job	14,000	7,300

Time to complete: 300 calendar days.
Liquidated damages: $75 per day.
cs—contingent sum, MC—medium curing, RC—rapid curing.

Wide Bid Spread on Small Wyoming Diversion Channel

Nine bids for this 2,600-ft Meeteetse Draw diversion channel near Thermopolis, Wyoming, ranged from $4,040 to $14,020. The Bureau of Reclamation, Thermopolis, awarded the contract to Charles M. Smith who underbid the second low bid by 23.7% and the engineer's estimate by 17.55%. Theodore E. Mann and Amos H. Adams are construction engineer and acting construction engineer for the Thermopolis Bureau of Reclamation.

The channel is designed with low side core bank construction and a 10-ft high dike to divert floodwaters that would endanger existing canals.

Channel excavation drew bids from $0.30 to $0.95 per cu yd. Prices bid on water and moistening material for the core banks varied between $4.00 and $60 per M gal.

Wage rates specified for this job are $2.60 for skilled labor, $2.00 for semi-skilled and $1.50 for common labor.

The nine bidders include:

1C	Charles M. Smith, General Contractor, Thermopolis, Wyo	$4,040
2	Gordon M. Sykes, Basin, Wyo	5,295
9	Holm & Stebner, Powell, Wyo	14,020
EE	Theodore E. Mann, Thermopolis, Wyo	4,900

Bids: 9-18-56 Items	Unit	Quantity	Unit Prices 1C	2
Exc for diversion channel	cy	9,000	$0.30	$0.40
from borrow	cy	2,000	0.25	0.40
Core banks	cy	1,200	0.25	0.10
Overhaul	cymi	300	0.30	0.50
Water and moistening matl for core banks	Mgal	25	4.00	5.00
Riprap, local sandstone	cy	50	7.00	10.00

Time to complete: 90 calendar days
Liquidated damages: $5.00 per day

No "Cure-All," but...

Salinas, California, finds a single grade of Bitumuls® solves five paving maintenance problems

HERE'S A SITUATION common to most growing cities: annexation of outlying residential developments has vastly expanded the street maintenance job *without* materially increasing available funds. Annexation has not only added to the street mileage, but has "contributed" many sub-standard pavements to the street system, thus adding to the complexity of the job.

In an effort to solve this problem, these three Salinas men most directly concerned have worked together: Thomas A. Dunne, Director of Public Service; his assistant, Al Rossi; and Harry Adams, Maintenance Supt. Their search for simplicity and standardization led them to look for a versatile asphalt material that would do many jobs. They found it in Bitumuls SS-1, an asphalt emulsion that can be handled and used without heating, in small quantities or large.

Now, stored in a single 25,000-gallon tank, Bitumuls SS-1 is used for: Patching, Tack Coats, Prime, Seal Coats & Surface Treatments, and for Base Stabilization. In addition, Salinas City Forces can also use this same grade of Bitumuls for the new Slurry Sealing; and—at high dilution—for dust-laying on unpaved, outlying roads. All of these jobs can be done with existing equipment: a grader, a "Pulvimixer", a water wagon, two distributors, and a roller.

The obvious economies resulting from the use of this one material for all these jobs merit investigation by paving maintenance men everywhere, regardless of the size of their community.

There's a Bitumuls man near you who can supply details. *Call him, today, or write:* **American Bitumuls & Asphalt Co., 200 Bush St., San Francisco 20, Calif.**

See You at the Road Show, Chicago, Jan. 28-Feb. 2
Booths 23-24; Materials & Supplies Section



(Top), "PULVIMIXER" reworks old pavement that has been scarified and bladed in restabilization operation. Distributor applies Bitumuls at ¾ gal./sq. yd. per inch of depth. (Center), DISTRIBUTOR applies prime on a waterbound base, using Bitumuls SS-1 diluted (2 parts SS-1 to 1 part water) at 0.3 gal./sq. yd. of dilution. (Bottom), HERE'S A CLOSE-UP of the finished texture of a Bitumuls SS-1 Seal Coat pavement.

(Right), SALES ENGINEER Bob Ridell, far left, of American Bitumuls & Asphalt Co., discusses plans with Tom Dunne, Director of Public Service for Salinas, and his assistants. At far right is a partial view of the 25,000 gal. storage tank. (Below), EVEN SCHOOL YARDS are given stabilized bases with Bitumuls SS-1.

Materials and Labor Prices — Monthly Market Quotations by ENR Field Reporters

See following ENR issues for OTHER PRICES:

- Wood Products, Glass, Explosives, Chemicals: Last, Oct 18; Next, Nov 22
- Clay Products, Lime, Plaster, Paint, Roofing: Last, Oct 25; Next, Nov 29
- Wage Rates, Building Board, Lath, Insulation: Last, Nov 1; Next, Nov 29
- Cement, Aggregate, Ready-mixed Concrete, Asphalt: Last, Nov 8; Next, Dec 6

IRON AND STEEL PRODUCTS—PER 100 LBS. BASE MILL PRICES

	STRUCT SHAPES	PLATE CARBON STEEL	REINF BARS billet	RIVETS ½-in. structural	SHEET PILING Base	STEEL RAILS Per Net Ton Standard	STEEL RAILS Per Net Ton Light	TRACK SUPPLIES Angle Bars	TRACK SUPPLIES Std Spikes	TRACK SUPPLIES Tie Plates	TRACK SUPPLIES Track Bolts
Birmingham Area	$5.00	$4.85	$5.075	$10.85	.....	$101.50	$120.00	$6.35	$8.775	$6.025	.....
Chicago Area	5.00	4.85	5.075	10.85	$5.90	101.50	120.00	6.35	8.775	6.025	.....
Pittsburgh Area	5.00	4.85	5.075	10.85	5.90	101.50	120.00	6.35	8.775	6.025	$13.10
Buffalo Area	5.00	4.85	5.075	10.85	5.90	101.50	120.00	6.35	8.775	6.025	13.10
Cleveland	.....	.....	5.075	10.85	5.90	.....	.....	.....	.....	.....	13.10
Youngstown Area	.....	.....	5.075	.....	.....	.....	.....	.....	8.775	.....	.....
Geneva	5.00	4.85	5.175	.....	.....	.....	.....	.....	.....	.....	.....
Los Angeles	5.70	.....	5.775	.....	8.90	.....	.....	.....	8.775	.....	.....
Pueblo	.....	.....	.....	.....	.....	.....	.....	6.35	8.775	6.025	.....

IRON AND STEEL PRODUCTS—F.O.B. WAREHOUSE, PER 100 LBS., BASE PRICE

	STRUCTURAL SHAPES Per 100 lb. base price	REINFORCING BARS Per 100 lb., base price 5 tons to carload lot New billet	REINFORCING BARS Rail steel	EXPANDED METAL LATH Per 100 sq. yd., carload lots Std. diamond mesh, 3.4 lb.	EXPANDED METAL LATH Std. ribbed 3.4 lb.	WELDED FABRIC REINFORCING Per 100 sq ft., carload lots fob mill
Atlanta	$11.50	.....	$8.90[e]	$49.50	$54.00	
Baltimore	8.67	8.10[j]	.....	42.00	46.50	
Birmingham	8.05[t]	7.91[t]	7.91[t]	65.00[p]	71.00[p]	
Boston	8.90[a]	8.47	8.47	50.90	55.85	4 × 16 in., No. 5 & 10 wires—Joliet, Ill., Donora, Pa., Monessen, Pa. $3.66
Chicago	8.05	6.81[gu]	6.81[gu]	49.00[‡]	60.00[‡]	
Cincinnati	8.70[ak]	7.69[rs]	.....	45.00[mn]	49.50[mn]	4 × 12 in., No. 8 & 12 wires—Joliet, Ill., Donora, Pa., Monessen, Pa. $2.43
Cleveland	8.38	6.79[c]	.....	43.50[‡]	48.00[‡]	
Dallas	9.45	8.25	8.25	49.00	52.00	
Denver	9.60	8.45[c]	.....	57.00[n]	63.00[n]	8 × 8 in., No. 8 & 8 wires—Joliet, Ill., Donora, Pa., Monessen, Pa. $3.84
Detroit	8.55	8.13	.....	56.00	63.00	
Kansas City	8.87[a]	8.73	.....	49.00	60.00	
Los Angeles	8.70[fd]	7.35	.....	57.50	63.50	
Minneapolis	8.45[d]	8.76[b]	8.76[b]	45.00[o]	49.50[o]	
Montreal	8–8.75[fC/8.05–8.45A]	7.75/8.95[t]	7.75/8.95	65.70[A]	70.20[A]	
New Orleans	.....	7.65[akx]	.....	45.50	50.00	
New York	8.71	7.93[y]	7.93[y]	47.50[no]	54.50[no]	
Philadelphia	8.04	7.14	.....	42.50[‡]	47.00[‡]	
Pittsburgh	7.43	6.57[**]	.....	42.50	47.00	
St. Louis	8.48[s]	7.90[c]	7.90[c]	59.50[l]	61.50[l]	
San Francisco	8.95	8.90[f]	.....	47.50	53.00	
Seattle	9.15	8.35[e]	.....	62.00[nr]	68.00[nr]	
Toronto	8.45*	7.60	7.60	56.00[mq]	59.00[mq]	

EXTRAS, per cwt.—*Quantity: less than 700#, + 50¢; 700-1499#, + 25¢; 1500-7999#, + 10¢. *Size: #2 + $2.20; #3 + $1.10; #4 + 50¢; #5 + 62.5¢; #6, #7 + 45¢; #8, #9, #10, #11 + 35¢. *Bending: heavy, + 40¢; light, + $2 (except in New York City and surrounding metropolitan area where bending must be done on the job). *Engineering details and placing from designs by others: over 500 tons, + 45¢; 200-500 tons, + 80¢ but not over $4,500; 20-200 tons, + 60¢ but not over $2000; 5-20 tons, + 70¢ but not over $240; under 5 tons, + 85¢ but not over $70. *Design only: + 60¢.

Quantity extras, per cwt.: under 100#, + $8; 100-399#, + $6; 400-999#, + $3.50; 1000-1999#, + 1.00; 2000-4999#, base price; 5000-9999#, — 10¢; 10,000-19,999#, — 30¢; 20,000-29,999#, — 50¢; 30,000# and up, — 70¢.

*‡ Delivered *a 2000–9999# *b 10,000–15,999#, fob city *c 20 tons or over *d 10,000–19,999# *e Intermediate struct'l *f Incl. delivering in free zone *g CL *h list price; dominion tax exempt; add provincial and municipal taxes *i add dominion, provincial and municipal sales taxes *j Intermediate and hard grade *k fob city *l delivered; contractor to do unloading *m copper alloy *n LCL *o asphalt coated *p del. of 500 sq. yd. or more. *q 3 lb *r 2% off for cash *s 2,000–4,999# *t add 15¢ del. *u add 6.25¢ switch *v incl 15¢ del. *x add 5¢ switch *y add 30¢ del. *z add 10¢ del. *A American made. *C Canadian made. [** Aver. of Canadian & American.

PLUMBING, HEATING, WATER, SEWER AND DRAIN PIPE

	C. I. PIPE PRICE INDEX[a]	ASBESTOS CEMENT PIPE per lin. ft. f.o.b. city 6" Pr Cl. 150	ASBESTOS CEMENT PIPE per lin. ft. f.o.b. city 12" Sew Cl. 1	VITRIFIED SEWER PIPE Per foot, Delivered ASTM C13-44T std. 8 in. s.s.	std. 12 in. s.s.	24 in. ds.	38 in. ds.	CLAY DRAIN TILE ASTM C4-24 PER 1,000 ft., carload lots, f.o.b. 6 in.	8 in.	CONCRETE SEWER PIPE Per ft., delivered: ASTMC 14-41 12 in.	24 in.
Atlanta	123.5	$1.64	$2.68	$.55	$1.30	$4.95	$12.25	$225.00		$0.88m	$3.25m
Baltimore	132.9	1.64	2.46	.665	1.28	5.08e	12.71	187.80	$289.20	1.01	2.75m
Birmingham	119.0	1.64	2.68	.44	.81	3.55w	10.37w	260.00‡	440.00‡	1.90m	4.00
Boston	135.6	1.66	2.46	.788qrt	1.502qrt	6.211qrt		203.40r	312.60r	1.60mg	3.80mg
Chicago	133.4	1.64	2.46	.93m	1.78m	7.52m	21.16m	220.00n	330.00n	1.30	4.00
Cincinnati	128.2	1.66	2.55	.665t	1.282St	4.905t	12.50S	240.00	370.00	.85m	3.25m
Cleveland	134.2	1.66	2.55	.567e	1.0935e	4.545t	11.787t	149.40m	231.60m	.85m	3.50m
Dallas	130.5	1.66	2.80	.439	.799	4.00b	9.17b			.63	1.86
Denver	140.1	1.73	2.80	.47n	.84n	3.73n				.74m	2.50m
Detroit	134.5	1.66	2.55	.85	1.60	6.45	17.50	240.00m	370.00m	.95	3.82
Kansas City	131.1	1.66	2.55	.61	1.105	4.54	12.75	260.00	485.00	.90	2.90
Los Angeles	140.2	1.73	2.46	.74l	1.61l	6.42l	15.36l	228.20l	348.90l	1.02	3.02f
Minneapolis	142.0	1.68	2.68	.83mo	1.50mo	6.50mo				1.78A	5.74A
Montreal				1.02u	1.80u	6.30u	12.00u			1.17A	3.11f
New Orleans	126.1	1.64	2.68	.51	.925	5.18	.....	350.00p	550.00p	.75	2.50
New York	131.4	1.66	2.46	.99	1.88	7.37	19.06			1.50	3.00
Philadelphia	130.8	1.64	2.46	.65	1.25	4.95e	12.65e	300.00‡	350.00‡	1.60A	3.95A
Pittsburgh	135.3	1.66	2.46	.468m	.864m	3.86m	9.78m	152.00	244.00	1.05A	2.50A
St. Louis	129.6	1.64	2.55	.50	1.08	4.45	10.80	180.00l	380.00l	1.45l	3.10l
San Francisco	140.2	1.73	2.46	.74d	1.62d	6.59d	16.47d	320.00l	530.00l	1.05m	3.30m
Seattle	140.8	1.73	2.46	.66b	1.26b	6.34	17.90	205.00c		1.00t	3.10t
Toronto				.76	1.425	6.00		157.00	280.00	.87	3.05

*‡ Delivered. *a PRICE INDEXES for CENTRIFUGAL CAST IRON PIPE (Include carload freight allowed to city). These also serve as the HISTORICAL RECORD of THE $ PER NET TON PRICE of CLASS B, B&S, PIT CAST IRON PIPE. F.O.B. Foundry Price Indexes Birmingham, Ala., 119.0; Burlington, N. J., 127.8. *b Extra strength ASTM C 200-44T *c 4-in., $113 *d SS361-A *e 30-in. *f 21 in. *g culvert pipe; reinforced, ASTM C 76-41 *h reinforced, ASTM C 75-41 *i reinforced, ASTM C 76-37 *j centrifugun; no standard specs. in Canada. *k 2% off for cash *l fob plant *m truck delivery *n LCL delivered, fob truck *o listed price based on LCL (no min.) *p freight allowed to destination in city *q ASTM C 13-40 *r CL fob origin, freight allowed *s 2 ft lengths *t 3 ft lengths *u CESA A 80-1941 specs, used *v standard strength *w ss; add 20% for d.s.

*WROUGHT STEEL PIPE (Full standard weight) Discount from list; see footnote

	Mill	2½ & 3 in. Butt Weld† Black %	2½ & 3 in. Butt Weld† Galv. %	3½ to 6 in. Lap Weld† Black %	3½ to 6 in. Lap Weld† Galv. %
Lorain, Ohio		23.00	9.25	13.50b	+0.75d
Aliquippa, Pa.		23.00	9.25	7.50b	+11.25
Sparrows Pt., Md		23.00	9.25		
Benwood, W. Va.		23.00	4.75	13.50d	+0.75d
Youngstown, O.		23.00	4.75		
Indiana Harbor, Ind		22.00	3.75	12.50ab	+6.25a
Sharon, Pa.		23.00	4.75	13.50a	+4.25a
Wheatland, Pa.		23.00	5.75	11.75d	+2.50d
Etna, Pa.		23.00	9.25	11.75d	+2.50d
Fontana, Calif.		10.50b	+7.75b	1.00ab	+17.75ab

† Threaded and coupled. a 3½ to 4 in. b Continuous weld. d 5 and 6 in. d 6 in.

* WROUGHT STEEL PIPE: Deduct discounts shown above from the following standard list consumers carload prices to get mill price. List prices per ft. (based on approx. $200 per net ton): Butt Weld ⅛ in., 8½¢; ¼ in., 6¢; ⅜ in., 6¢; ½ in., 8½¢; ¾ in., 11½¢; 1 in., 17¢; 1¼ in., 23¢; 1½ in., 27½¢; 2 in., 37¢; 2½ in., 58½¢; 3 in., 78½¢. Lap Weld 3½ in., 92¢; 4 in., $1.09; 5 in., $1.48; 6 in., $1.92. Add freight rates plus 3% transportation tax to get destination price.

WROUGHT IRON PIPE: List prices per ft. same as for wrought steelpipe, but add following "discounts" to get Pittsburgh mill price: Butt Weld —1 in. black, + 65.54, galv. + 95.77; 1¼ in. black, + 65.54, galv. + 95.23, 1½ in. black, + 61.79 galv. + 91.22; Lap Weld —2½ in. to 3 in. black + 67.95 galv. + 95.77; 4½ in. to 6 in. black + 64.74 galv. + 90.68 Add freight rates plus 3% transportation tax to get destination price.

FOAMGLAS®

the cellular, stay-dry insulation

STAYS DRY—Here's how you can prove to yourself that FOAMGLAS does stay dry. Cut a piece from a FOAMGLAS sample. Place it in water. Note how its hermetically sealed glass cells keep it afloat. Weight it down for days, weeks or longer if you like. Remove the weight and it bobs back to the surface . . . proof that the sealed cells have absorbed no water—still have their original insulating efficiency.

Wet insulation is no insulation . . .

Prove to yourself that FOAMGLAS stays dry!

Send for a sample and test it!

Moisture conducts heat! When an insulation begins to absorb moisture, its efficiency nosedives. It's no longer an insulation.

That can't happen to FOAMGLAS. Every block of this unique insulating material is composed of millions of hermetically sealed glass cells. Each cell is an individual insulating unit . . . and each is watertight. Water and vapor are sealed out to insure constant insulating effectiveness.

In a few minutes, in your own office, *you* can prove to yourself that FOAMGLAS *stays dry*. Send today for a free sample and directions for simple "desk top tests" you can perform, as illustrated on this page. You'll soon see why it pays to insulate floors, walls, ceilings, roofs, piping and equipment with FOAMGLAS. You're assured constant, long-lasting insulating efficiency without the headache and expense of insulation replacement.

Vapor-proof

Strong and rigid

Inorganic and incombustible

Lightweight

Pittsburgh Corning Corporation

Dept. K-116, One Gateway Center, Pittsburgh 22, Pa.

In Canada: 57 Bloor Street West, Toronto, Ontario

also manufacturers of PC Glass Blocks



Steel Rising for Chicago Newsplant

If you're familiar with Chicago you'll quickly recognize this spot. That's the Chicago River in the foreground, and part of the well-known Wrigley Building appears at right.

Those steel beams and columns, fabricated and erected by Bethlehem, are part of what will soon be another Windy City landmark — the new Sun-Times newspaper plant. It will be a splendid structure, said to be the world's most modern of its type. Modern too is the use of high-strength structural bolts during erection, an advancement in which Bethlehem has been a pioneer.

The new newspaper plant will have ten acres of floor space. The structure will house executive, editorial and business offices, as well as new presses capable of rolling off 120,000 papers an hour. Total height of the building will be nine stories, with two of them below street level. Some upper floors will be available for rental to commercial tenants.

Owner: Field Enterprises, Inc.; Architect: Naess and Murphy; General Contractor: George A. Fuller Company.

BETHLEHEM STEEL COMPANY
BETHLEHEM, PA.

On the Pacific Coast Bethlehem products are sold by Bethlehem Pacific Coast Steel Corporation. Export Distributor: Bethlehem Steel Export Corporation

BETHLEHEM STEEL

BETHLEHEM STEEL

Bids Asked—Low Bidders—Contracts Awarded—First Section—

Compiled by Business News Department—Engineering News-Record, 330 W. 42nd St., New York 36, N. Y., ELSIE EAVES, Manager
J. A. MAHONEY, M. WETZEL, L. M. FELIX, M. E. SCIORRA, F. S. DEMBEK, Reports.
J. H. WEBBER, M. R. ROESSLER, E. R. HUBER, Statistics.

NEW ENGLAND

HEAVY CONSTRUCTION—BA

▲† **Mass., Falmouth** — DORMITORIES — BA 11/27 — U. S. Eng., 150 Causeway St., Boston, seven 3 story, 41x205 ft. brick veneer airmen's dormitories, Otis Air Force Base. ENG-19-016-57-96. $2,000,000-$2,250,000. Plans deposit $25. CD 10/31.

BUILDINGS—BA

▲ **Mass., Canton**—HIGH SCHOOL—BA 11/20—Town, High School Bldg. Comm., c/o Supt. Schools, High School, Canton, high school, Washington St. $1,600,000. Plans deposit $100. Collens, Willis & Beckonert, 20 Newbury St., Boston, archts. CD 4/4.

▲ **Connecticut**—HOUSING—BA 11/27—U. S. Eng., 150 Causeway St., Boston, Mass., 64-units Capehart Housing on site imprvs. Defense Area Simsbury, Plainville and East Windsor, ENG-19-016-57-27. $1,056,000. Plans deposit $10. CD 10/29.

HEAVY CONSTRUCTION—LB & CA

† **Davison Constr. Co., Inc.**, 1306A Elm St., Manchester, N. H., CA $922,000, hangar motor service shop, warehouse, paint, oil and dope storage bldg. for Air National Guard, Grenier Air Force Base, ENG-19-016-57-44, MANCHESTER, N. H. U. S. Eng., 150 Causeway St., Boston 14, Mass. Bids Sept. 27. CD 10/10, under LB.

▲ **MASSACHUSETTS**—Commonwealth of Mass., Dpt. P. Wks., 100 Nashua St., Boston,
Charles Capone Constr. Co., Inc., 850a Providence Hy., Dedham, Mass., LB $1,663,644, est. $1,560,000, reconstr. Sect. US Rte. 1, incl. 6 bridges, Providence Turnpike, Norwood and Westwood. Bids Oct. 30. CD 10/3.

▲ **MASSACHUSETTS**—Commonwealth of Mass., Dpt. P. Wks., 100 Nashua St., Boston,
J. F. Fitzgerald Constr. Co., 1000 Turnpike St., Canton, Mass., CA $1,799,973, est. $1,551,941, expressway highway exten., Rte. 128, Northern Circle Hy., FAP-U-331-12 and U-346-1, Gloucester. Bids Sept. 25. CD 9/27, under LB.

▲ **MASSACHUSETTS**—Commonwealth of Mass., Dpt. P. Wks., 100 Nashua St., Boston,
S & M Constr. Co., 30 Salmon St., Providence, R. I., LB $1,088,625, est. $1,200,000. constr. section Mid Cape Hy., incl. 3 span steel stringer bridges, Proj. 328 (6), Brewster and Orleans. Bids Oct. 30. CD 10/17.

BUILDINGS—LB & CA

Charles W. Howard & Son, Inc., 32 Summer St., Malden, Mass. Owner Builds. $700,000. 35 RESIDENCES, Dana Rd., READING, MASS.

▲ **George A. Fuller Co.**, 11 Beacon St., Boston, Mass. CA Exceed $4,000,000. HOME OFFICE, Rte. 128 and Lake Quannapowit, WAKEFIELD, MASS. American Mutual Liability Insurance Co., 142 Berkeley St., Boston, Mass. Bids Sept. 13. CD 9/12.

▲ **P. Francini & Co., Inc.**, Water St., Derby, Conn. LB $1,334,000. OCCUPATIONAL THERAPY BLDG., Fairfield State Hospital, NEWTOWN, CONN. State P. Wks. Dpt., 165 Capitol Ave., Hartford, Conn. Bids Oct. 31. CD 10/22.

Ernest F. Carlson, Inc., 1694 Main St., Springfield, Mass., CA Approx. $750,000. 55,000 sq. ft. MFG. PLANT and OFFICE, Quinnipiac Ave., NORTH HAVEN, CONN. Soundscriber Corp., 146 Munson St., New Haven, Conn. Leo F. Caproni, 132 Temple St., New Haven, Conn., archt. Awarded Oct. 22.

▲ **Anderson-Fair Oaks Constr. Co.**, 145 S. Marshall St., Hartford, Conn., LB $1,300,000 (3 bidders). Proj. BI-D-198, JUNIOR-SENIOR HIGH SCHOOL, University of Connecticut, STORRS, CONN. State P. Wks. Dpt., 165 Capitol Ave., Hartford, Conn. Bids Oct. 31. CD 10/2.

▲ **A. F. Peaslee, Inc.**, 37 Lewis St., Hartford, Conn., CA, $1,075,680, est. $1,000,000, Richmond Lane Elementary SCHOOL, Lost Brook and Barksdale Rds., WEST HARTFORD, CONN. Town, Bd. Educ., 7 Whiting Lane, West Hartford, Conn. Bids Oct. 10. CD 10/12, under LB.

MIDDLE ATLANTIC

BUILDINGS—BA

N. J., **Linden**—SCHOOL—BA 12/20—Bd. Educ., Linden Twp., Linden, Junior High School addn., Coke Place. $800,000. Albert A. Kauffman, 252 N. Broad St., Elizabeth, archt.

HEAVY CONSTRUCTION—LB & CA

▲† **Arundel Corp.**, foot of Fulton St., Brooklyn, N. Y., CA $1,675,920, dredging, rock removal to depth of 37 ft. below mean low water, incl. removal approx. 108,500 cu. yd. place, measurement, ledge rock, 51,600 cu. yd. place measurement of material other than ledge rock from New York and New Jersey Channels, Sect. 4, Rock Area 12, CIVENG-30-075-57-27, NEW YORK, U. S. Eng., 111 E. 16 St., New York 3, N. Y. Bids Oct. 9. CD 10/11, under LB.

PENNSYLVANIA—State Hy. Dpt., 506 N. Office Bldg., Harrisburg,
D. T. Connelly, Terminal Bldg., Greater Pittsburgh Airport, Coraopolis, Pa., CA $995,001, rein.-con. pavement 4.37 mi., 5 rein.-con. bridges widen existing pavement, misc. constr. TR 68, Butler Co. Bids Sept. 28. CD 10/3, under LB.

BUILDINGS—LB & CA

Sano Rubin Constr. Co., 616 Delaware Ave., Albany, N. Y., LB $695,900, general constr. DORMITORY, for State University of College for Teachers, ALBANY, N. Y. Dormitory Auth. of State of New York, 55 Grant Ave., Albany, N. Y. Bids Oct. 11. CD 9/27.

▲ **Kayfield Constr. Corp.**, 116-55 Queens Blvd., Forest Hills, N. Y., LB $1,679,000 (7 bidders) general constr. of new addn. to and modernizing existing JUNIOR HIGH SCHOOL 50, S. Third St. and Driggs Ave., BROOKLYN, N. Y. Director Bureau Constr., 42-15 Crescent St., Long Island City, 1, N. Y. Bids Oct. 30. CD 10/3.

▲ **William L. Crown Constr. Co.**, 101 Park Ave., New York 17, N. Y., CA, $2,347,427, addnl. 3 stories, and penthouse to existing REHABILITATION INSTITUTE, NEW YORK, N. Y. New York University-Bellevue Medical Center 34 St. and 1st Ave., New York, N. Y. CD 7/10.

▲ **Psaty & Furham, Inc.**, 369 Lexington Ave., New York 17, N. Y., CA $4,579,000, general constr. BRONX HIGH SCHOOL of SCIENCE, W. 205 St. and Goulden Ave., Bronx Boro, NEW YORK, N. Y. Grand total $6,903,675. Bureau Constr., 42-15 Crescent St., Long Island City 1, N. Y. Bids Oct. 23. CD 10/30, under LB;
Astrove Plumbing & Heating Corp., 36-14 32 St., Long Island City, N. Y. CA $546,000, plumbing work (New York, N. Y.);
H. Sand & Co., Inc., 11 Park Pl., New York 7, N. Y. CA $702,675, heating work (New York, N. Y.);
Rao Electrical Equipment Co., Inc., 314 E. 39 St., New York 16, N. Y. CA $1,076,000, electrical work (New York, N. Y.).

▲ **Lange-Finn Constr. Co.**, 522 Broadway, Albany, N. Y. LB $1,613,000 (12 bidders) general constr. Scotia HIGH SCHOOL, SCOTIA, N. Y. Bd. Educ., Central School Dist. 1, Scotia, N. Y. Sargent, Webster, Crenshaw & Folley, 2112 Erie Blvd. E., Syracuse 3, N. Y., archts. Bids Oct. 24. CD 1/29/53.

McManus, Longe Brockwehl, Inc., 65 Arcadia Ct., Colonie, N. Y., LB $735,600 (9 bidders) general constr. JUNIOR-SENIOR HIGH SCHOOL, VOORHEESVILLE, N. Y. Bd. Educ., Central School Dist. 1, Voorheesville, N. Y. August Lux & Assocs., 143 Washington Ave., Albany, N. Y., archts. Bids Oct. 18.

▲ **Darosam Building Co.**, Samuel Schultz, West End Ave., Madison, N. J. Owner Builds. $1,750,000. 55 HOUSES, West End Ave., Rosedale Village, FLORHAM PARK, N. J. W. Harold Lushear, 241 Woodland Rd., Madison, N. J., archt.

William Hunsinker, Woodport, Lake Hopatcong, N. J., CA $900,000. 45 HOMES, Vista Court, Alamac Country Club Estates, LAKE HOPATCONG, N. J. Fred Bischoff operating at Alamac Country Club Estates, Vista Court, Lake Hopatcong, N. J. Henry W. Vreeland, 4 Court St., Morristown, N. J., archt.

▲ **Edward M. Waldron Inc.**, 42 Park Place, Newark, N. J., CA, $1,051,537 7 story RESEARCH CENTER, Burnet St., NEWARK, N. J. St. Michaels Hospital, 306 High St., Newark, N. J. CD 5/9/55.

▲ **Harvey Guerin**, Fairmount Ave., Chester, N. J., Owner Builds, $2,100,000. 75 HOME development, Lindstroom Tract, Route 206, Hillsborough Twp., SOMERVILLE, N. J.

▲ **George H. Evans & Co.**, 1914 Spring Garden St., Phila., Pa., CA, $1,412,610, general constr. SENIOR HIGH SCHOOL, WAYNE, PA. School Dist. of Radnor Twp., Wayne, Pa. Bids Aug. 21. CD 9/6, under LB.

▲ **Joseph F. Nebel Co.**, 3408 Wisconsin Ave., N. W., CA, $2,260,000. HEADQUARTERS BLDG., Wisconsin Ave. N. W., WASH., D. C. Equitable Life Insurance Co., 816 14 St. N. W. Wash., D. C. Bids Sept. 13. CD 9/17, under LB.

PROJECTS COVERED

By Size

Construction projects here reported cover the United States and Canada, are of these minimum sizes or larger: water supply, earthwork, waterways $44,000; other public works $73,000; industrial buildings $93,000; other buildings $344,000. Also Foreign projects of $100,000 and more in size of interest to American contractors.

By Regions & Classes of Construction

(In order of Listing)

BIDS ASKED
LOW BIDDERS
CONTRACTS AWARDED

New England
Middle Atlantic
South
Middle West
West of Mississippi
Far West

PROPOSED WORK

Water Supply
Sewers, Waste Disposal
Bridges
Streets & Roads
Earthwork, Waterways
Public Buildings
Mass Housing
Commercial Buildings
Industrial Buildings
Unclassified

In These Stages

PROPOSED WORK: Before and including appointment of engineers or architects.
BIDS ASKED: BA (new announcements only). For full calendar, see also preceding issues.
SOON LETS CONTRACT: SLC
LOW BIDDERS: LB On jobs below $500,000 in value all low bidder news will be the final reports published on the projects involved except where award is not made to the low bidder. In this case, a supplementary contract award report will be published.
CONTRACTS AWARDED: CA Except awards to low bidders previously reported in low bidder stage.
CD dates shown are of Construction Daily Issue in which last previous report was published.
OWNERS, ENGINEERS, ARCHITECTS, CONTRACTORS are invited to report their new jobs for listing in these reports when they meet or exceed the size minimums shown above. Address these news releases to J. A. Mahoney, REPORTS, ENGINEERING NEWS-RECORD, 330 W. 42 St., New York 36, N. Y.

Symbols and Abbreviations Include:

† Federal Government
▲ Project of $1,000,000 or over.
ENR Engineering News-Record
CD Construction Daily
For additional reports see Construction Daily.

SOUTH

BUILDINGS—BA

▲ **N. C. Jacksonville**—HOUSING—BA 11/29—Officer in Charge of constr., Fifth Naval Dist., Attention Code DB-300, U. S. Naval Base, Norfolk, Va.; construct and finance, 435 housing units, Marine Corps Air Facility, New River, Inb. No. NBy (CH)-1717, Proj. 053-81001-MC-1. Est. $4,000,000. Plans deposit $265.

HEAVY CONSTRUCTION—LB & CA

▲ **VIRGINIA**—Commonwealth of Va., Dpt. Hys., Central Highway Office Bldg., 1221 E. Broad St., Richmond,
Leo Butler Co., 9217 51st Ave., College Park, Md., LB $4,063,041 (4 bidders) Contr. D-2 (Hampton Roads Proj.) constr. waterproofed depressed roadway with 4 overhead bridge structures and 3 buildings, 2 of which house storm water pumping stations and 1 of which houses sanitary sewage pumping station, incl. equip. 1.1 mi. between centerline Stations 1115 plus 00 to 1173 plus 00 in city of Norfolk. Bids Oct. 31. CD 10/10.

▲ **WEST VIRGINIA** — State Road Comm., Charleston, Zone 5,
Boso & Ritchie, Inc., Ravenswood, W. Va., CA, $1,289,880, grading, draining, base 5.864 mi. Philippi-Belington Rd., Proj. F-117 (7), Barbour Co. Bids Sept. 25, awarded Oct. 29. CD 10/1, under LB.

▲ **ALABAMA**—State Hy. Dpt., Montgomery,
Ala.—**J. & H. Excavating Co.**, 901 22 Ave., Tuscaloosa, Ala., LB $231,921 grading, draining 9.277 mi. from Ala. 25, Bibb and Shelby Counties; LB $77,673, bit. 3.811 mi. Tuscaloosa Co.;
Ala.—**A. E. Burgess Co., Inc.**, 3700 10 Ave. N., Birmingham, Ala., LB $1,125,729 grading, draining, Fed. Aid Proj. I 202 (3) (8), Jefferson and Blount Counties;
Ala.—**Bennett Constr. Co.**, 107 Stuart St., Montgomery, Ala., LB $264,352 grading, draining 4.398 mi. Houston and Dale Counties;
Ala.—**H. M. Plunkett Jr.**, Blountsville, Ala., LB $200,689, bit. 5.231 mi. Blount Co.;
Ala.—**Thomas A. White Constr. Co.**, 1600 Midway Ave., Mobile, Ala., LB $74,610, bit. 2.864 mi. Pleasant Valley Rd. Eatens, Mobile Co.;
Ala.—**Glencoe Paving Co., Inc.**, 515 Locust St., Gadsden, Ala., LB $149,798, crushing, stockpiling rock, Blount Co. Bids Oct. 26. CD 10/16.

BUILDINGS—LB & CA

▲ **Tower Constr. Co.**, 1726 L St. N.W., Wash., D. C., CA Est. $3,000,000-$4,000,000. SHOPPING CENTER, Rte. 460, Melrose Ave. between Roanoke and Salem, ROANOKE, VA. Giant Food Properties, Inc., 1726 L St. N.W., Wash., D. C., Joseph Saunders, 121 S. Columbus St., Alexandria, Va., archt.

▲ **Jack Culpepper Contractor**, 114 E. 5 Ave., Tallahassee, Fla., LB $1,091,400. Negro High & Elementary SCHOOL (colored) Ochlocknee Elementary SCHOOL (colored); Pavo-Coolidge Elementary SCHOOL (colored) new Union Elementary SCHOOL (colored) Boston SCHOOL, Elementary SCHOOL addns. mech. remodeling (colored) White High & Elementary SCHOOL, Thomas County, THOMASVILLE, GA. State School Bldg. Auth.,

Nonskid, light, corrosion resistant

Alcoa® Abrasive Tread Plate is a strong aluminum alloy with gritty aluminum oxide rolled into the surface.

It's so nonskid you can walk right up a 30° incline, even when it's wet, greasy or covered with oil!

This tread plate won't lose its grip. Wearing it down simply exposes more rolled-in grit! It's two-thirds lighter than steel. It comes in many sizes and thicknesses. It's easy to punch, cut, form, weld, shear, etc.

THINK—Where can you use this light, corrosion-resistant tread plate? It's ideal for factory floors, ladder treads, train vestibules, plates, truck trailers, marine decking, elevator floors and sills and many other uses. See your Alcoa distributor.

ALWAYS FASTEN ALUMINUM WITH ALCOA ALUMINUM FASTENERS

• • • • • • • • • • • • • • • • • • • •

GET FREE SAMPLE OF ALCOA TREAD PLATE AND FREE BOOK!

ALUMINUM COMPANY OF AMERICA
1666-L Alcoa Building, Pittsburgh 19, Pa.

Gentlemen: Please send free sample of *Alcoa Abrasive Tread Plate* and informative 8-page booklet.

Name _____ Title _____

Company _____

Address _____

City _____ Zone _____ State _____

ALCOA ALUMINUM MILL PRODUCTS

Your Guide to the Best in Aluminum Value

THE ALCOA HOUR
TELEVISION'S FINEST LIVE DRAMA
ALTERNATE SUNDAY EVENINGS

DUDGEON HYDRAULIC JACKS
SALES RENTALS
• CAPACITY TO 600 TONS
FOR:
PILE TESTING
•
UNDER-PINNING
•
BRIDGES
•
PIPE PUSHING
•
SOIL TESTING
Write to Dept. 56
RICHARD DUDGEON INC.
709 BERGEN ST. • ST 9-4040 • BROOKLYN, N. Y.

TEST BORINGS
for
• COAL
• MINERALS
• DAMS & BRIDGES
• BUILDINGS
We bore into the Earth
PENNSYLVANIA Drilling CO.
DRILLING CONTRACTORS AND MFRS.
PITTSBURGH 20, PA.

244 Washington St., S.W., Atlanta, Ga. Bids Oct. 30. CD 10/2.

▲ J. Mann, 1959 71 St., Miami Beach, Fla., CA, Approx. $1,000,000. 9 story in front, 4 story in rear, concrete block, rein.-con., El Chama HOTEL, Parker and Lafayette Sts., TAMPA, FLA. Lafayette Corp., c/o contractor. Norman M. Giller & Assocs., 420 Lincoln Rd., Miami Beach, Fla., archts. Morton R. Fellman, 145 S. W. 1 St., Miami, Fla., structural engr.

† Meisner & Hoff, 615 Allendale Ave., Gulfport, Miss. CA $905,400, THERAPEUTIC EXERCISE CLINIC BLDG. and utilities, Veterans Admin. Center, GULFPORT, MISS. Veterans Admin., Munitions Bldg., Wash., D. C. Bids Oct. 2. CD 10/8, under LB.

MIDDLE WEST

BUILDINGS—BA

O., Lincoln Heights—HIGH SCHOOL—BA 11/26—Bd. Educ., McGee St., 2 story, rein.-con. high school, McGee St. $750,000. Plans deposit $25. Sullivan-Isaacs-Sullivan & Assoc., 1800 Reading Rd., Reading, archts.-engrs. CD 4/4.

HEAVY CONSTRUCTION—LB & CA

The Horvitz Co., 4375 E. 146 St., Cleveland 28, O. LB $894,149, est. $1,013,000 (2 bidders) impr. Snow Rd. from State to Rockside, Parma and Seven Hills, CLEVELAND, O. Comrs. Cuyahoga Co., Court House Cleveland 13, O. Bids Oct. 29. CD 10/2.

▲ ILLINOIS—Illinois State Toll Highway Comn., 20 N. Wacker Dr., Chicago, Zone 6,
Ryan Constr. Co., Inc., 800 E. Michigan St., Evansville, Ind., CA $2,728,964. Contract N-4-A, 5.49 mi. paving, precast concrete bridges near Algonquin N. of Elgin, McHenry Co. Bids Oct. 4. CD 10/9, under LB.

▲† S. J. Groves & Sons Co., 500 Wesley Temple Bldg., Minneapolis, Minn., LB $2,409,950. 2nd phase, widening and dredging Calumet Sag Channel near Chicago, CIVENG-11-032-57-10, ILLINOIS. U. S. Eng. 475 Merchandise Mart, Chicago 54, Ill. Bids Oct. 17. CD 9/10.

BUILDINGS—LB & CA

▲ Al. Rockwell, Galbraith Rd., Cincinnati, O. Own Forces. $1,925,000, 35 HOMES, subdivision, east side of Ridge Ave., AMBERLEY VILLAGE, O. Numlist & Frolicher, Traction Bldg., Cincinnati, O., engrs. Awarded Oct. 29.

▲ Coleridge Development Co., c/o Jerome Moss, Citizens Bldg., Cleveland 14, O. Own Forces. $1,000,000. 65 HOMES 40-acre site, north of Rte. 84 in Painesville and Concord Twps., PAINESVILLE, O.

Hagerman Constr. Co., 403 Strauss Bldg., Fort Wayne, Ind., CA $828,000. 1 and 6 story, part bsmnt. STUDENT CHAPEL, VALPARAISO, IND. University of Valparaiso, Valparaiso, Ind. Bids Sept. 17. CD 9/27, under LB.

▲ Kinnare Corp., 2816 W. Monroe St., Chicago, Ill., CA, $2,000,000. 2 story Madonna HIGH SCHOOL, paving, parking area, Belmont and Karlov Sts., CHICAGO, ILL. Franciscan Sisters, 3150 N. Pulaski Rd., Chicago, Ill. Bids Oct. 16. CD 9/27.

▲ James McHugh Constr. Co., 6449 S. Park Ave., Chicago, Ill., LB $2,280,148. 4 story women's DORMITORY, bounded by Woodlawn, Kimbark, 58 and 59 Sts., CHICAGO, ILL. University of Chicago, 5801 S. Ellis Ave., Chicago, Ill. Bids Oct. 29. Eero Saarinen & Assoc., Bloomfield Hills, Mich., and J. Lee Jones, 1101 E. 58 St., Chicago, Ill., archts. CD 10/5.

▲ Taylor & Gaskin, Inc., 2201 Park Ave., Detroit, Mich. CA Est. $4,000,000. 1 story, structural steel Ford Assembly PLANT, CHICAGO, ILL. Ford Motor Co., P. O. Box 117, Dearborn, Mich. Bids Oct. 12. CD 10/1.

▲ Jenkins & Boller, 545 Benny St., Waukegan, Ill., CA $1,250,400 (a) Little Fort SCHOOL, Blanchard Rd. (b) Greenwood SCHOOL addn., North Ave. (c) Hyde Park SCHOOL addn., 1525 Hyde Park Ave. (d) Glenwood SCHOOL, Northmoor Ave. (e) Oakdale SCHOOL, McAree Rd., WAUKEGAN, ILL. School Dist. No. 61, 574 McAllister Ave., Waukegan, Ill. Bids Oct. 1. CD 9/12.

WEST OF MISSISSIPPI

BUILDINGS—BA

▲ Colo., Camp Carson—HOUSING—BA 12/21—U. S. Eng., 1709 Jackson St., Omaha, Neb. construct and finance permanent family housing, Inv. 25-066-57-9. CD 8/28, under LB.

HEAVY CONSTRUCTION—LB & CA

MINNESOTA—State Hy. Dpt., 1246 University Ave., St. Paul,
McLean-Astleford Co., Inc., 7701 Harriet Ave., Minneapolis, Minn., CA $605,130, grav. base, c. conc. pavement and bridge 0.5 mi. St. Louis Park and Golden Valley, Hennepin Co. Bids Sept. 28. CD 10/4, under LB.

▲ IOWA—State Hy. Comn., Ames,
Iowa—Cunningham-Reis Co., 440 Insurance Exchange Bldg., Des Moines, Iowa. LB $180,311. bridges, culverts UG 856 (4) Montgomery Co.;
Iowa—Iowa Bridge Co., 5770 2 St., Des Moines, Iowa, LB $171,156. bridges, culverts, IN-ING-853 (2) Polk Co.;
Iowa—The Gould Constr. Co., 507 Security Bldg., Davenport, Iowa. LB $90,432. bridges, culverts U-831 (4), Scott Co.;

(Continued on page 90)

KEEPING UP WITH THE JETS!



Creating a hangar, engineering a building, fabrication and construction—Luria provides all these services. Moreover, the unique Luria System of Pre-engineering



Willard Storage Battery Company

—producing *customized* structures from standardized components—successfully helps reduce the time and cost of building. Over 500 aircraft installations and thousands of orders and *reorders* from industry attest to that.

Hangars for aircraft...
Buildings for industry...
LURIA leads in both!

The Luria line is a *complete* line. For industry: flat-roofs, gable-roofs and crane buildings, all types, all sizes. And for military and commercial aviation: hangars, repair docks, work platforms, utility and terminal buildings.

If you are planning expansion now or in the future, the complete Luria story will certainly be of interest, and very likely,

Radio Corporation of America

of profit to you. Just contact your nearest Luria representative. It pays!

LURIA ENGINEERING Company

511 FIFTH AVENUE, NEW YORK 17, NEW YORK *Plants:* BETHLEHEM, PA. • CHICAGO HEIGHTS, ILL.
District Offices: ATLANTA, BOSTON, PHILADELPHIA, CHICAGO, WASHINGTON, D.C., RICHMOND, PITTSBURGH

Some recent users of Seismic Surveys

- Dam site investigation ..... Westminster, Mass.
- Building sites ..... Penn. State Univ., State College, Pa.
- Bridge site ..... Connecticut River, Hartford, Conn.
- Super highway Berkshire Extens., N. Y. State Thruway
- Dam site exploration ..... Delaware River
- Bridge site ... Newburgh-Beacon Bridge, Hudson River
- Aguado Anasco Hwy., & Guajataca Bridge, Puerto Rico
- Water supply ... Water Resources Authority, Puerto Rico
- Dam site ..... Dover, New Jersey
- Hurricane Barrier ..... Narrangansett Bay, R. I.
- Quarry exploration ..... Massachusetts
- Generating plant expansion site ... Staten Island, N. Y.
- Housing development site ..... Trumbull, Conn.

For a copy of our factual Bulletin 1, on seismic surveys, write to Geophysical Survey Division, Gahagan Dredging Corp., 90 Broad St., New York 4, N. Y.

Established in 1898. Gahagan is a leader in hydraulic dredging

ANOTHER
GAHAGAN
CASE HISTORY



EFCO FORMS
for house foundations

EFCO Steel Forms for concrete construction are adaptable to wide use by their owners, including construction of house foundations. Other advantages:

- **Lifetime steel faces should never need to be replaced.**
- **Easy to handle and assemble.**
- **Saves time, material, money.**
- **Low original cost.**

Other forms from Economy are available on a rental basis. Write nearest office for catalog.

Economy Forms Corp.
DES MOINES, IOWA

Offices in St. Louis, Mo.; Kansas City, Mo.; Lincoln, Nebr.; Minneapolis, Minn.; Ft. Wayne, Ind.; Milwaukee, Wis.; Chicago, Ill.; Cincinnati, Ohio; Cleveland, Ohio; Metuchen, N. J.; Rochester, N. Y.; Springfield, Mass.; Washington, D. C.; Decatur, Ga.; Charlotte, N. C.; Dallas, Texas; Tulsa, Okla.; Houston, Texas; Los Angeles, Cal.; Oakland, Cal.; Denver, Colo.

The BELMONT IRON WORKS

Engineers — Fabricators — Erectors
Contractors — Exporters
Cable address—Beliron

STRUCTURAL STEEL
BUILDINGS & BRIDGES
RIVETED — ARC WELDED

Shops: Eddystone, Pa.—Philadelphia, Pa. Royersford, Pa.

22nd St. & Washington Ave. Philadelphia 46, Pa. Main Office

New York Office 44 Whitehall St., N. Y. 4, N. Y.

PHOENIX BRIDGE COMPANY

Engineers—Fabricators
Erectors
Structural Steel
BRIDGES and BUILDINGS

General Office and Shops
PHOENIXVILLE, PA.

Subsidiary—Barium Steel Corporation

(Continued from page 88)

Iowa—C. F. Lytle Co., 250 Insurance Exchange Bldg., Sioux City, Iowa. LB $1,374,892. bridges, culverts, I-52 IN-886 (7), Woodbury Co.;

Iowa—Pittsburgh Des Moines Steel Co., 1015 Tuttle St., Des Moines, Iowa. LB $92,501. structural steel and steel bearing piling for bridges FG-568 (2), Hardin Co.; LB $375,422, structural steel and steel bearing pilings for bridges IN-ING 853 (2) Group 2, Polk Co.; LB $164,599. structural steel and steel bearing piles for bridges, IN-ING 853 (2), Group 9, Polk Co.;

Iowa—Rock Island Bridge & Iron Works, Inc., 1630 Mill St., Rock Island, Ill. LB $106,032. bridges, culverts U 1052 (1) Group 1, Johnson Co.;

Iowa—Des Moines Steel Co., 421 S.W. 4 St., Des Moines, Iowa. LB $91,224. structural steel and steel bearing piles for bridges IN-ING-853 (2), Group 5, Polk Co.; LB $117,844, structural steel and steel bearing piling for bridges, IN-ING-853 (2) Group 7, Polk Co.;

Iowa—Allied Structural Steel Co., Clinton Bridge Corp. Div., Clinton, Iowa. LB $201,863. structural steel and steel bearing pilings for bridges UG-831 (5) Group 1, Scott Co. Bids Oct. 30. CD 10/18.

▲ IOWA—State Hy. Comn., Ames,

Iowa—Slade Constr. Co., Fairmont, Minn. LB $359,766. c. conc. pavement wid'n., b. conc. resurf. 2.0945 mi. UN-922, Clinton Co.;

Iowa—R. B. Burch, Inc., 249 33 St. Dr. S.E., Cedar Rapids, Iowa. LB $846,745. c. conc. pavement wid'n., b. conc. resurf. 5.727 mi. F-1052 (2) Johnson Co.;

Iowa—Holland Bros. Constr. Co., Inc., Decorah, Iowa, LB $110,061. c. conc. pavement wid'n., b. conc. resurf. 5.302 mi. S 1213 (3), Allamakee Co.;

Iowa—Mott Constr. Co., Centerville, Iowa. LB $75,863. grading 4.849 mi. Special F-1058 (1) Marshall Co.;

Iowa—E. M. Duesenberg, Inc., Clear Lake, Iowa, LB $550,985, grading 4.138 mi. IN-ING-853 (2), Polk Co.; LB $116,936, grading 0.666 mi. FN-217; LB $447,204, grading 2.296 mi. U 831 (4); LB $146,631, grading 0.299 mi. UG 831 (5), all foregoing Scott Co. Bids Oct. 30. CD 10/18.

TEXAS—Texas Turnpike Auth., 214 First Federal Savings Bldg., Austin,

Eckert-Fair Constr. Co., 1307 National City Bank Bldg., Dallas, Tex., CA $977,659. Service Area-North; Service Area-South, operation bldg., maintenance bldg. D-FW-64, Dallas-Fort Worth. Bids Oct. 23. CD 10/31, under LB.

▲ Michigan Sewer Constr. Co., Box 4753, Detroit 19, Mich., CA, $3,449,215. Vasquez Tunnel and Jones Pass Tunnel lining, Winter Park (Fraser) Clear Creek and Grand Counties, DENVER, COLO. Bd. Water Comrs., City & County Bldg., Denver, Colo. Bids Oct. 26. CD 10/31, under LB.

▲† Robert E. McKee, General Constrator, Inc., Box 562, El Paso, Tex., LB $1,189,990, track control and maintenance facilities, Holoman Air Force Base. ENG-29-005-57-33, ALAMOGORDO, N. M. U. S. Eng., Box 1538, Albuquerque, N. M. Bids Oct. 23. CD 9/20.

BUILDINGS—LB & CA

O. E. Madsen, Sexton Bldg., Minneapolis, Minn., LB $832,200 (10 bidders) HIGH SCHOOL, east of Bell Line, south of Glenwood Ave., etc., GOLDEN VALLEY (P.O. Minneapolis), MINN. Bd. Educ., Independent School Dist. 89, Grace Seed, clk., Golden Valley, Minn. Bids Oct. 30. CD 10/24.

▲ The Fluor Corp., Ltd., 2500 Atlantic St., Los Angeles, Calif., CA Total est. $25,000,000. design and construct 80,000 bbl. per day VACUUM PIPE STILL at refinery, PORT ARTHUR, TEX. The Texas Co., 135 E. 42 St., New York, N. Y. CD 10/29.

FAR WEST

BUILDINGS—SLC

▲ Wash., Tacoma—HOUSING—U. S. Eng., 4735 E. Marginal Way, Seattle, Zone 4, soon lets contract construct and finance 110-to 150-units of family housing, McChord Air Force Base, Inv. 57-30, $1,500,000. CD 10/5, under LB.

HEAVY CONSTRUCTION—LB & CA

† IDAHO—Bureau P. Rds., Dpt. Commerce, Boise,

MacGregor-Triangle Constr. Co., 200 Sunrise Rim, Boise, Idaho, CA $711,695. Proj. 476-A, grading, constr. bridge over Clearwater River on 6.9 mi. Clearwater - River Rd., Clearwater Co. Bids Oct. 19. CD 10/25, under LB.

† OREGON—Bureau P. Rds., Dpt. Commerce, Morgan Bldg., Portland,

Morrison-Knudsen Co., Inc., 319 Broadway Ave., Boise, Idaho, CA, $644,640 (5 bidders) 2.244 mi. Mt. Hood Hy. Clackamas Co. Bids Oct. 26. CD 10/17.

▲ CALIFORNIA—State Div. Hys., 1120 N St., Sacramento,

Calif.—Peter Kiewit Sons Co., 442 Post St., San Francisco, Calif., LB $5,180,910. c. conc. paving 5.4 mi. on cement treated subgrade, rein.-con. slab bridge on Hy. 40 Navada and Sierra Counties;

Calif.—John Delphia & Fred J. Early, P. O. Box 607, Patterson, Calif., LB $970,629 (8 bidders) 4-lane divided hy. 3.7 mi. U.S. 50, rein.-con. bridge at Snow Road Undercrossing, El Dorado Co. Bids Oct. 31. CD 10/4.

BUILDINGS—LB & CA

Myers Bros., Brumonet & Dembton, Inc., 3407 San Fernando Rd., Los Angeles, Calif. CA $700,000. 2 story, 84,000 sq. ft., FACTORY, 3360 Foothill Blvd., ALTADENA, CALIF. Stuart Mfg. Co., 3407 San Fernando Rd., Los Angeles, Calif.

R. A. Watt Constr. Co., 7862 S. Western Ave., Los Angeles, Calif., CA, $652,500. 75 stucco DWELLINGS,

(Continued on page 92)

NEW! a cost-cutting drill for the push-button age!

the JOY JUNIOR CHALLENGER

BIG-DRILL FOOTAGE... LOWER LABOR COST... LESS TIME BETWEEN HOLES

Our customers asked for a brute of a drill on a mobile, "push-button" carriage. In other words, they wanted more hole at less labor cost, shorter time between holes, and faster set-ups. Here's our answer: the self-propelled *Joy Junior Challenger* . . . the FIRST COMPLETELY POWER-OPERATED WAGON DRILL ever produced. It drills anywhere, in any position, in any formation. The operator has nothing much to do but think, and change steels. Here are a few of the reasons why the Junior Challenger will cut costs on your job:

ALL POWER OPERATION—All movements of feed, drill, and carriage are hydraulic or air-powered—no chuck wrench necessary.

DRILLS AT ANY ANGLE—Vertical bench hole, toe holes, horizontal holes, and angle holes both up and down from the horizontal.

RIGID ALIGNMENT—Feed is supported by *two* trunnions, will not vibrate or move out of line.

STABILITY—Treads move independently up or down to conform with terrain, then are locked simply by turning a valve.

NEW HEAVY-DUTY 4½" DRIFTER—Has features found on no competitive machine; drills up to 3½" holes to 40 ft. depth *in any formation.*

SECTIONAL STEEL—1¾" round steel system, sectional type with detachable striking bar, has 9/16" o.d. air tube for outstanding hole-cleaning ability.

Write for complete information to ***Joy Manufacturing Company, Oliver Building, Pittsburgh 22, Pa.*** In Canada: *Joy Manufacturing Company (Canada) Limited, Galt, Ont.*

SPECIFICATIONS

Easily drills up to 3½" holes to 40 ft. depth in any formation.

Drills horizontal holes to 7½ ft. height.

Write for FREE Bulletin 87-24

Consult a Joy Engineer

for AIR COMPRESSORS • ROCK DRILLS • WAGON DRILLS
CORE DRILLS • BLAST HOLE DRILLS
PORTABLE HOISTS • FANS • BLOWERS • TUNNEL, QUARRY, MINE EQUIPMENT

WSW C 5076 67

JOY

CONSTRUCTION EQUIPMENT MANUFACTURERS FOR OVER HALF A CENTURY

(Advertisement)



A busy New York City street was treated to the sight of huge 12-ton pile hammers pounding away at 1,600 H-beam piles into "made" ground to provide foundations for the South Street Elevated Highway. The piles varied in length from 35 ft. to more than 200 ft. and the contractor, Fehlhaber Corporation, used S10 Single-Acting Pile Hammers, manufactured by McKiernan-Terry Corporation, 80A Richards Ave., Dover, New Jersey, to do the work.

Only **Behlen**

FRAMELESS METAL BUILDINGS are...

HEAVY GAUGE METAL

This attractive supermarket is the new Behlen Flat Top design. Channel-ridged aluminized steel panels form self-framing arches.

CUSTOM-MADE at standard prices

Style and utility. Behlen Buildings like this school can be veneered with brick, stone, wood for individuality. This building designed with columns for greater economy.

CLEAR SPAN up to 121-ft. widths, if desired

Big 149' x 101' warehouse has no bulky support columns or arches to hamper material handling and storage.

FRAMELESS BOLTED CONSTRUCTION

Behlen panels are quickly bolted together. Elimination of support columns here permits wall-to-wall storage.

WRITE TODAY for complete information about Behlen Buildings. They are completely adaptable to a wide range of commercial and industrial uses. Available in aluminized steel, aluminum or galvanized steel, Behlen Buildings offer contemporary appearance and maximum use of floor space.

BEHLEN MANUFACTURING COMPANY
Dept. 82 **Columbus, Nebraska**

(Continued from page 90)

Lots 1 thru 75, Tract 21757, COMPTON, CALIF. Inglewood Lane Co., 7862 S. Western Ave., Los Angeles, Calif.

Carl O. Larsen, 1246 S. Main St., Santa Ana, Calif., CA $712,160. Proj. 20, reinforced brick Intermediate SCHOOL, GARDEN GROVE, CALIF. Garden Grove School Dist., Garden Grove, Calif. Bids Sept. 21. CD 9/28, under LB.

McDonald Bros., 2639 S. La Cienega Blvd., Los Angeles, Calif., CA, $928,310. East Valley District HEADQUARTERS, 12730 Saticoy St., LOS ANGELES, CALIF. Dpt. Water & Power, 311 S. Spring St., Los Angeles, Calif. Bids Sept. 28, awarded Oct. 22. CD 10/10, under LB.

Steed Brothers, 714 Date Ave., Alhambra, Calif., LB $821,000 (4 bidders) Duarte HIGH SCHOOL addn. Proj. No. 1, MONROVIA, CALIF. Monrovia-Duarte Union High School Dist. Colorado and Madison Sts., Monrovia, Calif. Bids Oct. 24.

▲ **South Coast Constr. Co.**, 230 30 St., Newport Beach, Calif., CA $1,113,465. 55 DWELLINGS, Highlands Drive, Tract 3057, NEWPORT BEACH, CALIF. Bay-Way Homes, Inc. & Island Estates, 230 30 St., Newport Beach, Calif.

▲ **Bollenbacher & Kelton**, 3245 Zion St., San Diego, Calif., Owner Builds, $1,309,700. 127 stucco DWELLINGS, Allied Gardens No. 10, SAN DIEGO, CALIF.

▲ **John H. Deeter**, 1230 17 St., Bakersfield, Calif., LB $1,147,000, est. $1,000,000 (6 bidders) Cuyama Valley HIGH SCHOOL, SANTA MARIA, CALIF. Santa Maria Union High School Dist., Santa Maria, Calif. Bids Oct. 25. CD 10/9.

▲ **C. L. Peck & Millie and Severson** 816 W. 5 St., Los Angeles, Calif., CA $2,449,000. new municipal AUDITORIUM, SANTA MONICA, CALIF. City, City Hall, Santa Monica, Calif. Bids Oct. 23, awarded Oct. 26. CD 9/13.

CANADA

BUILDINGS—BA

▲ **Ont., Windsor**—HOUSING—BA 11/20—H. I. Stricker, regional engr., c/o Central Mortgage & Housing Corp., 40 Eglinton Ave. E., Toronto, 96 single family dwellings, $1,000,000. Plans deposit $100.

Ont., Ottawa—ADMINISTRATION—BA 11/22—Dpt. P. Wks., Hunter Bldg., admin. bldg. for Dpt. Mines & Technical Surveys, Booth St. $400,000. Allward & Gauinlock, 57 Bloor St. W., Toronto, archts. R. P. Allsop & Assoc., Ltd. 290 Davenport Rd., Toronto, consult. engrs. CD 2/3.

N. S., Halifax—ABATTOIR—BA 11/29—N. S. Co-Operative Abattoir Ltd., c/o Leslie R. Fairn & Assoc., archts. 41 Argyle St., Abattoir bldg., Bedford Basin, Halifax area, $600,000. Plans deposit $200. CD 1/23.

BUILDINGS—SLC

▲ **Ont., Simcoe**—PLANT—Canada Wire & Cable Co. Ltd., 147 Laird Dr., Leaside, Toronto, soon lets contract 1 story, 113,000 sq. ft., steel, brick enamel wire dept. plant. $2,000,000. Babcock Scrivener Ltd., 119 Isabella St., Toronto, engrs. CD 7/17.

BUILDINGS—LB & CA

Burns & Dutton Concrete & Constr. Co. Ltd., 9004 125 Ave., Edmonton, Alta., LB $668,885 (4 bidders) PHYSICAL TRAINING BLDG., Army Barracks, EDMONTON, ALTA. Defence Constr. (1951) Ltd., 56 Lyon St., Ottawa, Ont.

Newton Construction Co. Ltd., P. O. Box 970, Sherbrooke, Que., LB $786,300 (6 bidders) detention BARRACKS and 3 gate houses, Camp Gagetown, FREDERICTON, N. B. Defence Constr. (1951) Ltd., 56 Lyon St., Ottawa, Ont.

Richard & B. A. Ryan Ltd., 78 Logan Ave., Toronto, Ont., LB $700,000. 51,000 sq. ft. COLD STORAGE, 16,800 sq. ft. dry storage surface area, loading docks, etc. and 6,800 sq. ft. office area, LANCASTER, N. B. Ayr Cold Storage Maritimes Ltd., c/o D. S. Wood, Admiral Beatty Hotel, St. John, N. B. Bids Oct. 22. CD 10/10.

▲ **Foundation Co. of Ontario Ltd.**, 1220 Bay St., Toronto, Ont., CA Over $1,000,000. 200x200 ft., steel frame 20,000 kw power NUCLEAR POWER PLANT, CHALK RIVER, ONT. Atomic Energy of Canada Ltd., Green Island, Ottawa, Ont., Ontario Hydro-Electric Power Comn., 620 University Ave., Toronto, Ont., and Canadian General Electric Co. Ltd., 212 King St. W. Toronto, Ont. Awarded Oct. 23.

I. Frydman, 345 Lonsdale Ave., Toronto, Ont., Owner Builds. $624,000. 11 story, rein.-con. brick APARTMENT, Bernard Ave. and St. George St., TORONTO, ONT. E. I. Richmond, 455 Spadina Ave., Toronto, Ont., archt.

Taylor Woodrow (Canada) Ltd., 636 Jarvis St. Toronto, Ont., CA, Est. $600,000. (7 bidders) 4 story, bsmnt., L-shaped, masonry, concrete, steel, RESIDENCE, TORONTO, ONT. Young Women's Christian Assn. 21 McGill St., Toronto, Ont. Bids Oct. 18, awarded Oct. 24. CD 10/5.

▲ **Pentagon Constr. Co. Ltd.**, 5005 Namur St., Montreal, Que., CA $2,401,098, GRAIN ELEVATOR impvs., Montreal Harbor, MONTREAL, QUE. National Harbor Bd., West Block, Parliament Bldgs., Ottawa, Ont. C. D. Howe Co. Ltd., 1421 Atwater Ave., Montreal, Que., consult. engr.

LATIN AMERICA

HEAVY CONSTRUCTION—LB & CA

▲ **American Cast Iron Pipe Co.**, 2930 N. 16 St. Birmingham, Ala., U. S. A. CA $1,355,928, water sys. ASUNCION, PARAGUAY. Corposana, Asuncion, Paraguay. Grand total $3,154,238. Bids Oct. 1. CD 7/12.

(Continued on page 94)

The addition is approximately 91 ft. x 114 ft. with 16 ft. x 30 ft. bays. Prestressed beams run the 114 ft. length, spanning 16 ft. over the precast columns. Prestressed channel slabs of 12 in. depth span the 30 feet between the beams at floors and roof.

Owner: MINNESOTA RUBBER and GASKET CO., St. Louis Park, Minn.

Architect: MAGNEY, TUSLER & SETTER Minneapolis, Minn.

Precast concrete manufactured and erected by: PRE-STRESSED CONCRETE, INC., St. Paul, Minn.

PRESTRESSED AND PRECAST STRUCTURAL CONCRETE

FRAMING saved time and money for

Minnesota Rubber and Gasket Company

The new three story addition to the St. Louis Park, Minnesota, plant of Minnesota Rubber and Gasket Company is constructed entirely of precast concrete columns and prestressed beams, floor channels, and roof channels. These modern materials cut framing costs 20%, permitted 4 months earlier occupancy and eliminated expensive fireproofing.

LEHIGH EARLY STRENGTH CEMENT saved time and money for

Prestressed Concrete, Inc.

All structural units were cast in the modern plant of Prestressed Concrete, Inc. Using Lehigh Early Strength Cement and hot water curing, the concrete reached 3500 PSI in 12 hours. As a result, the manufacturer gained maximum production efficiency and economy through early removal of units and quick reuse of forms.

Whatever your cement requirements, there are Lehigh Cements to fit them. And remember, somewhere on nearly every job, Lehigh Early Strength Cement will save time and money.

Interior view of Prestressed Concrete's casting plant. Four channel beds at left are 200 ft. long. In center is bed for precasting reinforced beams. Next to the far right is a 100 ft. bed for prestressing beams. At far right is a form for precasting columns.

- LEHIGH EARLY STRENGTH CEMENT
- LEHIGH PORTLAND CEMENT
- LEHIGH MORTAR CEMENT
- LEHIGH AIR-ENTRAINING CEMENT

LEHIGH PORTLAND CEMENT COMPANY

Allentown, Pa.



MALLEABLE IRON or

DROP FORGED?

Rugged dependability suggests that you insist on the best — Simplex *drop forged steel* trench braces.

Ball and socket joints at each end for tight grip at any angle. Blunt lever nuts or 3-way nuts — nail holes in both screw and butt ends. Furnished with or without pipe.

Simplex drop forged steel trench and timber braces *cost no more* and better eliminate the danger of cave-ins and costly re-digging.

SEND FOR BULLETIN: U 56

WORLD'S LARGEST MFGRS. OF INDUSTRIAL MECHANICAL AND HYDRAULIC JACKS

SIMPLEX JACKS

RE-MO-TROL UTIL-A-TOOL JENNY ROL-TOE

TEMPLETON, KENLY & COMPANY
2511 Gardner Road
Broadview, Illinois

BUILT TO YOUR needs from standard parts

15-HP SPECIAL PURPOSE HOIST
single fixed drum, worm gear drive

Meet your hoisting needs *precisely* at lowest possible cost. Call on our long experience in modifying and re-combining standard parts to meet specialized hoisting requirements.

Write for bulletins and catalogs

SUPERIOR-LIDGERWOOD-MUNDY CORPORATION

Main Office and Works:
SUPERIOR, WISCONSIN, U. S. A.
New York Office, 7 Dey St., N. Y. 7, N. Y.

LEFAX
TECHNICAL DATA BOOKS
POCKET SIZE • LOOSE LEAF

Printed on loose leaf, 6 hole, 6¾" x 3¾" bond paper, each book contains about 140 pages of technical data, condensed, accurate, essential, for engineer, technical worker, student, business man.

$1.25 each

Architecture	General Math	Phys. & Thermo.
Home Heating	Math Tables	Data
Illumination	Physics	Metals
Electrician's Data	Trig-Log Tables	Metallurgy
Builder's Data	Gen'l Chemistry	Hydraulics
Lumber Data	Chemical Tables	Radio
Air Conditioning	Analytic Chem.	Television & FM
Building Constr.	Mech'l Drawing	Electricity, AC
Reinf. Concrete	Machine Design	Electricity, DC
Piping Data	Machinist's Data	AC Motors &
Surveying	Mech. of Materials	Gen'trs.
Surveying Tables	Pwr Trans. Mach.	Transformers,
Highway Eng'g.	Thermo. Tbls. & Charts	Relays & Meters

Write for FREE catalogs (2000 listings). See how helpful LEFAX can be to you. Send $1.25 book, or $6 for any five books to LEFAX PUBLISHERS, Dept. ER-5, Phila. 7, Pa.

GUNITE
Since 1915
CONCRETE
SAND AND CEMENT
Placed by Air

We have the equipment, personnel and experience to complete any and all GUNITE work regardless of size or location.

Send for specifications and bulletins

GUNITE CONCRETE & CONST. CO.
1301 WOODSWETHER RD., KANSAS CITY 5, MO.
2016 WEST WALNUT, CHICAGO 12, ILLINOIS
3206 HOUSTON, HOUSTON 9, TEXAS
1508 PARKWAY DRIVE, ST. LOUIS 4, MO.
Milwaukee and Twin Cities Denver New Orleans

(Continued from page 92)

Kaiser Engineers, Div. of Henry J. Kaiser Co., 1924 Broadway, Oakland 12, Calif., U. S. A. CA $1,325,000, general constr. water sys. (Asuncion, Paraguay);

Allis Chalmers Mfg. Co., 1126 S. 70 St., Milwaukee, Wis., U. S. A., CA $201,550, centrifical pumps (Asuncion, Paraguay);

Westinghouse Electric Corp., 40 Wall St., New York, N. Y., U. S. A. CA $101,345, motor controls (Asuncion, Paraguay);

C. Tennant & Sons Co. of N. Y., 100 Park Ave., New York, N. Y., U. S. A. CA $170,415, galvanized steel pipe (Asuncion, Paraguay).

AMERICANS ABROAD

HEAVY CONSTRUCTION—LB & CA

▲† Saconia & Early Constr. Co., Madrid, Spain, LB $5,589,274 (3 bidders) POL terminal storage, SEVILLE, MADRID, ZARGOZA, SPAIN. Bureau Yards & Docks, Navy Dpt., 18 St. and Constitution Ave. N.W., Wash. 25, D. C., U. S. A.

PROPOSED PROJECTS

WATER SUPPLY

▲ Calif., Carlsbad—Carlsbad Municipal Water Distr., Carlsbad, voted $1,300,000 bonds Oct. 6, 2,500,000 gal. regulating water reservoir and 15 mi. water transmission line from the San Diego Aqueduct to Carlsbad.

▲ Mich., Detroit—City, Bd. Water Comrs., 735 Randolph, 4 mi. water main from Detroit north to Madison Heights, Dequindre from 8-mile to 12-mile, $1,200,000. G. Remus, c/o Water Dpt., 735 Randolph, ch. engr. CD 11/11/48.

▲ Okla., Lawton—City, defeated bonds Oct. 30, addnl. water supply, $6,182,840. Wyatt B. Hendrick, Security Bank Bldg., consult. engr. CD 10/25.

SEWERS, WASTE DISPOSAL

▲ Fla., Clearwater—Bd. Comrs., Pinellas Co. Court House Annex, sanitary sewerage sys. and treatment facilities. $6,750,000. Briley, Wild & Assocs., P.O. Box 3052, Daytona Beach, and Dr. A. P. Black, Black & Associates, Gainesville, engrs. CD 10/24.

▲ Idaho, Pocatello—City, City Hall, sewage treatment plant. $1,000,000. Work may start late next year. Hamilton & Voeller, 417 E. Center St., Pocatello, consult. engrs. CD 4/12.

▲ Mich., Detroit—City, Glenn C. Richards, comr. P. Wks., City-County Bldg., West End Relief Sewer, River of Dix, $3,140,000; Oakland Pump Stations, $185,000, Connor Creek Control Station $825,000, Ashland Diversion $210,000, 1957-58 projects; Mack Relief Sewer $3,460,000, Blue Hill Pump Station $115,000, Rivard Relief Sewer $2,700,000, 1961-62 projects. M. F. Wagnitz, 528 City-County Bldg., engr.

▲ Minn., St. Louis Park—City, J. Justad, clk., sanitary and storm sewer projects in north side of city. $2,000,000. G. M. Orr Eng. Co., 1004 Marquette Ave., Minneapolis, consult. engrs. CD 8/2/54.

▲ O., Hamilton—City, City Hall, sewage disposal plant, Riley's Island. $3,208,000. Consoer, Townsend & Assocs., 360 E. Grand Ave., Chicago 11, Ill., engrs. CD 10/26.

▲ Tenn., Athens—City, City Hall, installing city wide sewerage sys. $3,340,000. CD 6/9/54.

BRIDGES

▲ Ill., Chicago—City, City Hall, underpass, N. Western Ave. to Logan Blvd. $2,500,000. CD 4/9/55.

▲ Okla., Oklahoma City—City, City Hall, bond election Nov 27, bridges, $2,000,000. W. W. Baker, city engr. CD 3/27.

STREETS AND ROADS

▲ OHIO—State Hy. Dpt., Columbus,

Butler and Warren Counties—North-South Freeway from Tylersville Rd. in Butler Co. to Rte. 123, Warren Co. $11,500,000. Bids in 1957 or early 1958. Dodson, Kinney & Lindblom, 5 E. Long St., Columbus, and A. M. Kinney, Inc., 2905 Vernon Pl., Cincinnati, consult. engrs.

Hamilton and Butler Counties—North-South Freeway from Rte. 50 bypass to Tylersville Rd. in Butler Co. $9,000,000. Bids late 1957 or early 1958. Vogt, Ivers, Seaman & Assocs., 34 W. 6 St., Cincinnati, consult. engrs.

Warren Co.—North-South Freeway from Rte. 123 to Rte. 25, south of Dayton, $10,800,000. Bids 1957 or early 1958. Yule, Strickland, Jordan & McNee, 309 S. Broad St., Phila., Pa., consult. engrs.

▲ Okla., Oklahoma City—City, City Hall, bond election Nov. 27, streets. $4,000,000. W. W. Baker, city engr. CD 3/27.

▲ UTAH—State Road Comn., State Capitol, Salt Lake City,

Kane Co.—Contr. 1, Kanab, Glen Canyon Dam Site Rd., incl. 21 mi. of road from Arizona line toward Kanab. $1,600,000. Bids sometime this year.

▲ WYOMING—State Hy. Comn., Cheyenne,

Natrona Co.—relocating U. S. Hys., 20, 26 and 87 relocation, incl. bridge over North Platte River. $10,000,000-$20,000,000.

EARTHWORK, WATERWAYS

▲† California—Bureau Reclamation, Dpt. Interior, Denver Federal Center, Denver, Colo., Trinity Dam,

(Continued on page 96)

FIRE RESISTANCE

Permalite plaster*, used to fireproof structural steel members, gains 4-hour fire-ratings in

REPUBLIC NATIONAL BANK BUILDING
Dallas, Texas

STATE OFFICE BUILDING
Pittsburgh, Penna.

(and many other noted buildings)

Nationwide—noted buildings gain many advantages with

Permalite®

the world's largest selling Perlite aggregate

for **BETTER PLASTER**
BETTER CONCRETE

LIGHT WEIGHT

Permalite plaster*, only ⅓ the weight of sanded plaster, provided excellent workability, low moisture absorption and low suction ratio in the plastering of many outstanding buildings such as:

HOTEL FONTAINEBLEAU
Miami Beach, Florida

NAZARETH CHILD CARE CENTER
Boston, Mass.



INSULATION

Permalite, used either in insulating concrete or in roof or floor fill, gives highly desirable "K" and "U" factors in all types of buildings, from homes to warehouses.

examples

S. S. KRESGE CO. WAREHOUSE
(400,000 ft.² roof deck of Permalite lightweight insulating concrete*)
Fort Wayne, Indiana

PERSONAL RESIDENCE OF DESIGNER CLIFF MAY
(Permalite insulating concrete* Sub slab in 7,000 ft.² floor slab)
Los Angeles, Calif.

** the terms*

*"Permalite plaster" or "Permalite concrete" mean plaster or concrete in which Permalite expanded perlite is used as the aggregate.

Write for information on the many advantages of Permalite in modern construction

PERLITE DIVISION
GREAT LAKES CARBON CORPORATION
612 So. Flower St., Los Angeles 17, Calif.

(Continued from page 94)

Trinity River Division, Central Valley Proj., inasmuch as weather conditions at the time of issuance may make examination of site of proposed work difficult, prospective bidders are invited to inspect the site in the immediate future. Bids may be issued in December. L. N. McClellan, asst. comr. and ch. engr. CD 4/14/44.

▲ **Calif., San Jose**—Santa Clara County Flood Control Dist., 60 N. 2 St., voted $5,000,000 bonds Oct. 2, new creek channels and imprv. old ones to aid runoff, Northwest Zone. CD 8/17.

▲ **Pa., Erie**—City, City Hall, dredging, land reclamation and wharf and storage facilities for expanding harbor. $2,712,500.

▲ **Que., Jonquiere**—Villa de Jonquiere, Town Hall, hydro electric power station, Riviere Pibrac, $1,500,000-$2,000,000.

AIRPORTS

▲ **N. Y., Mitchel Field**—TECHNICAL BLDG—U. S. Eng., 111 E. 16 St., New York, Zone 3, plans by LaPierre, Litchfield Partners, 292 Madison Ave., New York, Zone 17, technical training bldg. $1,000,000-$3,000,000.

▲† **N. Y., Niagara Falls**—RUNWAY PAVING, etc.—U. S. Eng., 111 E. 16 St., New York, Zone 3, runway paving, $1,000,000-$3,000,000; theater, $100,000-$500,000, Niagara Falls Air Force Base. Thomas H. McLaig, 881 Main St., Buffalo, consult. engr. CD 10/20/55.

▲† **N. Y., Westhampton**—AIRPORT IMPRVS.—U. S. Eng., 111 E. 16 St., New York, Zone 3, electric distr. sys., $100,000; readiness crew bldg., $100,000-$500,000; runway paving, $500,000-$1,000,000, Suffolk Air Force Base. Gehron, Weiskopf & Pickworth, 101 Park Ave., New York, Zone 17, engrs. CD 8/22.

▲ **Okla., Oklahoma City**—AIRPORT—City, City Hall, bond election Nov. 27, airport extens. $4,300,000. W. W. Baker, city engr. CD 3/27.

LATIN AMERICA

▲ **Uruguay**—HYDRO ELECTRIC PLANT—Administration General de las Usinas Electricas y los Telefonos del Estado del Esrado, Montevideo, plans hydro electric plant and transmission lines at Rincon de Baygorria, on Rio Negro. $25,500,000.

PUBLIC BUILDINGS

▲ **Calif., Glendora**—SCHOOL—Glendora School Dist., 440 W. Foothill Blvd., voted $1,000,000 bonds, school. CD 9/20.

▲ **Calif., Lynwood**—SCHOOLS—Lynwood Unified School Dist., Lynwood, defeated bonds Oct. 16, high school, $1,370,000. elementary school $935,000. CD 7/13.

▲ **Calif., Orinda**—SCHOOLS—Orinda Union Elementary School Dist., Orinda, bond election Jan. 22, 1957, school expansion program, $2,150,000.

▲ **Calif., Redlands**—SCHOOLS—Redlands Union High School Dist., Redlands, bond election Nov. 12, Yucaipa Junior and Senior High Schools addns., Cope Junior High School and new Junior High School, $4,290,000. CD 2/7.

▲ **Colo., Greeley**—SCHOOL—School Dist. No. 6, 811 15th St., Greeley High School addn., 35,860 sq. ft. and new elementary school between Hillside and Brentwood addns.; 30,000 sq. ft., $1,328,000. Alfred Watts Grant, 1640 Court Place, Denver, consul. engrs.-archts. CD 9/26.

▲ **Conn., Enfield**—BUILDINGS—State P. Wks. Dpt., 165 Capitol Ave., Hartford, bldgs. at Osborne Prison Farm to replace existing barrack type bldgs. $1,000,000. CD 8/10/54.

▲ **Conn., Milford**—SCHOOL—Town, Town Hall, West High School, Milford Point Rd. $1,300,000.

▲ **Conn., Ridgefield**—SCHOOL—Town, Town Hall, 12 room elementary school North End, 8 room addn. to Veterans Park School, Ridgebury and Branchville, modernize East Ridge Bldg. for High School, $2,000,000.

▲ **Conn., Storrs**—SCIENCE, etc.—State P. Wks. Dpt., 165 Capitol Ave., Hartford, science bldg. $3,000,000; dormitory to accomodate 500 women, $1,200,000; dormitory to accomodate 500 men, $1,200,000; addnl. classroom facilities, $3,000,000; continuing education center, $2,400,000; intramural and athletic sports arena, $990,000; housing for faculty, $1,200,000; East-Side stands in football sadium, $390,000; educational television station, $80,000, University of Connecticut.

▲ **Ill., Chicago**—HOSPITAL, etc.—University of Illinois, 256 Administration Bldg., Urbana, plans by Pace Assocs., 53 W. Jackson Blvd., and Fugard, Burt, Wilkinson & Orth, 520 N. Michigan St. (A) research hospital addn. (B) dentistry, medicine, pharmacy bldg. addns., Wood and Harrison Sts. $3,840,000. CD 3/18/53; plans by Skidmore, Owings & Merrill, 100 W. Monroe St., research laboratory, vicinity Wood and Harison St. $1,925,000. CD 3/18/53.

▲ **Iowa, Iowa City**—SCHOOL—Iowa City Public Schools, Buford W. Garner, supt. Schools, $1,500,000 bond election Nov. 20, Junior High School. Louis Kingscott & Assoc., 605 Putnam Bldg., Davenport, archt. CD 10/24.

▲ **Iowa, Waterloo**—COUNTY, CITY—City, City Hall, and Black Hawk Co., County Bldg., Waterloo, plans by Black Hawk Architects, Inc., Waterloo, joint city-county bldg. $2,265,000. CD 8/23.

▲ **La., New Orleans**—SCHOOLS—Orleans Parish School Bd., 703 Carondelet St., plans by Ricciuti & Assn., 521 Royal St., Junior High School, on site bounded by Second, S. Tonti, Fourth and S. Rochebleave Sts., $1,552,320; plans by Carl L. Olschner & Assn., Pere Marquette Bldg., elementary school on site bounded by Clio, S. Dorgenois, Erato, and S. Broad Sts., $402,380.

▲ **Mass., Marshfield**—SCHOOL—Town, Supt. Schools, New St. plans by Haldeman & Jacoby, 153 Main St., Brockton, high school. Plain and Forest Sts. $1,300,000. CD 10/13/55.

▲ **Minn., Roseville** (P. O. St. Paul)—SCHOOL—Bd. Educ., 1261 Hy. 36, St. Paul, voted $2,300,000 bonds Oct. 23, school constr., incl. Junior High School, $500,000; Brimhall Elementary School addn., $500,000; addns. to 3 smaller schools, each under $200,000, Magney, Tusler & Setter, 303 Roanoke Bldg., Minneapolis, archts. CD 2/14/55.

▲ **N. J., Newark**—GARAGE—City, Parking Auth., City Hall, 3 level parking garage under Military Park, $2,000,000.

▲ **N. Y., Brooklyn**—SCHOOL—Bd. Educ., Bureau Constr., 42-15 Crescent St., Long Island City, plans by John A. Thompson, 111 E. 40 St., New York, Zone 17, 3 story, P.S. 11 (formerly P.S. 295), 419 Waverly Ave., Proj. E-387, $2,000,000.

▲ **N. Y., New York**—SCHOOL—Bd. Educ., Bureau Constr., 42-15 Crescent St., Long Island City, plans by Dominick Salvati & Son, 26 Court St., Brooklyn, Zone 2, P.S. 179 Amsterdam Ave. and West 101 St., Proj. E-816. $1,000,000.

▲ **Tex., Brownsville**—POWER PLANT—City, defeated bonds Oct. 13, power plant, $3,150,000 (Correction—status of bond election). CD 10/25.

▲ **Tex., Lubbock**—SCHOOL—Lubbock Independent School Dist., plans by Herbert M. Brasher & Assoc., 412 Ave. M, Junior High School, 31st St. and Quaker Ave., $1,000,000. CD 10/27/55.

▲ **Tex., Marshall**—COURTHOUSE—Harrison Co., c/o Courthouse, Longview, new courthouse. $1,000,000.

▲† **Tex., San Antonio**—LABORATORY—U. S. Engr., Box 1229, Galveston, medical laboratory, $3,500,000; classrooms bldg., $3,500,000; administration bldg., $1,500,000, at Brooks Army Medical Center, Fort Sam Houston. Wyatt C. Hedrick, 5201 Fannin St., Houston, consult. engr. CD 4/30/52.

▲ **Utah, Salt Lake City**—HIGH SCHOOL—Salt Lake City Bd. Educ., 440 E. First South, Salt Lake City, plans by Lowell E. Parrish, 325 Dooly Bldg., Southeast Junior High School, 18th East and 14th South. $1,350,000. CD 5/2.

▲ **Va., Norfolk**—SCHOOLS—Norfolk City School Bd., Bank and Charlotte Sts., administration bldg., teaching materials center, Broad Creek Village Sect. $500,000; elementary school, Tanners Creek, $650,000, 1958 project; Junior High School, Berkley sect., $1,000,000, 1959 project; elementary school, northern

(Continued on page 99)

SURCO® ...for fast, attractive, economical concrete FINISHING



Spalled, honeycombed, rough or otherwise faulty concrete can be effectively repaired and attractively finished by SURCO latex base coatings.

Applied 1/16"-1/4" thick over clean surface, and rubber floated into attractive sand finish, Surcoating water- and weather-proofs concrete in addition to filling. Excessively rough areas need not be recast; hand rubbing with stone is not necessary. And the cost . . . much lower than conventional concrete finishing.

SURCO concrete finishing can be used on any exterior or interior concrete, and provides a protective architectural finish.

Write for the following SURCO specifications:

1201—Industrial; **1204**—Terrazzo
1401—Water-proofing; **1501**—Roofing
1601—Stucco; **1701**—Plaster
1704—Concrete Finishing
1801—Tile Setting and Underlayment

SURCO®
INTERNATIONAL CORPORATION
1389 PEACHTREE STREET, N.E.
ATLANTA 9, GEORGIA

Solving "parking" problems for river traffic

Our natural traffic arteries, the rivers, today bustle with increasing transportation of all kinds of bulk materials. Efficient "parking" facilities, such as this coal loading dock on the Ohio River are needed to load and unload barges at terminal points. Made up of a series of steel sheet pile cells, filled with sand and gravel and capped with concrete, these docks are low in first cost and need little maintenance. The number, diameter and height of cells is determined by dock size and location as well as variations in river level. Two or three or dozens may be used. Large installations, equipped with barge shifting and unloading machinery, have been constructed to handle as many as sixty barges.

More than 100 docks have been built in the last eight years, another example of Dravo's unique construction experience "in and around water." For more information on docks or any of the products and services listed below, write to DRAVO CORPORATION, PITTSBURGH 25, PENNSYLVANIA.

DRAVO
CORPORATION



Blast furnace blowers • boiler & power plants • bridge sub-structures • cab conditioners • docks & unloaders • dredging • fabricated piping



foundations • gantry & floating cranes • gas & oil pumping stations • locks and dams • ore & coal bridges • process equipment • pumphouses & intakes

river sand and gravel • sintering plants • slopes, shafts, tunnels • space heaters • steel grating • towboats, barges, river transportation

Yoloy "E" is on the job



Fruehauf industrial trailers utilizing Yoloy "E" in their construction are: (above) three-compartment, 6300-gallon gasoline transport, and (right) 5000-gallon, 2-inch insulated hot asphalt hauler.

providing stronger, higher payload transport trailers

Keeping our millions of autos on the road—requires the most efficient and economical gasoline transports and asphalt haulers that today's industrial trailer industry can produce. Youngstown's Yoloy "E" Steel plays a prominent part in this picture.

In the two Fruehauf trailers (shown above) for transporting gasoline and asphalt, Yoloy "E" high strength low alloy steel is used to insure structural strength, decrease dead weight and increase payload capacity. Trailer components such as side sheets, top ribs, baffles, bulkheads, stiffeners, inner tanks and outer shells are all fabricated from Yoloy "E". The corrosion resistance of Yoloy "E" gives Fruehauf equipment a much longer service life—which helps build customer profits and satisfaction.

Yoloy is available in sheets, plates, strip, bars, shapes, cold-drawn bars and tubular products—including both seamless and continuous weld pipe. Your nearest Youngstown District Sales Office is ready to supply information and service engineering on the Yoloy Steels best fitted to meet your industrial requirements.

Youngstown
YOLOY STEEL

QUALITY YOUNGSTOWN SERVICE

THE YOUNGSTOWN SHEET AND TUBE COMPANY
Manufacturers of Carbon, Alloy and Yoloy Steel

General Offices Youngstown, Ohio District Sales Offices in Principal Cities.

SHEETS - STRIP - PLATES - STANDARD PIPE - LINE PIPE - OIL COUNTRY TUBULAR GOODS - CONDUIT AND EMT - MECHANICAL TUBING - COLD FINISHED BARS - HOT ROLLED BARS - WIRE - HOT ROLLED RODS - COKE TIN PLATE - ELECTROLYTIC TIN PLATE - BLACK PLATE - RAILROAD TRACK SPIKES - MINE ROOF BOLTS

(Continued from page 96)

or eastern section of city, $650,000, 1959 project; high school, northeastern section $2,000,000, 1960 project; elementary school, location undetermined, $650,000, 1960 project; elementary school, location undetermined, $650,000, 1961 project; plans by A. Ray Pentecost, Jr., & J. B. Courtney, Colonial Ave. at 21st St., Junior High School, Tanners Creek area (Lakewood), $1,500,000, 1958 project; plans by Louis A. Oliver & H. L. Smith, 3rd, 409 Yarmouth St., Junior High School, northeastern section (Lansdale), $1,500,000, 1961 project. W. P. Sullivan, c/o Norfolk School Bd., engr.

▲ **B. C., Vancouver**—SCHOOL—Vancouver School Bldg., 1595 W. 10 St., plans by E. D. King, 1595 W. 10 St.,4 story, rein.-con. composite Junior-Senior High School, Prince Edward and 23 Sts. $2,000,000. CD 12/18/53.

▲ **Ont., Hamilton**—NUCLEAR RESEARCH REACTOR—Atomic Energy of Canada Ltd., Ottawa, The Hydro-Electric Power Comn. of Ontario, 620 University Ave., Toronto, Hamilton College of McMaster University, Hamilton, nuclear research reactor for university and industrial research. $1,300,000.

▲ **Que., Montreal**—TECHNICAL SCHOOL—Provincial Government, Dpt. Youth & Social Welfare, Que., technical school Domaine St. Sulpice, $2,000,000.

COMMERCIAL BUILDINGS

▲ **Calif., Corte Madera**—STORES—Madera Gardens Development Co., c/o John S. Boles, archt., 215 Leidendorf St., San Francisco, 1 and 2 story stores, concrete, Madera Shopping Center, $2,000,000.

▲ **Calif., Los Angeles**—APARTMENT—Paul Trousdale & Clinton Murchison, Jr., c/o Pereira & Luckman, archts., 9220 Sunset Blvd., 22 story Beverly Towers Apartment, Sunset Blvd. $10,000,000.

▲ **Calif., Palo Alto**—INN—John Rickey, 4219 El Camino Real, Palo Alto, 6 story rein.-con. addn. to Rickey's Studio Inn, patio for each room. $1,000,000.

▲ **Calif., San Mateo**—SHOPPING CENTER—Irving Feldman, c/o Murphy & Hastings, engrs., 650 El Camino Real, Redwood City, shopping center in Baywood Plaza Sub-division. $1,000,000.

▲ **Calif., Sausalito**—MOTEL—Grace Management Corp. & U. S. Leasing Corp., 465 Calif. St., San Francisco, motel and swimming pool on berthing facilities on Land Spit Property, $3,000,000.

▲ **Colo., Loveland**—HOTEL, etc.—Loveland Hotel Co., (John D. & Clint Murchison Jr., Dallas, Tex.) plans by Ralph D. Peterson, archt.-engr., 1707 Gilpin St., Denver, 125 room hotel, country club and convention headquarters on the North shore of Lake Loveland, $1,000,000. CD 2/15.

▲ **Conn., Ellington**—HOUSES—Sidney Moses, 464 Farmington Ave., Hartford, 80 houses development, Crane Acres, Crane Rd. $1,116,000.

▲ **Conn., New Haven**—DORMITORY—Yale University, 105 Wall St., New Haven, plans by Douglas Orr, 111 Whitney Ave., New Haven, women students dormitory, Temple St. $1,000,000. CD 6/26.

▲ **Conn., West Hartford**—HOUSES—Hunter Park, Fernbel Lane, 57 houses development, Hunter Park, West Side. $1,285,350.

▲ **Idaho, Boise**—CHURCH—First Methodist Church, 1012 State St., plans by H. E. Wagoner, Archts. Bldg., Phila., Pa., and Hummel, Hummel & Jones, 1324 Idaho St., Boise, church bldg. $1,000,000. CD 10/21/55.

▲ **Mich., Garden City**—HOSPITAL—Peoples Community Hospital Auth., 35166 Mich. Ave., Wayne, bond election Nov. 6, hospital. $2,000,000.

▲ **Minn., Minneapolis**—BUILDING—First Federal Savings & Loan Assn., W. Youngquist, pres., 110 S. Seventh St., plans by Larson & McLaren, 1901 Foshay Tower, 6 story, 82x128 ft. building, Seventh St. and Marquette Ave. $1,500,000.

▲ **Mont., Great Falls**—SHOPPING CENTER—Tenth Avenue Realty Co., c/o archt., and William F. O'Haire, Shelby, plans by Frank Shanley, Barber-Lydiard Bldg., 73,295 sq. ft. brick and glass walls "Miracle Mile" Shopping Center. $2,000,000.

▲ **N. J., Morristown**—HOSPITAL—Bd. Trustees All Soul's Hospital, 95 Mt. Kemble Ave., plans by Fletcher & Thomas, 211 State St., Bridgeport, Conn., particularly Mr. Gerald Phelan of that firm with offices at 1051 Bloomfield Ave., Clifton, 6 story, brick, steel hospital. $3,000,000. CD 1/13/54.

▲ **N. J., Newark**—OFFICE—Muntual Benefit Life Ins. Co., 300 Broadway, plans by Frank Grad & Sons, 11 Commerce St., 6 story office bldg., Broad and Bridge Sts. $1,500,000.

▲ **N. Y., Brooklyn**—APARTMENT—Concord Leasing Corp., 97-27 64 Rd., Rego Park, plans by George G. Miller, 125 W. 45 St., 6 story apartment and 55-car garage, 2400 East 3rd St. $1,500,000.

▲ **N. Y., Brooklyn**—SHOPPING CENTER—Red Rudinger, 30-97 Steinway St., Long Island City, plans by Morris Brody, 560 Saddle Ridge Rd., Woodmere, 250,000 sq. ft. shopping center on east side of Flatbush Ave. and Ave. I. $5,000,000.

▲ **N. Y., Greenburgh**—SHOPPING CENTER—Glenel Realty Corp., c/o Henry G. Greeve, archt., 855 Sixth Ave., New York, Zone 1, shopping center, $1,000,000.

▲ **N. Y., Mount Kisco**—HOSPITAL—Northern Westchester Hospital, E. Main St., plans by Rogers & Butler, 219 E. 44 St., 2 story hospital addn. $1,000,000.

▲ **N. Y., Plattsburgh**—SHOPPING CENTER—North Country Shopping Center, c/o Jerome Lieberthal, Chrysler Bldg., New York, Zone 17, plans by Sargent, Webster, Crenshaw & Folley, 2112 Erie Blvd. E., Syracuse, Zone 3, shopping center, on 40 acre tract, on Rte 9. $3,000,000. Constr. within two months. (Correction-status). CD 10/1.

WHEN IT'S **COLD** *keep your job moving*

Clayton SUMMERAIRE

"120"
120,000 BTU's
at 950 cu. ft. of heated air per min.
$190
F. O. B.

PRE-HEATING MOTORIZED EQUIPMENT FOR EASY STARTING

DRYING NEW CONSTRUCTION PLASTER PAINT AND MASONRY

SPACE HEATING SEMI-ENCLOSED WORK AREAS

THAWING OUT FROZEN BULK SHIPMENTS AGGREGATES COAL ETC

PREVENTING THE FREEZING OF CONCRETE IN CURING STAGE

Clayton MFG CO.
Box 550
El Monte, California

New Medium Capacity Portable Heater

Announcing the new Clayton Summeraire "120" Portable Heater . . . a revolutionary "climatizer" especially designed for the construction industry. Small, light, compact, sturdy, the "120" is ideally suited to room-by-room drying of plaster, paint, masonry; for thawing out ground, aggregates, equipment.

MORE SAFE, ODORLESS HEAT AT LOWER COST

The Clayton Summeraire "120" delivers 950 cu. ft. of heated air per minute; 120,000 BTU's per hr., producing a temperature rise of 150°F. Burns less than 1 gal. fuel oil or kerosene per hr. Electric solenoid valve cuts off fuel supply in event of power failure. Controlled flame in enclosed combustion chamber insures odorless, fume-free air delivery. Other models in "300" series offer hourly heating capacities up to 375,000 BTU's per hr., electric or gasoline engine driven, with or without automatic thermostat control of pre-set temperatures. Ask for demonstration.

CLAYTON MANUFACTURING CO. ENR 11/56
BOX 550, EL MONTE, CALIF.

( ) Send me literature on new Model "120" Summeraire
( ) Send me literature on Model "300" Summeraire
( ) I'd like a free on-the-job demonstration without obligation

NAME _____
FIRM _____
ADDRESS _____
CITY _____ STATE _____



DRILLED PILING and BELLED CAISSONS | *consultants on foundation problems*

ALSO FORMATION TEST HOLES, STARTER HOLES FOR PILE DRIVING, ELEVATOR SHAFTS, DE-WATERING AND UNDERPINNING . . .

CAISSON SIZES . . . 16" to 84"
BELL SIZES . . . . . 2" to 15'
SHAFT DEPTHS . . . . . to 200'

CASE FOUNDATION CO.
Rt. 1, Roselle, Ill.

Phone (Chicago) . . . . . **Austin 7-3584**
Write for Specifications

KOHLER Electric Plants

for floodlights, power tools, where the work is done



Save man hours with independent electricity anywhere, any time. Portable, light-weight 2500 watt Kohler model provides low-cost power for floodlights, saws, drills, other electric tools. Has 4 receptacles, pilot light. Two-wheel, rubber-tired hand cart available. Other sizes, 500 watts to 35 KW. Write for folder N-2.

Model 2.5M25, *2500 watts, 115 volt A.C. Manual starting.*

Kohler Co., Kohler, Wisconsin
Established 1873

KOHLER OF KOHLER

PLUMBING FIXTURES • HEATING EQUIPMENT • ELECTRIC PLANTS
AIR-COOLED ENGINES • PRECISION CONTROLS

FOR CHARTER *Large or Small... Modern*

STEEL SCOWS · BARGES FLOATING EQUIPMENT

ALL CAPACITIES: DIMENSIONS RANGE FROM 20' TO 327' LONG, 25' TO 40' WIDE, 5' TO 12' DEPTH

HUGHES . . . the Charter Fleet that's custom-built to fill all Contractors' needs . . . at your service from Florida to Maine.

*With over 60 years' experience in chartering and selling marine equipment, we invite Contractors to consult us without obligation regarding requirements for any job.

HUGHES BROS., INC

17 Battery Place, New York 4, N. Y. **Tel. WHitehall 4-1048**

CLEARING HOUSE FOR MARINE DIFFICULTIES SINCE 1894

▲ **Pa., Export**—LABORATORY—Mellon Institute, 4400 5 Ave, Pittsburgh, plans by Charles & Edward Stotz, 801 Bessmer Bldg., Pittsburgh, 2 story, bsmnt. radiation research laboratory. $1,000,000. 300 volt Va de Graaf accelerator awarded to High Voltage Eng. Corp., Cambridge, Mass.

▲ **Tenn., Memphis**—OFFICE—Kemmons Wilson, 4985 Summer Ave., 18 story office. $4,000,000.

▲ **Tex., Ft. Worth**—MEDICAL CENTER—Lonark Corps., c/o H. R. Clement, pres., 832 Monroe St., plans by Herbert Voelcker & Assoc., 1202 Dennis St., Houston, medical center and hospital masonry and glass, White-settlement Rd. and Boland, $7,500,000.

▲ **Tex., Houston**—SHOPPING CENTER—Fairmount Park Shopping Center, c/o Wm. G. Farrington, Developer, 1661 Tanglewood St., shopping center units. $10,000,000.

▲ **Tex., San Antonio**—HOUSING—Trinity University, 715 Stadium Dr., plans by Bartlett Cocke, O'Neil Ford, 3501 Broadway, housing facilities. $1,000,000. CD 7/22/53.

▲ **Wash., Puyallup**—SHOPPING CENTER—W. K. Fanning, Puyallup, will not construct shopping center on land west of Meridian and north of River Rd.; $2,000,000. Project abandoned. CD 8/17.

▲ **Que., Montreal**—OFFICE—D. K. Besner Realties Regd., c/o Louis & Aspler, archts., 5165 Sherbrooke St. W., 10 story, 3 bsmnt. levels, 77x180 ft., rein.-con. office bldg. S.E. corner Mountain St. and proposed extension of Burnside Ave. $1,000,000.

INDUSTRIAL BUILDINGS

▲ **Calif., Antioch**—PLANT—Crown-Zellerbach Corp., 343 Sansome St., San Francisco, Zone 9, tissue, towels, napkins and bags converting plant. $8,000,000.

▲ **Calif., Dominguez**—PLANT—Borden Co., 350 Madison Ave., New York, N. Y., pentaerythritol plant. $1,000,000.

▲ **Conn., Newtown**—FACTORY—F. W. French Tube Co., 91 Walnut St., Watertown, 70x600 ft. factory for production of television tubes with railroad siding, Rt. 25, $1,500,000. (Correction—owners address). CD 10/29.

▲ **Mich., Detroit**—GARAGE—Griswold Garages, Inc., c/o H. E. Beyster & Assoc., archts., 700 Griswold Bldg., Zone 26, 10 story, rein.-con., steel garage, incl. 2 stores, Larned and Griswold Sts. $2,000,000.

▲ **Mich., St. Joseph**—PLANT—Health Div. of Daystrom, Inc., Benton Harbor, plant 16 acre site, Hilltop Rd., $1,500,000.

▲ **Mont., Missoula**—PLANT—Waldorf Paper Products Co., P. A. Schilling, pres., 2250 Wabash Ave., St. Paul, Minn., plans by G. Dimond Assoc., Inc., Endicott-on Fourth Bldg., St. Paul, Minn., pulp plant, main bldg., kilns, digesters, boilers, etc. $6,000,000 CD 10/25.

▲ **Tex., Bisnop**—PLANT—Celanese Corp. of America c/o 180 Madison Ave., New York, N. Y., expansion of chemical products plant, $6,500,000.

▲ **Tex., Houston**—STEEL PLANT—Jones & Laughlin Steel Corp., Melrose Bldg., steel plant. $300,000,000. Lockwood & Andrews, Union Natl. Bank Bldg., engrs., studying type structures needed for plant. A. C. Stimson Surveying Co., 2405 San Jacinto St., engr., site surveying. Raymond Concrete Pile Co., 610 Woodrow St., engr., drilling cores for fdn.

▲ **Tex., Houston**—PLANT—Texsteam Corp., 320 Hughes St., (subsidiary of Vapor Heating Corp., Chicago, Ill.), plant to mfg. various types of mechanical equipment. $1,000,000; storage or warehousing. $150,000, 14 acre site, between Post Oak Rd. and Sam Houston Airport.

▲ **Tex., Nacogdoches**—PLANT—Bassons Industries Corp., 1424 W. Farms Rd., New York., and c/o John Streit, Nacogdoches, plant to mfg plastic, teflon insulated wire and cable products, plastic pipe, etc. $2,000,000.

▲ **Alta., Edmonton**—WAREHOUSE, etc.—City, Civic Block, sketch plans by Bell & McCulloch, 9946-106th St., warehouse and workshop bldg. $1,500,000.

▲ **Ont., Brockville**—PLANT—Automatic Electric Sales Canada Ltd., 100 Strowger Blvd., plans by Percy Booth, 4795 St. Catherine St. W., Montreal, Que., 86,000 ft. plant expansion, $1,500,000. T. Pringle & Son Ltd., 4795 St. Catherine St., W., Montreal, Que., consult. engrs.

UNCLASSIFIED

▲ **California and Hawaii**—UNDERWATER CABLES—Pacific Telephone & Telegraph Co., 140 New Montgomery St., San Francisco, Calif., 2 underwater cables from near Point Arena, Calif. to KoKo Head, Oahu, T. H., $35,000,000. Construction to begin around June 1957.

▲† **N. Y., Niagara Falls**—AA FACILITIES—U. S Engr., 111 E. 16 St., New York, Zone 3, plans by Thomas H. McKaig, 881 Main St., Buffalo, AA support facilities, Field Maintenance Shop at Fort Niagara, $500,000-$1,000,000; plans by John J. Kassner, 111 Broadway, New York, AA support facilities, Field Maintenance Shop, plans by Duane Lyman Assoc., 505 Delaware Ave., Buffalo, New York, AA support facilities, 2 miscellaneous utilities, $100,000-$500,000. CD 12/20.

▲ **Ont., Toronto**—EXHIBITION GRANDSTAND—Canadian National Exhibition Assn., Exhibition Park, Toronto, plans by Marani & Morris, 1250 Bay St., rein.-con., steel, brick exhibition grandstand Exhibition Park, $6,000,000. CD 11/29/55.



New TARSET®

selected for Maximum Protection of Big Dam Facing

THE Huntington Lake power dams in Central California have performed yeoman service since their construction in 1917. But 38 winters in the High Sierra is a long time . . . long enough for the annual freezing and thawing cycles to react on the concrete surfaces of the dams' faces. Southern California Edison Company therefore took important maintenance measures last summer.

To provide maximum protection against corrosion, welded steel plates—behind which was poured a six-inch minimum thickness of concrete—were installed on the upstream faces of the two dams. The steel plates were then sandblasted and given a protective coating of Pitt Chem "Tarset," the new coal tar-epoxy resin coating.

Tarset, the toughest, hardest coating of its kind ever developed from coal tar, is being called upon to solve all sorts of corrosion problems formerly classified as "impossible." Tests show that Pitt Chem Tarset can stop corrosion caused by atmospheric exposure . . . sour crude petroleum and petroleum products . . . salts and acids. And it actually becomes harder at temperatures as high as 400°F!

What can Tarset do for you? Outline your corrosion problem—either by phone or letter—and we'll gladly help you solve it.

Send for Descriptive Booklet on TARSET today

Free booklet tells how to use amazing new Tarset to reduce costly corrosion. Gives detailed description of Tarset's specifications, properties and application characteristics. Write for *your* copy today!

WSW 6084

COAL CHEMICALS • PROTECTIVE COATINGS • PLASTICIZERS • ACTIVATED CARBON • COKE • CEMENT • PIG IRON

Bids—Low Bids—Contracts—Second Section

NEW ENGLAND

HEAVY CONSTRUCTION—BA

STATE HIGHWAY LETTINGS

BRIDGES

November 19 Connecticut November 20 Massachusetts
December 5 Rhode Island

STREETS AND ROADS

November 19 Connecticut November 20 Massachusetts

▲ **Mass., Chicopee Falls**—DORMITORIES—BA 11/26—U. S. Eng., 150 Causeway St., Boston, airmen's dormitories Westover Air Force Base, ENG-19-016-57-81. $1,000,000-$1,250,000. Plans deposit $35, refundable. Extended date. McClintock & Craig, Inc., 458 Bridge St., Springfield, and Cram & Ferguson, 248 Boylston St., Boston, archts. CD 10/11.

BUILDINGS—BA

▲ **Conn., Stamford** — FACTORY — BA 11/27 — Pitney-Bowes, Inc., 69 Walnut St., factory. $3,000,000. Leo F. Caproni, 132 Temple St., New Haven, archt. CD 12/15.

▲ **Mass., Amherst**—LABORATORY—BA 11/30—Commonwealth of Mass., University of Mass., Kenneth W. Johnson, treas., c/o Div. Bldg. Constr., 38 Chauncy St., Boston, U-602, 2 story brick, limestone trim chemistry laboratory addn. $1,694,000. Plans deposit $100. Appleton & Stearns, 53 State St., Boston, Mass., archts. CD 7/12/54.

▲ **R. I., Providence**—COLLEGE OF EDUCATION—BA 11/27—State R. I. & Prov. Plants, Div. Purchase, State House, Bid No. 394 to 401. Proj. No. Rice-23, College of Education Bldgs. $3,500,000. Plans deposit $150. Extended date. Howe, Prout & Ekman, 17 Custom House St., archts. CD 10/10.

▲ **Rhode Island**—HOUSING—BA 12/11—U. S. Eng., 150 Causeway St., Boston, Mass., construct and finance, Capehart Family House, at Bristol, North Kingston, Foster, North Smithfield and Coventry. ENG-19-016-57-17. $1,518,000. Plans deposit $10.

HEAVY CONSTRUCTION—LB & CA

▲ **Merritt-Chapman & Scott Corp.**, 260 Madison Ave., New York 3, N. Y., CA, **$3,271,063**. South Windsor-Windsor Bridge across Connecticut River, South Windsor-Windsor, HARTFORD, CONN. Hartford Bridge Auth., 284 Sheldon St., Hartford, Conn. Bids Oct. 2. CD 10/25, under LB.

BUILDINGS—LB & CA

▲ **Wexler Constr. Co.**, 118 Needham St., Newton Highlands, Mass., CA **$1,307,700**. four DORMITORIES, HANOVER, N. H. Trustees Dartmouth College, Hanover, N. H. Bids Oct. 16. CD 10/18, under LB.

▲ **E & F Constr. Co.**, 94 Wells St., Bridgeport, Conn., LB **$1,398,000** (6 bidders) two 4 story WOMEN'S DORMITORIES, DINING HALL, BRIDGEPORT, CONN. University of Bridgeport, 200 Park Pl., Bridgeport, Conn. Bids Oct. 30. CD 10/10.

MIDDLE ATLANTIC

HEAVY CONSTRUCTION—BA

STATE HIGHWAY LETTINGS

BRIDGES

November 30 Pennsylvania

STREETS AND ROADS

November 30 Pennsylvania

BUILDINGS—BA

▲ **Pa., Monroeville** — HIGH SCHOOL — BA 11/19 — Monroeville School Auth., Turtle Creek, 1 and 2 story, approx. 150,000 sq. ft. masonry and aluminum Senior High School. $2,500,000. Plans deposit $100. Walter Schardt Assocs., 1001 South Ave., Wilkinsburg, archts. CD 6/19.

▲ **N. J., Atlantic City**—HOSPITAL WING—BA 12/14 Atlantic City Hospital, 26 S. Ohio Ave., new hospital wing and also entrance bldg. $2,500,000. Vincent G. Kling, 9818 Corinthian Ave., Phila., Pa., archt. Keast & Wood, 2031 Chestnut St., Phila Pa., engrs. CD 5/10.

† **N. Y., Bath**—RECREATION-THEATRE—BA 1/15—Veterans Admin., Munitions Bldg., Wash., D. C., constr. Recreation and Theatre Bldg. No. 92, Veterans Admin. Center. $900,000-$1,400,000. CD 9/19.

HEAVY CONSTRUCTION—LB & CA

▲ **Comrs. Parks, Dpt. Parks**, Arsenal Bldg., Central Park, 64 St. and Fifth Ave., New York 21, N. Y. rejected bids Oct. 22, South Beach Imprvts., Contr. 4A, promenade, playgrounds, parking field, utilities, Miller Field to Iona St., Richmond Boro, NEW YORK. LB $1,553,877 (A); LB $575,696 (B). CD 10/24, under LB.

BUILDINGS—LB & CA

▲ **Asbury Park Enterprises**, c/o Cronheim, 39 Branford Pl., Newark, N. J., CA, Est. **$1,500,000**. 7 story APARTMENT and STORES, Ocean Ave. between Asbury and 1 Ave., ASBURY PARK, N. J. Cronheim, Inc., 39 Branford Pl., Newark, N. J. Henry Boyer, c/o owner, archt.

▲ **Ritter Bros.**, 1511 N. Cameron St., Harrisburg, Pa. LB **$1,214,609**. general constr. JUNIOR SENIOR HIGH SCHOOL, ENOLA, PA. East Pennsboro Twp. School Auth. School Bldg., Enola, Pa. Bids Oct. 30. CD 10/3.

▲ **United Engineers & Constructors, Inc.**, 1401 Arch St., Phila., Pa. CA **$1,000,000**. HOSPITAL, PHILA., PA. The Magee Memorial Hospital for Convalescents, c/o Thomas Hart, pres. Bd. Trustees, 15 and Walnut Sts., Phila., Pa. Hatfield Martin & White, 266 S. 17 St., Phila., Pa., archts. Horace B. Nicholson, 215 S. Broad St., Phila., Pa., engr. CD 1/26.

▲ **Ernest Di Sabatino & Sons**, 2601 W. Fourth St., Wilmington, Del., LB **$1,769,000**. Ogletown JUNIOR HIGH SCHOOL, Ogletown, NEWARK, DEL. Bd. Educ., Newark, Del. Bids Oct. 31. CD 12/13.

SOUTH

HEAVY CONSTRUCTION—BA

STATE HIGHWAY LETTINGS

BRIDGES

November 21 Virginia

STREETS AND ROADS

November 21 Virginia November 30 Kentucky

BUILDINGS—BA

▲ **La., Alexandria**—HOUSING—BA On Or About 11/28—Base Procurement Office, England Air Force Base, construct and finance 300 housing units, armed services housing. (Capehart), Bids No. 16-600-57-34, $3,000,000. CD 10/10, under LB.

HEAVY CONSTRUCTION—LB & CA

▲ **Vanguard Constr. Co.**, 3478 Westminster Ave., Norfolk, Va., CA **$1,229,804**, sewers, RICHMOND, VA. City, Director Purchases & General Services, Mosque Bldg., Laurel and Main Sts., Richmond, Va. Bids Oct. 16. CD 8/31.

▲ **E. G. Singletary & Co.**, 105 Homewood Dr., Greensboro, N. C., LB **$1,144,600**, sewage treatment plant, GREENSBORO, N. C. City, City Hall, Greensboro, N. C. Bids Oct. 30. CD 10/18.

▲ **FLORIDA**—State Road Dpt., Tallahassee,
C. A. Scott Constr. Co. and Faulk & Coleman Constr. Co., Box 938, Tallahassee Fla., CA, **$1,156,104**. limerock, base, b. conc. box culverts, twin bridges, conc. sheet pile bulkheads 5.078 mi. SR 5, Job 7901-175, Volusia Co. Bids Oct. 31, awarded Nov. 1. CD 10/16, under LB.

▲ **Houston Contg. Co.**, 2707 Ferndale St., Houston, Tex. CA **$3,250,000**, 120 mi. 20 in. and 11 mi. 16 in. natural gas lines from Eunice to east near Thibadoux, LOUISIANA. Texas Gas Transmission Corp., Melrose Bldg., Houston, Tex. CD 12/16.

BUILDINGS—LB & CA

▲ **U. S. Eng.**, 2301 Grant St., Mobile 7, Ala., rejected bids Oct. 9, construct and finance 100-unit Capehart family HOUSING, ENG-01-076-57-2, FORT McCLELLAN, ALA. Will re-advertise. CD 10/12, under LB.

▲ **U. S. Eng.**, Box 1229, Galveston, Tex., cancelled bids to have been opened Oct. 31, construct and finance 2,000-unit permanent family HOUSING, Inv. 57-8, (Capehart) FORT POLK, LA. $15,000,000. CD 10/25.

▲ **Farnsworth & Chambers Co., Inc.**, Box 332, New Orleans, La., CA **$1,244,600**. 5 story Our Lady of Lourdes HOSPITAL addn., LAFAYETTE, LA. Our Lady of Lourdes Hospital, Lafayette, La. Bids Aug. 15, awarded Oct. 25. CD 8/29, under LB.

MIDDLE WEST

HEAVY CONSTRUCTION—BA

STATE HIGHWAY LETTINGS

BRIDGES

November 20 Illinois November 21 Michigan

STREETS AND ROADS

November 20 Illinois November 21 Michigan
November 27 Ohio

BUILDINGS—BA

▲ **Mich., Holly**—SCHOOL—BA 11/29—Village, Holly Area School Dist., high school, Maple Ave. $1,200,000. Plans deposit $25. Extended date, H. E. Beyster & Assoc., Inc., 700 Griswold Bldg., Detroit, Zone 26, archt. CD 11/1.

▲ **Wis., LaCrosse**—SCHOOL—BA 11/29—Bd. Educ., 2 and 3 story, 185x214 ft. Logan High School addn., alterations. $1,100,000. Schubert, Sorensen & Assoc., 308 Hoeschler Bldg., engrs. CD 11/17/55.

▲ **Ill., Evanston**—HOSPITAL—BA 12/4—Evanston Hospital Assn., 2650 Ridge Ave., 6 story hospital addn. $3,500,000. Burnham & Hammond, 52 W. Jackson Blvd., Chicago, archts. CD 11/9/55.

BUILDINGS—SLC

▲ **Ill., Chicago Heights**—HIGH SCHOOL—Catholic Bishop of Chicago, 719 N. Wabash St., Chicago, soon lets contract Central Catholic High School, bit. driveways, parking lot, southwest corner Joe Orr Rd. and Ashland Ave. $1,500,000. R. L. Ignelzi; 29 W. 16 St., archt. Perkins & Will, 309 W. Jackson Blvd., Chicago, assoc. archts. CD 8/28/52.

HEAVY CONSTRUCTION—LB & CA

▲ **OHIO**—State Hy. Dpt., Columbus,
O.—**W. J. Elliott & Sons**, Rte. 4, McConnelsville, O. LB **$159,000**, est. $173,500 (5 bidders) Type T-170, T-32 and structure 0.217 mi. SR 682-0.08, S-1137 (1), Proj. 447, Athens Co.;
O.—**National Engineering & Contracting Co.**, 1968 W. Third St., Cleveland, O., LB **$1,765,790**, est. $1,629,700 (3 bidders) type T-71 and structure 0.341 mi. USR 42R-17.43, I-1057 (2), City of Cleveland, Proj. No. 448, Cuyahoga Co.;
O.—**Foley Constr. Co.**, 5050 Orchard St., Cincinnati, O. LB **$2,458,485**, est. $2,816,200, (8 bidders) type T-71 and structures 3.061 mi. SR 4W-7.81, I-316 (7), City of Cincinnati, Village of Elmwood Place, Proj. No. 449, Hamilton Co.;
O.—**Arthur S. Langenderfer, Inc.**, 4690 W. Bancroft St., Toledo, O., LB **$949,965**, est. $996,600 (2 bidders) Type T-50 on B-20 and T-70, 3.284 mi. C. R. No. 6, S-1209 (1), Village of Sylvania, Proj. No. 450, Lucas Co.;
O.—**The A. Bentley & Sons Co.**, 201 Belmont Ave., Toledo, O., LB **$3,325,000**, est $3,922,000 (7 bidders) type T-71 and structures 3.02 mi. USR 24-A-4.04, I-1052 (13), City of Toledo, Proj. No. 451, Lucas Co.;
O.—**Nilen Black, Inc.**, 706 E. Highland Ave., Wooster, O., LB **$237,712**, est $255,700 (5 bidders) type T-35, structure, 1.113 mi. SR 212 (2.73-3.50), S-1203 (1), Village of Bolivar, Proj. No. 452, Tuscarawas Co.;
O.—**A. J. Baltes, Inc.**, 11 Olive St., Norwalk, O., LB **$798,238**, est $890,100 (4 bidders) Type T-71 and structures 1.845 mi. SR 10-(13.75-15.25), Proj. No. 453, Lorain Co.; LB **$346,315**, est. $388,000 (4 bidders) Type T-71, 1.516 mi. USR 30N-6.13, Proj. 457, Richland Co.;
O.—**The McCourt Constr. Co.**, 720 Home Ave., Akron, O. LB **$169,606**, est. $160,100, Type T-35, 1.785 mi. SR 548-0.00, 21.36, Proj. No. 454, Medina and Wayne Counties;
O.—**Sidwell Bros.**, Rte. No. 2, S. Zanesville, O., LB **$234,808**, est. $340,900 (5 bidders) Type T-35, 3.105 mi. SR 75-4.71, Proj. No. 456, Perry Co.;
O.—**Peerless Constr. Co.**, 560 Rawson Ave., Fremont, O. LB **$141,357**, est. $148,200 (5 bidders) Type T-35, 0.803 mi. USR 6-21.59, Proj. 458, Sandusky Co.;
O.—**Smith Constr. Co. of Ohio**, P. O. Box 515, Vienna, O. LB **$519,417**, est. $532,000 (2 bidders) Type T-35 and structures 5.317 mi. SR 88-(7.04-11.93), Proj. 460 Trumbull Co.;
O.—**Harper Supply, Inc.**, 118 W. Front St., Napoleon, O., LB **$155,409**, est. $179,800 (5 bidders) Type T-35 on-B-70 and structures 0.312 mi. SR 127-(12.37) (13.54), (15.16), Proj. 461, Van Wert Co.;
O.—**Shelly & Sands, Inc.**, Thornville, O., LB **$1,214,766**, est. $1,410,600 (3 bidders) Type T-35, 10.936 mi. USR 50A-29.60; SR 7-40.23, Washington Co. Bids Oct. 30. CD 10/22.

▲ **ILLINOIS**—State Div. Hys., Centennial Bldg., Springfield,
General Paving Co., Inc., 303 John St., Champaign, Ill., CA, **$2,647,348**. c. conc. paving 3.71 mi. concrete base course 1.17 mi. bit. resurf. all on U. S. 45, Champaign Co. Bids Oct. 23. CD 10/26, under LB.

▲ **Robert R. Anderson Co.**, 4550 W. Patterson St., Chicago, Ill., LB **$2,049,141**. Calumet Skyway Toll Bridge; Sect. 3-A-1, substructure for structures, storm sewers paving, etc. Dante Ave. to N. side of Elliott Ave., CHICAGO, ILL. City, City Hall, Chicago, Ill. Bids Nov. 1. CD 10/9.

▲ **Lombard & Long Co.**, 600 W Jackson Bldg., Chicago, Ill., CA, **$1,049,546**, pumping station, chemical bldg. filter bldgs., etc., LAKE FOREST, ILL. City, City Hall, Lake Forest, Ill. Bids Sept. 17, CD 10/8, under LB.
Kuch & Watson, Inc., Lake Forest, Ill., CA, **$397,387**, water mains (Lake Forest, Ill.).

▲† **Al Johnson Constr. Co.**, 608 Foshay Tower, Minneapolis, Minn., **Peter Kiewit Sons Co.**, 1024 Omaha National Bank Bldg., **Cunningham, Kiewit Co.**, 4229 Lafayette St., Omaha, Neb. and **Morrison-Knudsen Co., Inc.**, 319 Broadway Ave., Boise, Idaho. (joint bid) LB **$18,338,145**. dredging Amherstburg Channel 15 mi. down Detroit River from Woodward Ave., deepen from 21 ft. at present to 27.5 ft., Wayne Co., MICHIGAN. U. S. Eng., 600 E. Jefferson Ave., Detroit 26, Mich. Bids Nov. 2. CD 9/9/54, under New York.

BUILDINGS—LB & CA

▲ **Cantrell Brothers**, 116 York Ave., Elmhurst, Ill., Own Forces, **$6,000,000**. 240 HOMES, sewers, water and streets Grand and York Rd.; **$2,000,000**. SHOPPING CENTER, Grand and York Rd., BENSENVILLE, ILL.

▲ **Sumner Sollitt Co.**, 307 N. Michigan Ave., Chicago, Ill., LB **$2,187,000**. 204-unit HOUSING, Prairie Ave., Courts Exten., South Park Ave. and 27 St., CHICAGO, ILL. Chicago Housing Auth., 608 S. Dearborn St., Chicago, Ill. Bids Oct. 30. CD 10/18.

▲ **Tonyan Constr. Co.**, 100 Borden St., McHenry, Ill., LB **$1,544,312**. HIGH SCHOOL addn., swimming pool, 500 S. Green St., MCHENRY, ILL. School Dist. 156, 500 S. Green St., McHenry, Ill. Bids Oct. 12. CD 10/2.

▲ **S & L Constr. Co.**, 910 Penobscot Bldg., Detroit, Mich. CA Est. **$1,200,000**. SHOPPING CENTER, Grand River and Mooney St., FARMINGTON, MICH. Farmington Shopping Center, Farmington, Mich. Bids Oct. 23. CD 10/22.

WEST OF MISSISSIPPI

BUILDINGS—BA

▲ **Mo., St. Louis County**—DISTRIBUTION CENTER—BA 11/20—General Electric Appliance Div., General Electric Corp., 5021 Fyler Ave., St. Louis, Zone 9, 1 story, masonry, steel, concrete distribution center incl. 110,000 sq. ft. warehouse, 25,000 sq. ft. office

and display area, rail siding and truck loading facilities west side Warson Rd., in Lindbergh-Warson Industrial Center. $1,000,000. Syl G. Schmidt & Assoc., 1819 Railway Exchange Bldg., 611 Olive St., St. Louis, Zone 1, archt.-engr. CD 10/1.

▲ **Tex., Austin**—SUPREME COURTS—BA 11/30—State, State Bldg. comn., Administration Bldg., 7 story, 2 bsmnt. levels, 148,000 sq. ft. supreme courts bldg. $3,000,000. Bid date changed. Jessen, Jessen, Millhouse & Greeven, 2816 Hemphill Park, Page, Southerland & Page, 602 West Ave., Austin and Mackie & Kamrath, 2713 Ferndale St., Houston, archts. Walter P. Moore, 2 Pinedale St., Houston and Blum & Gurrero, 1111 Neches St., Austin, engrs. CD 10/31.

▲ **Tex., Fort Worth**—CIVIL COURTS—BA 12/5—Tarrant Co., c/o Gus Brown, judge, Court House, 5 story, masonry civil courts bldg. on Courthouse Square. $2,-200,000. Plans deposit $50. Wyatt C. Hedrick Co., 1200 T & P Bldg., archt. CD 6/8.

▲ **Mo., St. Louis County**—SCHOOL—BA 12/6—St. Louis Archdiocese of Catholic Church, Rev. James R. Hartnett, exec. secy, 3810 Lindell Blvd., St. Louis, Zone 8, St. Thomas of Aquinas High School on 13 acre tract northside Lindbergh Blvd. at intersection with San Fernando Hills subdivision. $1,500,000. Hellmuth, Obata & Kassabaum, 315 N. 10 St., St. Louis, Zone 1, archts. CD 5/31.

▲† **Iowa., Burlington**—POST OFFICE—BA About 12/12—General Service Admin., P. Bldgs. Serv., General Service Bldg., 19 and F Sts. N.W., Wash. 25, D. C., (a) financing, constructing and sale of building (b) financing construction and sale of the building, (c) construction of building, U. S. Post Office, etc., Jefferson, Main and Front Sts. $1,114,000. CD 11/16/55.

▲† **Kan., Kansas City**—POST OFFICE—BA About 12/12—General Services Admin., P. Bldgs. Serv., General Services Bldg., 19 and F Sts. N.W., Wash. 25, D. C. (a) financing, constructing and sale of building (b) financing construction and sale of the building, (c) constructing building, U. S. Post Office and Court House, Seventh and Ann Ave. and Armstrong Ave. $1,930,-000. CD 10/4/55.

▲ **Kan., Topeka**—HOUSING—BA 1/15—Purchase Div. Directorate of Procurement & Prof. Topeka Air Force Base, Topeka, construct and finance 640 housing units, for armed services, (Capehart), Inv. 512. $7,500,000. CD 2/13.

▲ **Tex., El Paso**—SHOPPING CENTER—Bids Asked—Owners, c/o J. Ted Cottle, 112 N. Stanton St., shopping center. $3,250,000. CD 9/26/55.

BUILDINGS—SLC

▲ **Tex., Amarillo**—DEPARTMENT STORE—Sears Roebuck & Co., 925 S. Homan St., Chicago, Ill., soon lets contract 104,000 sq. ft. department store. $1,-000,000. George L. Dahl, 2101 N. St. Paul St., Dallas, archt. CD 4/19.

HEAVY CONSTRUCTION—LB & CA

▲ **MISSOURI**—State Hy. Dpt., Jefferson City,
Mo.—**W. J. Menefee Constr. Co.**, 419 W. Main St., Sedalia, Mo. LB $1,057,644. c. conc. 10.543 mi., St. Charles Co.;
Mo.—**Koss Constr. Co.**, 205 Farm Bureau Bldg., Des Moines, Iowa. LB $701,224. 24 ft. c. conc. 6.885 mi., Dunklin Co.;
Mo.—**M. E. Gillioz**, Monett, Mo. LB $493,017. 24 ft. c. conc. 4.88 mi., Barry Co.; LB $79,635. 24 ft. c. conc. 0.35 mi., Barry Co.;
Mo.—**J. A. Tobin Constr. Co.**, 3700 Rainbow Blvd., Kansas City, Mo. LB $156,717. 24 ft. c. conc. 1.26 mi., Buchanan Co.; LB $119,899. 24 ft. c. conc. 0.921 mi., Andrew Co.;
Mo.—**Frank Trager**, Chillicothe, Mo. LB $89,881. grav. or crushed stone surf. 9.354 mi., Saline Co.;
Mo.—**R. G. Aldridge**, 1610 Nebraska St., Kansas City, Kan. LB $863,737. c. conc., sanitary sewer, water main, Marion Co. Bids Nov. 1. CD 10/19.

▲ **TEXAS**—State Hy. Dpt., Austin,
James Constr. Co., Box 9575, Oklahoma City, Okla. CA $1,128,637. 0.176 mi. Corpus Christi Ship Channel Bridge, Contr. II, substructure for steel spans on Hy. US 281, Proj. U 204 (7), Nueces Co. Bids Oct. 18. CD 10/24, under LB.

▲ **TEXAS**—State Hy. Dpt., Austin,
rejected bids Oct. 17, Contr. III Corpus Christi Ship Channel Bridge, Fed. Proj. U-204 (8), Nueces Co. LB $3,911,816 (Correction—status). CD 10/24, under CA.

▲ **Flenniken Constr. Co.**, 5206 Maple St., Dallas, Tex., and **L. H. Lacy Constr. Co.**, 5603 Yale St., Dallas, Tex. CA $4,928,685. combined work at Love Field, DALLAS, TEX. City, City Hall, Dallas, Tex. Bids Oct. 29. CD 11/1, under LB.

BUILDINGS—LB & CA

▲ **Cowdin Bros.**, 411 S. Haskell St., Dallas, Tex. CA $1,367,119, NEWSPAPER PLANT addition, DALLAS, TEX. Dallas Times Herald, Herald Square, Dallas, Tex. Bids Sept. 14. CD 10/8, under LB.

▲ **J. E. Morgan & Sons**, Box 6029, Dallas, Tex., LB $1,686,200, est. $2,000,000. 8 story OFFICE-BANK, Preston Rd., DALLAS, TEX. Preston State Bank, c/o R. E. Alexander, Jr., 3704 Abrams Rd., Dallas, Tex., archt. Bids Oct. 30. CD 10/2.

▲ **Jones-Hettelsater Constr. Co.**, 1911 Baltimore Ave., Kansas City, Mo., CA Est. $1,000,000. 60x50 ft. rein.-con. MILL, 84x300 ft., steel, concrete WAREHOUSE, 37x75 ft. concrete OFFICE BLDG., FORT WORTH, TEX. General Mills, Inc., 400 2nd Ave. S., Minneapolis, Minn.

▲ **Linbeck Constr. Co.**, Box 13007, Houston, Tex., LB $2,535,000, est. $2,600,000. Yates Area SENIOR HIGH SCHOOL, HOUSTON, TEX. Houston Independent School Dist., 1300 Capitol St., Houston, Tex. Bids Nov. 1. CD 10/3.

▲ **Southwestern Constr. Co.**, Box 1204, Houston, Tex. CA $1,000,000. PLANT or MAINTENANCE BLDG., HOUSTON, TEX. Hughes Tool Co., 5425 Polk St., Houston, Tex. CD 4/25.

▲ **Fish Engineering Corp.**, M & M Bldg., Houston, Tex. CA $6,000,000. design and construct petrochemical styrene PLANT, ODESSA, TEX. Odessa Styrene Co., c/o C. L. Moore of El Paso Natural Gas Products Co., Odessa, Tex. CD 11/7.

▲ **Lembke-Clough & King, Inc.**, 1013 Arcturus Dr., Colorado Springs, Colo., LB $6,463,069. 12 story 300-bed HOSPITAL, COLORADO SPRINGS, COLO. Glockner-Penrose Hospital, 2200 N. Tejon St., Colorado Springs, Colo. Bids Oct. 31. CD 9/18.

FAR WEST

HEAVY CONSTRUCTION—BA

STATE HIGHWAY LETTINGS
BRIDGES
November 28, December 5 California
November 29 Nevada
STREETS AND ROADS
November 28, 29, December 5, 6 California

▲ **Calif., Los Angeles**—BA 12/14—Los Angeles County Flood Control Dist., 2250 Alcazar St., Proj. 84, Slauson Ave. Relief Drain, $6,493,000. H. E. Hedger, c/o owner, engr. CD 11/7/52.

BUILDINGS—BA

▲ **Calif., Centerville**—HOSPITAL—BA 11/27—Washington Township Hospital, Bd. Directors, Washington Twp., Centerville, Washington Township Hospital addn. $1,500,000. Plans deposit $100 for general contract; $25 for others. Stone, Mulloy, Marraccini & Patterson, Architects, AIA, 619 California St., San Francisco, archts. CD 2/14.

▲ **Wash., Mount Vernon**—HOSPITAL—BA 11/27—Public Hospital Dist. No. 1, 2 story, 78 bed hospital, $1,000,000. Plans deposit $50. J. W. Maloney, Central Bldg., Seattle, Zone 4, archt. CD 9/20.

BUILDINGS—SLC

▲ **Calif., San Jose**—PLANT—International Business Machines, 99 Notre Dame St., soon lets contract rein.-con., structural steel I.B.M. Plant Phase No. 2. $8,750,000. John S. Bolles, 215 Leidesdorff St., Pier 5, San Francisco, archt. CD 10/25.

HEAVY CONSTRUCTION—LB & CA

▲ **El Paso Natural Gas Co.**, E. P. N. G. Co. Bldg., El Paso, Tex. Own Forces, $9,500,000. laying 193 mi. 34 in. gas line between San Juan Basin and Topock, $1,350,000. laying 38 mi. 20 in. gas line between San Juan Main line and Phoenix, ARIZONA. CD 2/5/53, under Texas, New Mexico, Arizona and California.

▲† **U. S. Eng.**, 751 S. Figueroa St., Los Angeles, Calif., cancelled bids to have been opened Nov. 8, airmen's dormitories, Luke Air Force Base, ENG-04-353-57-30, PHOENIX, ARIZ. $1,000,000. CD 10/17.

▲ **CALIFORNIA**—State Div. Hys., 1120 N. St., Sacramento,
Gordon H. Ball and Ball & Simpson, 685 Delaware St., Berkeley, Calif., LB $6,419,253, est. $6,900,000. (7 bidders) freeway 9.9 mi. with frontage roads, ramps and interchanges and 14 bridges pumping plant between Arm Springs Junction and Beard Rd., Alameda Co. Bids Nov. 7. CD 10/4.

▲ **CALIFORNIA**—State Div. Hys., 120 S. Spring St., Los Angeles,
Peter Kiewit Sons Co., 345 Kieways Ave., Arcadia, Calif., CA $2,168,770. grading, surf. 7.2 mi. U. S. Alternate 101, Ventura Co. Bids Oct. 18, awarded Nov. 2. CD 10/22, under LB.

▲† **Diversified Builders, Inc.**, P. O. Box 390, Montebello, Calif., LB $1,080,000 (4 bidders) ground ballastic ranges, Naval Ordnance Test Station, China Lake, Spec. 4198-56, INYOKERN, CALIF. Eleventh Naval Dist., 1220 Pacific Hy., San Diego, Calif. Bids Nov. 1. CD 10/18.

BUILDINGS—LB & CA

▲ **Campbell Constr. & Equip. Co.**, 1150 Folsom St., San Francisco, Calif., CA Est. $3,000,000. 4-story SEMINARY, KENMORE, WASH. Catholic Archdiocese of Seattle, 907 Terry St., Seattle; Wash. J. W. Maloney, Central Bldg., Seattle 4, Wash., archt. CD 10/25.

▲ **Campbell Constr. Co.**, 800 "R" St., Sacramento, Calif., CA $1,183,321. La Sierra HIGH SCHOOL addn., CARMICHAEL, CALIF. San Juan Union High School Dist., 7551 Greenbach Lane, Fair Oaks, Calif. Bids Oct. 24, awarded Oct. 31. CD 11/1, under LB.

▲ **Dinwiddie Constr. Co.**, 210 Crocker Bldg., San Francisco, Calif., CA, $2,016,000. 3 story, 82,226 sq. ft. DEPARTMENT STORE, HAYWARD, CALIF. The Emporium-Capwell Co., 835 Market St., San Francisco, Calif. Welton Becket & Assoc., 155 Maiden Lane, San Francisco, Calif., archts. CD 2/8/55.

▲ **Hayward Union High School Dist.**, 22300 Foothill Blvd., Hayward, Calif., rejected bids Sept. 12, Tennyson HIGH SCHOOL, HAYWARD, CALIF. LB $3,038,-000. CD 9/20, under LB.

▲ **Campbell Soup Co.**, c/o John S. Bolles, archt., Pier 5, San Francisco, Calif., rejected bids Oct. 9, 1 story concrete block, mushroom PLANT, Gazos Creek Area, PESCADERO, CALIF. Est. $1,000,000. Will readvertise. CD 10/2.

▲ **McNeil Constr. Co.**, 5858 Wilshire Blvd., San Diego, Calif., CA, $2,404,346. FACTORY OFFICE BLDG., 5001 Hearney Villa Rd., SAN DIEGO, CALIF. Convair Astronautics Div., General Dynamics Corp., 3165 Pacific Hy., San Diego, Calif. Bids Oct. 17, awarded Oct. 20. CD 5/4.

▲ **Williams & Burrows**, 500 Harbor Blvd., Belmont, Calif. CA, $4,561,615. 7 story, rein.-con. NURSING WING, Santa Clara County Hospital, SAN JOSE, CALIF. Bd. Supervs., Santa Clara Co., Court House, San Jose, Calif. Bids Oct. 3, awarded Oct. 26. CD 10/9, under LB.

▲ **San Mateo Investment Co.**, 25 Ave. and South El Camino Rezl, San Mateo, Calif., Owner Builds. $1,-000,000. 24-alley BOWLING ALLEY, SAN MATEO, CALIF. Gordon F. Powers, 3667 Atlantic Ave., Long Beach, Calif., archt. CD 5/16.

CANADA

HEAVY CONSTRUCTION—BA

STATE HIGHWAY LETTINGS
STREETS AND ROADS
November 21 Ontario

BUILDINGS—BA

▲ **Ont., Toronto**—HOSPITAL—BA 12/12—City, City Hall, Toronto East General Hospital extension incl. (1) North and south exten. to west wing, (2) outpatients dept. exten. (3) laundry and interns' residence (4) laundry and internes residence (alternative design) Coxwell and Sammon Aves., East York, $3,200,-000. Auguste Martineau & Assocs., 2291A Yonge St., archt. Arthur H. Frampton & Co., 38 King St. W., engrs. CD 2/6.

HEAVY CONSTRUCTION—LB & CA

▲ **Poole Constr. Co., Ltd.**, 2402 2a St., S. E., Calgary, Alta, CA Est. $7,000,000. 70 ft. high, 1,000 ft. long earthfill dam on Whitehorse Rapids to provide area with hydro-electric power, Whitehorse, YUKON TERRITORY, Northern Canada Power Comn., 150 Wellington St., Ottawa, Ont. Bids Oct. 29, awarded Oct. 30. CD 10/7.

BUILDINGS—LB & CA

▲ **Atlantic Development & Investment Corp. Ltd.**, 51 Yonge St., Toronto, Ont. Owner Builds, $10,000,000 493-room, 22 story, rein.-con., glazed brick, HOTEL, Carlton St., 450-car 7-level ramp GARAGE at rear of hotel, TORONTO, ONT. E. I. Richmond, 455 Spadina Ave., Toronto, Ont. archt. CD 1/5, under Ben Seaton, as owner.

▲ **Atlantic Development & Investment Corp., Ltd.**, 51 Yonge St., Toronto, Ont. Owner Builds. $15,000,000. 18 story OFFICE, Carlton and Younge Sts., TORONTO, ONT. E. I. Richmond, 455 Spadina Ave., Toronto, Ont., archt. CD 3/21.

LATIN AMERICA

HEAVY CONSTRUCTION—LB & CA

▲ † **PANAMA**—Bureau P. Rds., Dpt. Commerce, Inter-American Hys., 18 and F Sts. N. W., Wash. 25, D. C.
Framoroco S.A. and Constructora del Pacifico, Panama City, CA $2,477,416. Proj. 15, approx. 28 mi. grading, small drainage structures, selected materials sub-base, crushed stone base course and nine bridges. Bids Oct. 17. CD 10/23, under LB.

AMERICANS ABROAD

HEAVY CONSTRUCTION—BA

▲ Bids are being taken on the following project under International competitive bidding of NATO.

FRANCE

Secretariat d'Etat a l'Industrie et au Commerce, Service Special des Depots d'Hydrocarbures, 85 Boulevard du Montparnasse, Paris, supply and installation of pipes as follows: 87 kilometers 10 in. pipe Langres-Mirecourt, $2,430,000; 101 kilometers, 10 in. pipe, Mirecourt-Phalsbourg, $2,857,140; Mirecourt-Metz 76 kilometers, 8 in. pipe, $1,940,208; Deux-Ponts-Phalsbourg, 48 kilometers of 8 in. pipe, $1,125,714; Phalsbourg-Strasbourg, 56 kilometers 8 in. pipe, $1,400,000; Metz-Marville, 74 kilometers, 4 in. pipe, $1,057,000. Firms wishing to participate in this work should submit their applications to bid before November 17. Bids Asked.

Companies desiring to bid who are not already certified to participate in NATO projects should send their qualifications to the Trade Development Division, Bureau of Foreign Commerce, U. S. Department of Commerce, Wash. 25, D. C., for a brochure describing the NATO international bidding program.

▲ Bids are being taken on the following project under International competitive bidding of NATO.

Ministero Difesa-Aeronautica, Direzione Generale Demanio, Ufficio Studi, Ia Sezione, viale Castro Pretorio, Rome.

ITALY

Proj. 054, const. 7 pumping stations and 2 fuel storages interconnected to pipe line. $1,520,000. Firms wishing to participate in this project should submit their applications before November 12 for opening of bids December 20. A brochure describing the NATO international competitive bidding program is available on request from the Trade Development Division.

(Proposal Advertisement see pp. 119 to 122)

Construction Scoreboard

Activity this Week



AMOUNT OF CONTRACTS LET

By Ownership	This Week	Cum. 46 wks 1956	Chge %
	millions		
Federal	$50.4	$1,533.9	+1
State and Municipal	116.6	5,840.6	+25
Total Public	167.0	7,374.5	+19
Total Private	202.8	12,012.5	+14
U. S. Total	$369.8	$19,387.0	+16
By Type of Work			
Waterworks	$5.4	$318.9	+32
Sewerage	10.6	535.2	+54
Bridges	10.5	556.8	+29
Highways	45.9	2,218.8	+16
Earthwork, Waterways	6.7	661.4	+35
Buildings:			
Public, Excl. Housg.	37.5	1,844.5	+21
Public Housing	1.0	288.5	+21
Private Housing	61.6	4,922.7	−12
Commercial	27.9	1,706.4	+13
Industrial	94.1	4,706.7	+84
Unclassified	68.6	1,627.1	−12
U. S. Total	$369.8	$19,387.0	+16

NOTE: Minimum size projects included are: Waterworks and waterways, $44,000; other public works, $73,000; industrial buildings, $93,000; other buildings, $344,000.

NEW CAPITAL FOR CONSTRUCTION

	Week of Nov. 8	Cum. 45 wks 1956	Chge '55-'56 %
	millions		
Corporate Securities	$85.1	$4,260.9	+37
State and Municipal:			
All Except Housing	61.1	4,086.3	−1
Housing	48.4	70.7	−2
Federal Loans	...	134.0	+12
Federal Aid	...	1,070.0	+25
Total Nonfederal	$194.6	$9,641.9	+16
Federal Appropriations:			
In U. S.	$...	$3,460.3	+2
Outside U. S.	...	15.9	−81
Total New Capital	$194.6	$13,118.1	+12

Cost Indexes as of Now

ENR INDEXES (1913 = 100), 20-cities' average	Week of Nov. 8 1956	% Change from Oct. 11 1956	% Change from Nov. 10 1955
Construction Cost	704.13†	−0.02	+4.7
Building Cost	500.48	+0.1	+4.5

† Last week this index listed as 904.13 instead of 704.13.

To convert above indexes to 1926 = 100: Divide Construction Cost by 2.080; Building Cost by 1.850.
1949 = 100: Divide Construction Cost by 4.770; Building Cost by 3.518.



CONTRACTS AWARDED

Millions of dollars	October 1956	10-Mos. 1956	% Change from 1955 Oct.	% Change from 1955 10-Mos.
Total U. S., ENR reported	$1,878.3	$18,386.0	+23	+17
Private	1,141.5	11,475.7	+15	+17
Public	736.8	6,910.3	+39	+18
State and Municipal	607.5	5,460.2	+52	+23
Federal	129.3	1,450.1	− 1	+ 2
ENR Volume Index, 1913 = 100	729	688	+16	+13

NEW CONSTRUCTION CAPITAL

Millions of dollars				
Total U. S.	$747.1	$12,643.5	+ 1	+16
State and Municipal Bond Sales	442.7	3,882.9	+ 2	+ 8
Corporate Security Sales	296.1	4,080.3	−0.4	+40
Federal Loans, Aid (nonfederal work)	8.3	1,204.0	+24	+24
Federal Appropriations (federal work)	0	3,476.2*	...	+0.3

* Includes funds for outside U. S.

MATERIALS SHIPMENTS

	Unit	1956 July (Jl) Aug. (A) Sept. (S)	Cum. (No. of Mos.)	% Change fr. Year Ago Mo.	% Change fr. Year Ago Cum.
Portland Cement, Bur Mines	thous bbls	31,333(Jl)	173,627(7)	+ 8	+ 6
Conc Paving Awards, PCA	thous sq yd	5,267(S)	65,969(9)	− 9	− 8
Fabricated Structural Steel	thous tons	241(S)	2,344(9)	−17	+ 7
Bookings, AISC	thous tons	246(S)	2,979(9)	−28	+11
Reinforcing Bars, Net, AISI	thous tons	238(Jl&A)	1,545(8)	−37	+11
Lumber, NLMA	mil fbm	3,262(A)	25,134(8)	−11	− 7
Orders	mil fbm	3,120(A)	24,760(8)	−16	−10
Production	mil fbm	3,537(A)	25,424(8)	− 3	− 3
Douglas Fir Plywood, DFPA, 3/8"-basis					
Production (average per week)	mil sq ft	103.0(S)	98.8(9)	+ 8	+ 6
Orders (average per week)	mil sq ft	108.5(S)	94.3(9)	+15	+ 1
Clay Products, Bur Census					
Brick, Unglazed, Common, Face	mil bri	618.6(Jl)	3,968.6(7)	− 1	+0.4
Vitrified Clay Sewer Pipe	thous tons	178.0(Jl)	1,062.0(7)	+ 4	+ 1
Structural Tile, Unglazed	thous tons	56.8(Jl)	396.2(7)	−19	−18
Asphalt Products, Bur Census					
Asphalt Roofing	thous sales sqs	6,171(A)	41,147(8)	−10	− 5
Asphalt Siding	thous sales sqs	117(A)	771(8)	− 4	− 5
Aluminum, Wrought, Net, Bur Census					
Sheet and Plate (non-heat treatable)	mil lbs	66.0(A)	747.2(8)	−34	+10
Wire and Cable	mil lbs	26.6(A)	208.0(8)	+10	+24
Extruded Shapes (soft alloys)	mil lbs	54.4(A)	436.2(8)	− 2	+ 7

EMPLOYMENT AND FAILURES

Contract Const Employment, BLS	thous	3,301(S)	2,991(9)**	+ 7	+ 9
Contractor Failures, Dun & Bradstreet					
Number		146(S)	1,298(9)	+28	+30
Liabilities	thous	$7,840(S)	$70,410(9)	+84	+23

** Average per month



Booth & Flinn, Pittsburgh, have the contract for the Packer Avenue Bridge, which will span the Delaware to connect the New Jersey Turnpike with the State Expressway.

GULF PRODUCTS and FINE SERVICE

keep equipment rolling on New Jersey Turnpike extension project

Like leading contractors everywhere, Booth & Flinn, Pittsburgh, want to keep costs down and equipment performance up. That's why they have standardized on Gulf Products. They use Good Gulf, the smooth-performing gasoline. They use Gulflube Motor Oil H.D. to protect both gasoline and diesel engines. And to make sure that their diesels will start promptly and be knock-free even at slow speeds, Booth & Flinn specify Gulf Dieselect Fuel. From long experience they know they can depend on Gulf not only for quality products but also for technical assistance if needed and prompt delivery *always.*

Gulf's sales engineers and 1500 strategically located warehouses want to serve *you,* too. How they can do it is told in the new booklet "Gulf and *Your* Business." Send for it now.

GULF

E.N.R.

Gulf Oil Corporation • Gulf Refining Company
1822 Gulf Building, Pittsburgh 30, Penna.

Without any obligation on my part, send me a copy of the new booklet "Gulf and Your Business."

NAME_____

TITLE_____

COMPANY_____

CITY_____ ZONE____ STATE_____

THE FINEST PETROLEUM PRODUCTS FOR ALL YOUR NEEDS

NEW...Snow-and-Ice-Free Interchanges on Indiana's East-West Toll Road





with Steel Pipe Snow Melting Systems

"Really *new* and *important*" . . . "an *innovation* in highway construction" . . . are some of the things said about the Steel Pipe Snow Melting Systems installed at gates and interchanges on the recently opened Indiana East-West Toll Road. That they will add immeasurably to bad weather safety factors and increase the traffic handling capacities at these vital points of entry and exit is the opinion of highway engineers.

With the forthcoming expansion of the nation's highway systems, roadbuilders in the snow belt should give serious consideration to the advantages of automatic snow and ice melting in highway construction . . . for interchanges, bridge floors, elevated ramp sections, over-passes, and other exposed road sections where conventional control methods may be both costly and inadequate.

For such installations, *Steel Pipe is first choice*, as in this Indiana road, the elevated approach to the New York Port of Authority bus terminal, the Staten Island Ferry Ramp, and many others. Yes, steel pipe is the most widely used pipe in the world, for snow melting, radiant heating, plumbing, fire sprinkler systems, power, steam, air transmission and electrical raceways.

Write today for free booklet "Steel Pipe Snow and Ice Removal Systems."

Steel Pipe is First Choice

Committee on
STEEL PIPE RESEARCH
AMERICAN IRON AND STEEL INSTITUTE
150 East Forty-Second Street, New York 17, N.Y.



Photogrammetry's growth sets stage for . . .

Doubling a Market in a Decade

Photogrammetry, well-established as an engineering tool, is also becoming well-established from the business standpoint.

There are now approximately 50 private firms professionally engaged in aerial photography and photogrammetry for mapping purposes, according to a recent study made by C. L. Miller, assistant professor of surveying at Massachusetts Institute of Technology.

In addition, there are at least another 50 firms that are in the aerial photography field to a limited extent that were not included in Professor Miller's study.

Of the 50 professional firms, 18 may be classified as aerial photographic firms and 32 as photogrammetric firms. The latter are equipped with stereoplotting instruments.

Since some of the photogrammetric companies subcontract their aerial photography to other firms, Professor Miller found that there are actually 33 companies in the field of aerial photography.

Airborne surveying did some high flying in the decade from 1945 to 1955. During this period, the number of firms engaged in photogrammetry jumped from four to 32. Although the exact figures are not yet available, Professor Miller feels there has been a significant increase in the number of photogrammetric firms this year.

And, Miller expects the number of firms in the photogrammetric field to double in the next 10 years because of the impact of the new federal-aid highway program.

Are most photogrammetric firms active just in this one branch of the field? Miller says no. In fact, in many cases, the photogrammetric activities are subordinate to the firm's other work.

For example, 15 of the firms covered in the Miller study actually are consulting and civil engineering firms with a photogrammetric division.

Although the bulk of the photogrammetric work probably will continue to be performed by the large aerial survey firms that specialize in this field, Miller says there is a significant trend toward the addition of photogrammetric facilities by smaller civil engineering and surveying firms operating on a local and regional basis.

• **Where are they?**—Of the 50 photogrammetric firms covered in the study, 14 are in the North; five are in the South; three in the Midwest; four in the Southwest; and the biggest bulk, 24, are in the West.

Of these 50, five are considered local firms, 26 operate throughout one region, and 19 are national in scope. Of the 19 national firms, 10 also work overseas.

From a business standpoint, it's interesting to note the equipment these firms own, the men they employ, and the fees they collect.

These 50 photogrammetric firms covered in the Miller study own and operate a total of 158 airplanes and 261 aerial cameras. And, while some civil engineers feel that few precision stereoplotters are available in the United States, Professor Miller found that these 50 firms owned 277 such precision instruments.

• **Whom do they employ?**—The study showed that these firms employed 264 engineers, 325 stereoplotters, 742 draftsmen, and 180 field survey crews. But, the field isn't getting much help from engineering schools in providing some of this trained personnel, according to Professor Miller.

He says in the report:

"The failure of the engineering schools to provide education facilities in this important field is quite evident from the fact that, although the firms classify 186 of their men as photogrammetric engineers, only 40 had completed a college course in photogrammetry."

• **How much business?**—In comparison with other segments of the construction business, the total business volume in the photogrammetric field probably seems small.

The study reported an estimated total business volume for the 50 firms of about $23 million a year. About $8.3 million in fees came in for aerial photography services; $14.7 million was for photogrammetric services.

One third of the total fees came from the federal government. State and local governments accounted for another 27%, and the remaining 40% came from private industry.

Road Materials Plentiful In Nearly All Key Cities

Roadbuilding materials, including cement and aggregates, are in good supply in most of the key cities surveyed by ENGINEERING NEWS-RECORD this month. These are the principal exceptions:

• **Cement**—A temporary shortage of cement in Detroit is clearing up. The shortage was due to a strike, now settled, at the Huron Cement plant at Alpena, Mich. The local shortage was alleviated by rail shipments from Ohio, Illinois, Pennsylvania and New York. The Toronto shortage continues.

• **Crushed slag**—Baltimore reports a slight shortage of crushed slag but delivery times have been cut to only a few days. With the steel mills operating full blast again, the once-short city of Birmingham now reports a plentiful supply.

• **Gravel**—Only one major city, Cleveland, currently reports a shortage of gravel.

• **Ready-mixed concrete**—Chicago is the only major area short.

(B&F continued on page 108)

Construction Outlays Set October Record

Despite a slight seasonal decline, outlays for construction put in place set a new October high.

The $4.1-billion total for the month edged the previous high, set last year.

Most major construction categories, except housing, continued strong.

New October records were posted for private industrial plants, highways, public utilities, office buildings, sewer and water facilities, churches and public schools.

Meanwhile, the value of housing put in place skidded to a level more than 14% below the October record of a year ago.

On a seasonally adjusted basis, new construction activity for the first 10 months of this year has been at an annual rate of more than $44 billion, compared with $43 billion in 1955. Actual expenditures for the first 10 months ran 3% ahead of the corresponding 1955 figure.

Public construction outlays in the January-through-October period totaled $11.3 billion, 7% above the comparable 1955 period, principally because of sizable increases in highways, and sewer and water facilities.

Federal work dropped moderately during this period, the Bureau of Labor Statistics reported. Advances on military facilities and conservation and development projects failed to offset the sharp drop in work for the Atomic Energy Commission.

The federal government spent almost 20% more this year than last for grants-in-aid on state and local construction. However, the proportion of federal funds is not considered high. During the first 10 months, federal grants accounted for about 4% of the total outlays for state and local school construction; 7% for hospitals and 15% for highways.

Brightest aspect of the residential market for construction put in place is the additions and alteration field. At the end of the first 10 months, this type of work totals $1.2 billion, 9% ahead of the comparable 1955 period. October alone was 16% higher than the same month last year.



$10-Million Co-op Apartment Planned

A 22-story, $10-million luxury co-operative apartment building is slated to get under way soon in Beverly Hills, Calif. Designed by the architectural firm of Pereira & Luckman, the 102-unit project will include a three-level garage, a swimming pool; cabanas, private gardens and a health club as well as a private club on the roof. Paul Trousdale and Clinton Murchson, Jr., are the developers.

Loan Funds Scarce

Shortage of cheap money causes civilian housing delays at Redstone Arsenal

The "crash" housing program at Huntsville, Ala., to provide living quarters for essential civilians in the stepped-up missile and rocket research program at Redstone Arsenal is being threatened with delays. The reason is a paucity of Federal Housing Administration and Veterans Administration mortgage money.

Huntsville, like most other cities throughout the nation, has been hit by the tight money market. Scores of families pouring into the city each week find rental housing scarce and mortgage money for VA and FHA housing loans almost non-existent.

The recently-enacted Title 809 of the National Housing Act, designed to encourage construction of houses for essential civilian employees of the Defense Department, was supposed to ease the housing situation.

But, local real estate men say that the law presumed loan money would be available. The new title does not provide a source of mortgage money. It merely enables the Defense Department to give an additional guarantee on FHA-insured mortgages and provides for lower downpayments and longer amortization periods.

Conventional mortgage loans are available in Huntsville, but many of the incoming families apparently cannot meet the downpayment requirements for conventional loans. And, in the Huntsville area, conventional interest rates range from 5½% up, as against 4½% for VA and FHA mortgages.

Old City: New Look

Long-term, $250-million face-lifting mapped for section in Philadelphia

Philadelphia's historic central city area may be modernized at a cost of $250 million in a long-range program that will be spearheaded by private capital.

A non-profit organization, the Old

(Continued on page 110)



WHOLE FLOOR OF BUILDING has been pulled loose by this crane of John J. Duane Company. To do it, workmen drove two holes in the floor (walls and roof had already been removed) and inserted cable down through holes and up to crane. Crane then tugged until floor ripped loose. This is typical of workout the firm's cranes receive, but using Cities Service lubricants they give flawless performance.

Razes buildings, raises efficiency using Cities Service lubricants

9000 hours on a crane and no trouble . . . truck goes 65,000 miles, uses no make-up oil!

JOHN J. DUANE COMPANY, Quincy, Massachusetts, operates 10 cranes, 14 gasolene and diesel trucks, three forklifts, and a bulldozer . . . all powered and lubricated by Cities Service. The results are notable. Says John Duane: "Using Cities Service C-300 Motor Oil, one of our diesel cranes has gone 9000 hours with absolutely no trouble, and the oil has doubled the period between overhaul for our truck fleet. Furthermore, one gasolene truck has gone 65,000 miles without adding a drop of C-300 between crankcase drains. We're also mighty pleased with Trojan P-2 Grease. Used on the tracks of our cranes, Trojan P-2 keeps them operating flawlessly under the most severe conditions."

Like Mr. Duane, you'll lengthen overhaul periods, cut operating costs when you start using Cities Service products. Get all the facts from a Cities Service Lubrication Engineer. Or write: Cities Service Oil Company, Sixty Wall Tower, New York 5, N. Y.

CITIES SERVICE

QUALITY PETROLEUM PRODUCTS

Construction Market: Baltimore

"Tight money is keeping the lid on the pot," a Baltimore banker said last week. He was talking about his city's construction market, now bubbling like a kettle of boiling water.

A survey of Baltimore's contractors, lending institutions, public agencies and equipment suppliers shows that homebuilders are about the only people getting burned in the current situation.

"Do we have enough work?" a spokesman for union-shop contractors asked rhetorically. "Why, we have so much going on that out-of-state contractors are moving in fast."

This optimism is prevalent despite the general belief that construction loan money, both the short-term and long-term variety, promises to be short for months to come.

James W. Rouse, Baltimore mortgage banker, says the money shortage is delaying and cutting back on commercial projects, is curtailing homebuilding and, to a lesser extent, is crimping industrial expansion.

But, he warns that incessant talk about tight money should not becloud the fact that the Baltimore construction industry is in remarkably healthy shape and promises to stay that way into the foreseeable future.

In public works alone, where tight money is less of a factor, contractors will have a big volume of work coming up in the next few months.

The $12-million Maryland State Office Center is out for bids that will be opened Nov. 29. This state building is in a redevelopment tract just northwest of downtown Baltimore.

This is just part of the city's growing urban renewal program now in the process of being consolidated under one administrative agency. This agency will push a 20-year, $900-million program.

Bids are due Nov. 20 on the Lexington Terrace public housing project, which will consist of five high-rise and 13 two-story buildings containing a total of 677 dwelling units.

These are immediate projects. Following them in a month or two will be some $4 million worth of shopping centers and apartments in two other redevelopment areas.

The federal government is planning a $17-million office center that will be integrated with the urban renewal program.

But urban renewal is not the only star in the Baltimore galaxy. Around the first of the year, the Maryland Roads Commission will let contracts for $20 million in highway improvements financed under the new federal highway bill. Much of this work will be done in the Baltimore area, chiefly in connection with the circumferential route around the city. This route will tie in with the Patapsco River crossing which will be opened in December 1957.

The city government is moving along on the new $70-million Jones Falls Expressway, which will be Baltimore's main north-south artery when completed. Planners also are going ahead on a proposed east-west expressway, eight lanes wide, across the city's midriff.

Commercial building continues strong, particularly in the shopping center field. Industrial building is setting new records, according to the Baltimore Association of Commerce. This type of work is boosted by Bethlehem's $200-million expansion at Sparrows Point and the new $20,-million Glidden Co. project.

This leaves housing, where small builders are being hurt. Tight money has driven away many potential buyers. But many builders are counting on this potential for the future.

Some think the slowdown in housing might be good. It will force homebuilders to turn out better homes to lure those buyers who can afford bigger downpayments and higher interest rates.

One of the city's largest suppliers of earthmoving equipment cautions against pessimism. His firm sells equipment to grading subcontractors, many of whom work for the small homebuilders.

"A year ago," he says, "the contractors were paying these subs regularly and my customers were paying off their debts. Now, many subcontractors are asking for a little more time to pay off their notes. They say the contractors they work for are having hard times.

"But, remember one thing: Even though these boys might be slowing down on their payments, they still are buying equipment. In fact, our sales this year are ahead of 1955. So long as these men feel they can go ahead, things look pretty good for the future of this market."

Philadelphia Development Corporation, has requested a charter and hopes to get under way officially in the immediate future.

Endowed with quasi-official standing, this privately-financed organization will co-operate with the Philadelphia Planning Commission and the Philadelphia Redevelopment Authority.

The $250 million renewal program will be concentrated in the midtown and fringe areas between Spring Garden, Lombard, and Broad Streets and the Delaware River.

Through private financing, and federal grants (channeled through the redevelopment authority), the new corporation will serve as primary redeveloper. Specific projects will be carried out by private investors and builders in accordance with a comprehensive plan drawn by the City Planning Commission.

A group of architects already is at work, under a contract with the City Planning Commission, to develop the general outline of the program, according to Albert M. Greenfield, commission chairman.

Plans call for complete demolition of the old Dock Street wholesale market district, a renovation of Franklin Square and restoration of about 400 historic homes in the redevelopment area.

Private homes, apartment buildings and perhaps hotels will be built on these razed sites.

The program also calls for improvements along Market Street, site of most of Philadelphia's big department stores and of many of its commercial retail establishments, from Front Street, near the Delaware River waterfront, up to 10th Street.

The corporation, although organized as a private body, will have some of the powers of the present Development Authority and thus will be able to aid private institutions, such as Jefferson Hospital, in plans for new residences for nurses and internes.

Planning Chairman Albert Greenfield calls the program, "the most ambitious city redevelopment program in the country." He emphasized that private builders will be encouraged to undertake as many projects as possible, with the new non-profit corporation handling only work private enterprise cannot do.

William L. Day, chairman of the board of the First Pennsylvania Banking and Trust Co., is president of the Old Philadelphia Development Corporation. Other officers named so far are Paul Ingersoll, assistant secretary of the Penn Mutual Life Insurance Co., secretary; and James J. Mickley, vice president of the Girard Trust Corn Exchange Bank, treasurer.

(*B & F continued on page 112*)



Temporary shelters erected with Fiberglas Reinforced Weatherproof Papers are easy to cover, provide long, dry service.

ALL-ROUND WEATHER BARRIER

Fiberglas Reinforced Weatherproof Papers shut out wind and rain at lowest cost

You can build temporary shelters in a hurry and at low cost with Fiberglas* Reinforced Weatherproof Papers. Nailed tightly over a rough frame, these papers seal out moisture, allow safe storage of valuable materials and equipment.

The protection is long-lasting, too, because these papers are built around rot-proof, moisture-proof Fiberglas filaments with enduring strength. Yet Fiberglas Reinforced Weatherproof Papers have great flexibility and lightness; they're easy to handle in large sections. They are also available in pre-cut tarpaulin form, with edge grommets.

Fiberglas Reinforced Weatherproof Papers give you more protection in a variety of construction applications, yet they cost no more than ordinary reinforced papers. Send for free sample kit showing a variety of construction applications. Owens-Corning Fiberglas Corporation, Dept. 145-I-13, 598 Madison Ave., New York 22, N. Y.

Cover lumber and equipment with Fiberglas Reinforced Weatherproof Papers. It's the economical way to protect wood and equipment from the elements.



Concrete curing with Fiberglas Reinforced Weatherproof Papers is economical, yields cleaner, harder surfaces. *T.M. Reg. O-CF Corp.

flow information at your finger tip!

- MAIN-LINE METERS
- FLOW and CHEMICAL FEED CONTROLS
- INSTRUMENTS

METROVALVES

AUTOMATIC FLOW REGULATION—TOTAL FLOW REGISTRATION

Select the required flow by simply setting a pointer to the desired dial position. Total flow is easily read on the counter type clock. Ideal for either remote telemeter applications or on the spot control.

Contact any Sparling Office for complete information.

SPARLING METER COMPANY

Incorporated

225 NORTH TEMPLE CITY BLVD., EL MONTE, CALIF.

ATLANTA 3.....66 Luckie Street NW	945 North Main St.....LOS ANGELES
BOSTON 8.....6 Beacon Street	650 First Avenue West.....ROSELLE, N. J.
CHICAGO 8.....1500 South Western Ave.	85 Industrial St.....SAN FRANCISCO 24
CINCINNATI 2.....626 Broadway	904-A Elliott Ave. West.....SEATTLE 99
DALLAS 1.....505 No. Ervay St.	207 Queens Quay West.....TORONTO, CAN.
KANSAS CITY 6, MO.....6 E. Eleventh St.	248 London Rd.....ROMFORD, ENGLAND

Sound Powered Telephones



for bridges, tunnels and highways

Activated solely by the sound energy of the voice, these phones operate under any conditions without batteries or any other type of current. Effective over a distance of many miles. Cost of upkeep is negligible. In outdoor and indoor models. Systems may be standard or altered to suit any of your requirements. Write for illustrated catalog.

HOSE-McCANN TELEPHONE CO., INC.

761 THIRD AVENUE, BROOKLYN 32, N. Y.

. . . Business and Finance

Business Briefs . . .

• **Aluminum catches up**—The aluminum industry's "prodigious" efforts to increase production are paying off, according to I. W. Wilson, president of Aluminum Company of America. Now the industry should concentrate on developing new markets. Two viewed by Wilson: residential building uses and highway applications.

• **Million homes in '57**—On the eve of the U. S. Savings and Loan League's annual convention, League President Walter H. Dreier reported, "the worst of the decline in new homebuilding is behind us," predicted 1 million housing starts in 1957.

• **Industrious homebuilder**—Development of a 320-acre industrial site has been projected at Phoenix, Ariz., by John F. Long, who for the past eight years has concentrated on residential construction in central Arizona. Long has built more than 3,000 homes. Now, he plans the industrial area near his subdivisions, will try for electronics and other light manufacturing firms.

• **State office buildings**—The Florida State Cabinet authorized issuance of separate bond issues totaling $9 million for construction of branch state office buildings in Jacksonville, Tampa, Miami and Winter Park. Agencies using the buildings will pay rentals that will be used to retire the bonds.

• **Paying proposition**—F. H. McGraw & Co., engineers and constructors, had good news for stockholders. Directors declared a 15 cents a share dividend payable Dec. 18, and announced the common stock has been placed on a regular quarterly dividend basis. Construction completed during the first nine months totaled $16 million, and produced a net profit, after taxes, of $303,247—equal to 71 cents per common share. This compared with a net loss of $217,000 during the same period in 1955.

• **Equipment merger**—Chain Belt Co., of Milwaukee, Wis., acquired General Road Machines, Inc., of Niles and Newton Falls, Ohio. General Road, which will operate as a subsidiary of Chain Belt, is a manufacturer of road-building equipment.

• **Cleveland Trencher sales up**—Cleveland Trencher Co.'s sales for the first nine months were up slightly over the same period in 1955 ($5.5 million vs. $5.3 million), but net profit was down slightly.

• **Higher interest—later**—Interest rates will move higher, but there won't be any significant rise for the balance of this year, according to Fred F. Florence, president of the American Bankers Assn.

BUILDING?



- INDUSTRIAL PLANTS
- POWER HOUSES
- PUBLIC UTILITIES
- PUBLIC BUILDINGS
- COMMERCIAL BUILDINGS
- PETRO-CHEMICAL UNITS
- BRIDGES
- HIGHWAYS
- SHIPS
- HOUSING

WHATEVER YOU ARE BUILDING

. . . there may be a grating application that can save you time and money and improve the project. As founders of the grating industry, with over half a century of experience, the Irving Grating Company is well qualified to recommend designs to help you solve specific problems.

We are manufacturers of Riveted, Pressure-locked and Welded Gratings in Steel, Aluminum and other metals.

TYPICAL USES OF IRVING GRATING:

Open Steel Flooring
Safety Treads
Floor Armoring
Walkways
Trench Covers
Balconies
Loading Platforms
Vestibule Mats
Sun Deflectors
Bridge Decking
Draingrates
Contour Retainer Grid for Refractory Shells

SOME OF THE ADVANTAGES:

Self-Cleaning
Self-Draining
Permits passage of light and air
Lightweight
Strong
Will last indefinitely
Fireproof
Resists Corrosion
Simple to Install
Minimum maintenance
Custom built

"A FITTING GRATING FOR EVERY PURPOSE"

IRVICO®
ESTABLISHED 1902

IRVING SUBWAY GRATING CO., Inc.
ORIGINATORS OF THE GRATING INDUSTRY

Offices and Plants at:
5063 27th St., LONG ISLAND CITY 1, N. Y.
1863 10th St., OAKLAND 20, CALIFORNIA

Representatives in Canada, Mexico and South Africa

Teamsters' Aim: Two Million Members

Construction and industrial workers loom large in union's plans to add new members and to strengthen its position

Teamster plans to push the union's membership past the two million members mark will reach into the heavy and highway construction field and perhaps will compound the confusion already surrounding the conflicting jurisdictional claims of craft and industrial unions.

Membership drives for construction workers have been mapped for Virginia, West Virginia and western Pennsylvania, Philadelphia, Washington, D. C., and Baltimore. The drives will be financed jointly by the locals and the international. Principal target is an independent union—A. D. Lewis' United Construction Workers, which is part of John L. Lewis' United Mine Workers. And along with the drive, greater emphasis is promised on mutual assistance pacts, on area-wide bargaining and on uniform agreements.

These were some of the topics on the agenda at the annual convention of the Eastern Conference of Teamsters, recently held in Washington, D. C.

According to the conference's Building and Construction Division, the teamster's four-way pact with laborers, carpenters and operating engineers (ENR July 26, p. 105) is functioning well, but UCW still remains a threat in several sections of the conference area. The pact, signed two years ago and aimed at UCW and nonunion contractors, contains a pledge by the four unions not to engage in jurisdictional work stoppages at projects on which their members are employed—a pledge based on the premise that unity among the trades and cooperation with union contractors will lead to greater employment opportunities for members of the participating unions. Out of that alliance came the National Joint Heavy and Highway Construction Committee, which, incidentally, was instrumental in getting the prevailing wage provisions put in the Federal-Aid Highway Act of 1956.

As a collateral effort to strengthen their own position, particularly in the field of collective bargaining, teamster locals within the conference are being urged by the Building and Construction Division to negotiate jointly on an area-wide basis and to make greater use of standard provisions in building and construction labor contracts. The activities of the division are now under the direction of Anthony Capone, former business representative of Building Material and Construction Local 398, Rochester, N. Y.

But perhaps the most dramatic proposal presented at the convention was formation of an industrial division within the teamsters union. The proposal came from Union Vice President and Central Conference Chairman James Hoffa, who expressed the view that no ready solution to the jurisdictional conflict between craft and industrial unions will come out of the AFL-CIO. Apparently on the theory that a bird in the hand is worth two in the bush, Hoffa suggested that the teamsters meanwhile proceed intensively to organize workers in industrial plants on an industry basis without regard to craft restrictions.

Now one of the largest and most vigorous of the AFL-CIO affiliates, Beck's teamsters claim a membership in excess of 1.4 million and report a net worth of $36.5 million. About 425,000 of the union's members are in the Eastern Conference area.

How Labor Interprets the Election Results

Organized labor last week attributed President Eisenhower's victory at the polls to the President's personal popularity, not to the Republican program or to the failure of labor's political activity.

It claimed some credit for the heavy vote splitting that occurred and for the election of many gubernatorial and Congressional candidates considered friendly to labor. And to some observers labor scored a victory in the rejection by popular vote of a right-to-work law in Washington and in the defeat of Warren Shaw, a proponent of right-to-work legislation who ran for Governor of Kansas on the Republican ticket.

Last week's Presidential election was the first in which labor had behind it the weight of the new AFL-CIO combination.

While Stevenson and Kefauver had received the endorsement of the federation and of a host of individual unions, President Eisenhower, however, had won the personal support of some of the leaders of the AFL-CIO building trades. Among them were Richard Gray, head of the Building and Construction Trades Department; Maurice A. Hutcheson, president of the carpenters union, and Dave Beck, president of the teamsters union.

Labor endorsement of other candidates, on both state and national levels, had followed recommendations made on a nonpartisan basis by the AFL-CIO's Committee on Political Education, which had analyzed and widely publicized the voting records of political candidates.

AFL-CIO President George Meany, who has said that labor's biggest challenge lies in the legislative halls, attributed the fact that Congress remained Democratic despite President Eisenhower's record margin "in large part to the educational work of labor" and said the election results gave labor "renewed hope" for a predominantly liberal and progressive Congress in 1958.

Atom Plant Opposed

Building trades ask veto of union request to halt construction in Michigan

Union efforts to halt construction of the $45-million atomic energy facility being built at Lagoona Beach, Monroe, Mich., have been opposed by the Monroe County Building Trades Council. The attempt to suspend construction was spearheaded by Walter Reuther, head of the auto workers union, and reportedly stemmed from a fear that the installation would endanger the health and safety of those living in the Detroit and Toledo areas.

The plant, on which United Engineers and Constructors of Philadelphia is one of the contractors, is being built for Power Reactor Development Co. under a conditional construction permit issued by the Atomic Energy Commission. Three unions—auto workers, electrical workers (IUE) and paperworkers—have asked the AEC to order suspension of construction pending investigation of the safety hazards involved.

(Continued from page 114)

Claiming that the installation is an "unproved and exceptionally hazardous type of reactor," the three unions have taken the position that the AEC did not find that the plant could be constructed and operated "without undue risk to the health and safety of the public" and that the construction permit should not have been issued in the absence of such a finding. The Building Trades Council in Monroe already has urged that construction not be suspended and looks to the Toledo Building Trades Council for similar support.

An AEC hearing on the safety issue, originally scheduled for this week, was postponed to Dec. 10. Meanwhile, the AEC has declined to order a halt to construction. Ten acres of land already have been filled preparatory to construction, and pouring of concrete for the footings was expected to begin last week.

Contractors' Problem

AGC official claims labor keeps building costs high

The president of the Carolinas Branch of the Associated General Contractors of America has blamed increased construction costs on the "backward thinking" of labor union officials.

Speaking at the annual meeting of the North Carolina Ready Mixed Concrete Association at Pinehurst, N. C., Frank P. Morris said the main problem of builders today is to convince organized labor that it should bring its thinking up to date. "Labor," he said, "is one of the biggest costs in any construction project, yet labor officials are constantly trying to increase labor costs without increasing efficiency."

To support his charge that labor attempts "to halt cost-cutting progress," Morris cited use of pumps and air compressors as examples.

Organized labor insists, he said, that "contractors hire one man to push the button in the morning to start the pump and compressors and again at night to shut them off. Not only do labor officials want that man to sit there idle all day, they want him to make more money for doing it."

"These backward thinking officials," Morris asserted, "are merely pied pipers who are leading the honest working man to his destruction."

(Labor continued on page 117)

MODERN STRUCTURES

NEED MODERN METHODS

Lamson HIGH-STRENGTH STRUCTURAL STEEL BOLTS



400 tons of structural steel completely assembled with approximately 82,000 High-Strength Bolts—Diameters ⅞" thru 1".

And here's the result . . . a modern, safe structure, assembled quickly, less expensively and QUIETLY.

● Lamson High-Strength Bolts are the answer to today's need for construction speed and economy as well as tomorrow's requirements for strength and safety.

Once properly installed, High-Strength Bolts CANNOT be matched for strength or low inspection and maintenance costs.

Compared to old-fashioned riveting, High-Strength Bolts are stronger statically, higher in fatigue resistance and have far greater shear strength.

In the photographs to the left you see the new airport terminal at Cleveland's Hopkins airport . . . completely assembled with Lamson High-Strength Structural Steel Bolts . . . another safe, modern structure . . . designed for tomorrow—today.

Write for the COMPLETE High-Strength Bolt story. This 8-page brochure is yours for the asking without obligation.

Lamson + Sessions

The LAMSON & SESSIONS Co.
1971 West 85th Street • Cleveland 2, Ohio
Plants at Cleveland and Kent, Ohio
Birmingham • Chicago

Large Bolts ● Cotters
Square and Hex Nuts ● Weather-tight Bolts ● Bent Bolts
Phillips and Clutch Head Screws ● Lock Nuts ● Cap Screws



TODAY...

Roebling tensioning materials have created many markets for prestressed concrete . . .
warehouses • garages • stadiums
bridges • piers • hangars
and other construction

TODAY...

Another new market for fabricators

Prestressed* Concrete Line Poles

Shown here is one of the latest in the constantly growing list of applications for prestressed concrete. These power line poles were designed and fabricated for the Florida Power Corporation by Finfrock Industries, Inc., Orlando, Florida.

Each pole is prestressed with ⅜" diameter Roebling uncoated 7-wire stress-relieved strands, pretensioned and bonded to the concrete.

Easily transported and installed, the 65 ft (above ground) poles have a life expectancy of 50 to 100 years. Once erected, they are maintenance-free. The high cost of replacement every few years is eliminated.

Why don't you investigate the possibilities of this new market to increase your profits? Roebling engineers, who pioneered in the development of prestressed concrete in America, will supply general information or help with specific problems. Write to Construction Materials Division, John A. Roebling's Sons Corporation, Trenton 2, N. J.

ROEBLING

A Subsidiary of The Colorado Fuel and Iron Corporation

**Not to be confused with ordinary reinforced concrete*

AFL-CIO Housing Proposals

Labor asks federal government to redirect homebuilding activity with emphasis on low and middle-income needs

In its current issue of "Labor's Economic Review," the AFL-CIO presents its recommendations for a "far-reaching, comprehensive housing program" embracing construction of at least 2 million new dwelling units a year to help close up the gap between "housing construction and housing requirements."

If the housing program, directed primarily at the needs of low and middle-income families, were adopted by Congress, payment of prevailing wages would be required on all forms of federally-assisted construction. Here's what the program calls for:

- A Department of Housing and Urban Affairs headed by a cabinet officer.
- A National Mortgage Corporation authorized to make long-term, low-interest loans for cooperative, sales and non-profit rental housing for moderate-income families.
- A large-scale, low-rent public housing program for low-income families.
- A federal program of low-cost loans to unions, churches, cooperatives and other non-profit organizations for sponsoring special housing programs for the elderly.
- An expanded urban redevelopment program with emphasis on slum clearance and city rebuilding.
- Payment of prevailing wages on all federally-assisted housing construction.
- Protection of home owners against foreclosure when unemployed because of lay-offs, accidents and illness.

According to the AFL-CIO, our housing programs never have been successful because they haven't generated enough construction to keep pace with the nation's needs and because they've failed to produce housing at costs most people can afford.

• **Vicious circle**—Only one new home, the federation asserts, is being built for every two that are needed.

A rapid rise in population (43% in the last 20 years) and deterioration of older housing units have combined, the AFL-CIO says, to give the nation a homebuilding rate, on a per capita basis, that's 20% less than it was in 1925. And the demand for housing will grow more urgent as demolition spreads in the vanguard of highway and public works construction.

In the face of these trends, the AFL-CIO charges, tight credit conditions and higher home prices are forcing more and more people out of the housing market. Even the VA and FHA programs, the federation argues, call for higher carrying charges than most moderate-income families can afford. Here, the complaints are that interest rates are unreasonably high in view of the fact that the lender's risk virtually has been eliminated, extra costs are numerous, and the loans are too quickly amortized.

At the same time, continued the AFL-CIO, older citizens, whose housing needs have been overlooked in the past, are growing more numerous and forming a larger proportion of our population.

• **Solution**—To the AFL-CIO the solution is a fundamental redirection of homebuilding activity spearheaded by the federal government along the lines proposed, with new units made available to all races and creeds without discrimination.

Parts of the program were contained in bills presented to the 84th Congress by Sen. Herbert Lehman (D., N.Y.) and Rep. Albert Rains (D., Ala.) but neither bill was passed.

The AFL-CIO expresses the hope that the next session of Congress will consider solution to the housing problem one of its major objectives.

Labor Unity Shows Gains As State Mergers Proceed

Tentative agreement has been reached on merger of AFL and CIO forces in North Carolina. In the meantime, state mergers have been completed in New Mexico and Alabama.

The North Carolina agreement was reached by a negotiating committee that has attempted to overcome merger objections voiced by the AFL last August when the building trades blocked the merger (ENR Aug. 30, p. 77). According to W. Millard Barbee, head of the State Federation of Labor, the new proposal is "generally satisfactory" to both groups. Next step will be ratification of the proposal.

The New Mexico and Alabama mergers, embracing 375,000 AFL-CIO members, brought to 18 the number of state mergers that have been completed. Right-to-work laws were singled out for attack at both merger conventions.

State mergers, which must be completed by Dec. 5, 1957, are an integral part of the unity movement that founded the AFL-CIO last year. Unity "is working" despite its problems AFL-CIO George Meany told delegates to the recent convention of ironworkers, and "good faith" will continue to be the key to its success, he said.

Lathers and Employers End Dispute Over Labor Supply

A Chicago dispute over employment practices of union lathers was settled last week after seriously hampering construction activities for three weeks. Under a new agreement, running until June 1, 1958, between the Chicago Plasterers Association and Local 74, a Joint Manpower Commission will be established to study ways and means of keeping the labor supply adequate.

During the dispute (ENR, Oct. 25, p. 114), the lathers were charged with restrictive employment practices with respect to admission of new members, enrollment of apprentices and the use of outside union lathers and of nonunion workers.

Terms of the settlement will permit outside journeymen to be employed in Chicago, with the approval of the Joint Manpower Commission, when needed. Problems of apprentice training and overtime work will be dealt with by two committees slated to be formed under the settlement agreement.

Organizing Agreement Is Reached in Hawaii

A jurisdictional dispute over organization of the trowel trades in Hawaii has been ironed out as AFL-CIO efforts continue to extend the trade union movement in the islands.

Under the agreement, plasterers and cement masons will be organized by Arthur A. Rutledge, head of the teamsters and hotel workers local in Hawaii. Bricklayers and tile setters, whom Rutledge had previously claimed (ENR Oct. 4, p. 148), will remain within the jurisdiction of the bricklayers union, which has assigned the task of organizing to Will C. Jarrett.

Other membership drives previously launched include one by the painters and one by the carpenters.

Carpenters Union Supports Lumber Industry Promotion

The carpenters union, which is celebrating its 75th anniversary this year, has promised close cooperation with the lumber industry in promoting use of

(Continued on page 119)

Both ends working against the highway muddle

Allison TORQMATIC DRIVES make it possible for this big Euclid TS-18 *Twin Power* scraper to "eat up hills" and build a highway.

Note well that "Twin Power." For this scraper has two engines and two TORQMATIC Converter-Transmission teams. Only with the advantages of the converter-transmission team can two power units at opposite ends work simultaneously pushing and pulling.

To contractors these twin TORQMATIC teams mean faster work, more payload hauled and less equipment needed to do a bigger job. That's real Allison economy.



You can get Allison TORQMATIC DRIVES in a wide range of equipment built by almost 100 manufacturers. For full details on Allison TORQMATIC DRIVES for the equipment you buy or build, write Allison Division of General Motors, Box 894E, Indianapolis 6, Indiana.

Allison

TORQMATIC DRIVES

wood products. Promise came from union President Murice A. Hutcheson when he spoke last week to the Building Codes and Trade Promotion Committee of the National Lumber Manufacturers Association in Washington, D. C.

One of the main objectives of the joint promotional activity, Hutcheson indicated, should be amendment of building codes to promote wider use of wood products. "We need," he said, "up-to-date codes which recognize all the improvements in both product and technique in wood construction in the past 50 years." Hutcheson also included reduced insurance rates on wood construction and maintenance of "realistic" controls over the import of plywood and other wood products among the goals of the cooperative effort.

In offering the lumber industry the support of the carpenters union, Hutcheson said the primary concern of his union is to improve the lot of its members and to promote the national welfare. The union, he asserted, is not interested in "Utopia" ideas or in "isms."

Labor Briefs . . .

• **Prevailing wages**—The right of the City of Philadelphia to require contractors to pay employees "no less than the wages prevailing in the community" has been upheld by a state court. Payment of prevailing wages, said the court, is a "reasonable" requirement.

• **Industrial contracts**—An arbitrator handling a grievance of the United Rubber Workers union has ruled that an industrial concern must live up to a provision in its labor contract restricting use of outside contractors. If the contract requires the work be done by plant employees where "possible and practical," the clause means what it says.

• **Higher benefits**—In drafting the California State Federation of Labor's 1957 state legislative program, the federation's Executive Council will ask for higher workmen's compensation benefits, and larger unemployment insurance and unemployment disability insurance benefits.

• **Safety**—As a result of the collapse of the partially constructed Consumers Power Co. building near Jackson, Mich., on Oct. 3, the Michigan Conference of Building Trades Councils may call a legislative conference in Lansing to try to push an adequate safety code bill through the state legislature.

OFFICIAL PROPOSALS

APPEAR HERE EACH THURSDAY. PROPOSAL ADVERTISEMENTS ACCEPTED UP TO 10:30 A.M. FRIDAY FOR THE ISSUE DATED THE FOLLOWING THURSDAY.

Bids: November 27, 1956.

Municipal Airport Lighting System Ogdensburg, New York

NOTICE TO BIDDERS

Sealed proposals for furnishing all labor, equipment and material and appurtenances for electrical improvements to the Municipal Airport of the City of Ogdensburg, New York, until 2:00 P. M. Eastern Standard Time, on Tuesday, November 27, 1956 at the Common Council Room in the City Hall, Ogdensburg, New York at which time they will be publicly opened and read aloud.

Bids will be taken on the following contract:

Installation of runway and taxiway lights, wind cone, beacon and beacon platform, hangar lights and electric service.

The information for Bidders, Proposal, General Provisions, Special Provisions, Specifications and Plans, Form of Contract and Performance Bond may be examined at the Office of the City Clerk, Ogdensburg, New York, and copies thereof may be obtained from William T. Field, Consulting Engineer, 320 Flower Building, Watertown, New York upon the payment of Thirty ($30.00) Dollars for each set.

The City of Ogdensburg reserves the right to waive any information in or to reject any or all bids or to accept any bid that it deems, to be in the best interest of the city.

The acceptance of any bid is subject to the approval of the Civil Aeronautics Administration.

Each bidder must deposit with his bid, security in the amount of not less than five per centum (5%) of the bid in the form and subject to the conditions provided for in the Information for Bidders.

The successful bidder will be required to furnish a contract performance bond in such form and having as surety thereon such surety company or companies as are approved by the City Corporation Counsel, in the amount of not less than 50% of the total amount of the accepted bid.

Attention of bidders is particularly called to the requirements as to conditions of employment to be observed and minimum wage rates to be paid under this contract.

Dated: October 25, 1956

CITY OF OGDENSBURG, NEW YORK
LEE W. KEYES, MAYOR

WILLIAM T. FIELD
Consulting Engineer
Watertown, N. Y.

Bids: November 30, 1956.

Construction of 16-inch and 30-inch Diameter Water Supply Mains Arlington County, Virginia

ADVERTISEMENT FOR BIDS

Sealed proposals for furnishing all materials and equipment and doing all work required for the construction of 16-inch and 30-inch diameter water supply main, as described below, will be received by the Purchasing Agent in Room 213, in the Court House Building at Arlington County, Virginia, until 11:00 A.M., Eastern Standard Time, on Nov. 30, 1956, and there publicly opened and read immediately thereafter:

STAGE II
CONTRACT 4
CONSTRUCTION OF 16-INCH AND 30-INCH DIAMETER WATER SUPPLY MAIN AND APPURTENANCES

1. Location: The work is located in Arlington County, Virginia, on public streets from 30th Street N. to Yorktown Boulevard, along Yorktown Boulevard to N. Vermont Street and N. Vernon Street, along N. Vernon Street to 24th Street N. and on 24th Street N. to Wakefield Street (36 inch Water Supply Main) and on 24th Street N. from Wakefield Street to Old Dominion Drive and 26th Street. (16 inch Water Supply Main).

2. Type of Work: The principal items of work include the following:

Approximately 4400 lin. ft. of 30-inch steel or reinforced concrete water pipe together with manholes, cone valves, miscellaneous, blow-off, air release or inlet valves, connections to existing water mains, etc.

Approximately 1700 lin. feet of 16-inch cast iron water pipe, together with miscellaneous gate valves, manholes, hydrants, connections to existing mains, etc.

Approximately 1000 lin. ft. of 24-inch concrete storm sewers and appurtenances.

3. Copies of Plans and Specifications, Information for Bidders, Bid Forms and other bidding and contract documents may be examined at the office of the Chief Engineer of the Water Division, County Court House, Arlington, Va.; at Dodge Reports, 900 F. Street, N. W., Washington, D. C. and at the office of ALEXANDER POTTER ASSOCIATES, CONSULTING ENGINEERS, 50 CHURCH ST., NEW YORK (7), N. Y.

4. Copies of Plans, Specifications and Bidding Documents may be obtained from the Purchasing Agent in Room 213, Court House Building at Arlington, Virginia upon deposit of THIRTY ($30.00) DOLLARS PER SET.

Full refund will be made to actual bidders for return of One (1) Set, in good condition, within two weeks after closing date for receipt of bids; refund for return of all other sets, in good condition, WITHIN THE SAME PERIOD, will be Fifty (50%) percent of the deposit. No refund will be made for return of documents in poor condition or later than the two week period stipulated.

All bids must be on the form contained in the Contract and Specifications.

Contractors, whether resident or non-resident in Virginia will be required to show evidence of a certificate of registration as required by Chapter 7 of Title 54 of the Code of Virginia before their bids will be considered, if the bid is $20,000 or more. All bids must be accompanied by a certified check or acceptable bidder's bond in an amount of not less than Five Per Cent (5%) of the amount of the bid, made payable to the Treasurer of Arlington County, as bid security.

The successful bidder will be required to furnish a Performance Bond conditioned upon the faithful performance of the Contract and upon payment of all persons supplying labor and furnishing materials on the construction of the work.

No bidder may withdraw his bids within Thirty (30) days after actual date of opening thereof.

The County Board of Arlington County, Virginia, reserves the right to reject any or all bids and to waive any informality in the bids.

ARLINGTON COUNTY, VIRGINIA
By: H. G. Bonney
Purchasing Agent

Bids: December 4, 1956.

Contract Exd-120.065

ADVERTISEMENT
THE PORT OF NEW YORK AUTHORITY
PORT AUTHORITY BUILDING
FOURTEENTH FLOOR ALTERATIONS
NORTH SIDE

Sealed proposals for altering a portion of the north side of the fourteenth floor of the Port Authority Building, 111 Eighth Avenue, New York 11, N. Y., will be received at the office of the Chief Engineer of The Port of New York Authority, Room 1160, 111 Eighth Avenue, New York 11, N. Y., until 2:30 P. M. on Tuesday, December 4, 1956, at which time said proposals will be opened and read in Room 1168.

Contract documents may be seen at the office of the Engineer of Design of the Authority, Room 1115, and copies will be furnished upon request. No deposit will be required but the documents shall be returned in good condition not later than forty days after the opening of proposals.

THE PORT OF NEW YORK AUTHORITY
Donald V. Lowe, Chairman

New York, November 15, 1956

OFFICIAL PROPOSALS

Bids: November 30, 1956.

Construction of a Steel Water Tank

ADVERTISEMENT FOR BIDS
FURNISHING AND ERECTING
ELEVATED STEEL WATER STORAGE
TANK, 500,000 GALLON CAPACITY
ARLINGTON COUNTY, VIRGINIA

Sealed proposals for furnishing all material and equipment and doing all work required for the furnishing and erecting of an elevated steel water storage tank, as described below, will be received by the Purchasing Agent in Room 213, in the Court House Building at Arlington County, Virginia, until 11:00 A. M., Eastern Standard Time, on NOVEMBER 30, 1956, and there publicly opened and read immediately thereafter:
CONTRACT 5.
FURNISHING AND ERECTING ELEVATED STEEL WATER STORAGE TANK 500,000 GALLON CAPACITY

1. Location: The work is located in Arlington County, Virginia, on County Owner property at N. Wakefield Street and 24th Street N.

2. Type of Work: The principal items of work include the following:-

Furnishing and erecting a 500,000 Gallon Elevated Steel Water Storage Tank complete with all accessories, including Obstruction Lighting and Cathodic Protection.

3. Copies of Plans and Specifications, Information for Bidders, Bid Form and other Bidding and Contract Documents may be examined at the Office of the Chief Engineer of the Water Division, County Court House, Arlington, Va.; at Dodge Reports, 900 F. Street, N. W., Washington, D. C. and at the Office of ALEXANDER POTTER ASSOCIATES, CONSULTING ENGINEERS, 50 CHURCH STREET, NEW YORK 7, N. Y.

4. Copies of Plans, Specifications and Bidding Documents may be obtained from the Purchasing Agent in Room 213, Court House Building at Arlington, Virginia, upon Deposit of TEN ($10.00) DOLLARS PER SET.

Full refund will be made to actual bidders for return of One (1) Set, in good condition, within two weeks after closing date for receipt of bids; refund for return of all other Sets, in good condition, WITHIN THE SAME PERIOD, will be Fifty (50%) Percent of the Deposit. No refund will be made for return of documents in poor condition or later than the two-week period stipulated.

All bids must be on the form contained in the Contract and Specifications.

Contractors, whether resident or non-resident in Virginia will be required to show evidence of a certificate of registration as required by Chapter 7 of Title 54 of the Code of Virginia before their bids will be considered, if the bid is $20,000 or more.

All bids must be accompanied by a Certified Check or Acceptable Bidder's Bond in an amount of not less than Five Per Cent (5%) of the amount of the Bid, made payable to the Treasurer of Arlington County, as bid security.

The successful bidder will be required to furnish a Performance Bond conditioned upon the faithful performance of the Contract and upon payment of all persons supplying labor and furnishing materials on the construction of the work.

No bidder may withdraw his bid within Thirty (30) Days after actual date of opening thereof.

The County Board of Arlington County, Virginia, reserves the right to reject any or all bids and to waive any informality in the bids.

ARLINGTON COUNTY, VIRGINIA
By: H. G. Bonney
Purchasing Agent

Bids: December 20, 1956

Port of Corinto, Nicaragua, C.A.

FURNISHING AND DELIVERING
MATERIALS HANDLING EQUIPMENT
AUTORIDAD PORTUARIA DE CORINTO
MANAGUA NICARAGUA

Sealed bids in triplicate for Furnishing and Delivering Materials Handling Equipment, Port of Corinto, will be received by the Autoridad Portuaria de Corinto, hereinafter referred to as the Autoridad Edificio Cerna, Calle Central Este, entre 4 y 5 Ave., 4° Piso, Managua, Nicaragua, C.A. until 10:00 A.M. Nicaragua time on December 20, 1956, at which time the bids will be opened.

The work consists of designing, manufacturing, testing, furnishing and delivering gasoline or diesel powered materials handling equipment, including the following general types:

14 Fork Lift Trucks, Cushion Tired—5,000 lb. capacity
2 Fork Lift Trucks, Pneumatic Tired—16,000 lb. capacity
1 Straddle Truck, Pneumatic Tired—18,000 lb. capacity
5 Tractors Warehouse, Cushion Tired—500 lb. drawbar pull
3 Tractors Warehouse, Cushion Tired—2,600 lb. drawbar pull
1 Crane, mobile-single engine pneumatic tired with 30 foot boom and minimum capacity of 14,000 lbs. on 10' radius
1 Crane, mobile-single engine pneumatic tired with 50 foot boom and minimum capacity of 25,000 lbs. on 15 foot radius
80 Trailers, warehouse-pneumatic tired, 72" x 108", 5000 pound capacity.
6 Trailers, heavy duty cushion-tired 84" x 204", 50,000 pound capacity.
1500 Pallets, hardwood, 4 way non reversible 48" x 72".

Spare parts sufficient for two years operation of the equipment listed above.

Contract Documents including specifications may be obtained from the Autoridad upon payment of Seventy Córdobas per complete set of Contract Documents, which money will not be refunded.

The Contract Documents may be examined at the above offices of the Autoridad, the offices of the Consulate General of Nicaragua in New York City, and at the New York offices of Tippetts-Abbett-McCarthy-Stratton, Engineers.

The Authority reserves the right to reject any or all bids and waive any informality or irregularity in bids received.

Each bid shall be accompanied by a bank guarantee from a bank approved by the Autoridad or bid bond satisfactory to the Autoridad, in the amount of five (5) percent of the total bid price, in Córdobas. The total bid price in Córdobas shall be deemed to be the total dollar equivalent amount of the bid multiplied by 7.0.

AUTORIDAD PORTUARIA DE CORINTO
Managua, Nicaragua

Bids: December 11, 1956.

Contract LT-160.024

ADVERTISEMENT
THE PORT OF NEW YORK AUTHORITY
LINCOLN TUNNEL
THIRD TUBE
TUNNEL PAVING

Sealed proposals for the tunnel paving for the Third Tube of the Lincoln Tunnel will be received at the office of the Chief Engineer of The Port of New York Authority, Room 1100, 111 Eighth Avenue, New York 11, New York, until 2:30 P.M. on Tuesday, December 11, 1956, at which time said proposals will be opened and read in Room 1108.

Contract documents may be seen at the office of the Engineer of Design of the Authority, Room 1115. Documents will be furnished upon deposit of $30.00 per set for not more than three sets to any one company (each set including one copy of the contract drawings). Additional sets will be furnished upon payment of $30.00 per set, which payment is not returnable. Deposits and payments shall be delivered to the Treasury Department, Room 1001, where a receipt in duplicate will be issued. A copy of the receipt shall be delivered to Room 1115, where the documents will be furnished.

Those who have submitted a bid on the contract will receive a refund of the deposit for each set of documents, not exceeding three, returned within forty days after the opening of proposals. Those who have not submitted a bid will receive a refund of one-half of the deposit for each set of documents, not exceeding three, returned within forty days after the opening of proposals.

THE PORT OF NEW YORK AUTHORITY
Donald V. Lowe, Chairman

New York, November 15, 1956

Bids: December 11, 1956.

Contract PN-340.005

ADVERTISEMENT
THE PORT OF NEW YORK AUTHORITY
PORT NEWARK
BUILDINGS NOS. 290, 291, 292 and WHARF
RECONSTRUCTION OF WHARF

Sealed proposals for the reconstruction of a wharf on the North side of the City Channel at Port Newark will be received at the office of the Chief Engineer of The Port of New York Authority, Room 1100, 111 Eighth Avenue, New York 11, N. Y., until 2:30 P. M. on Tuesday, December 11, 1956, at which time said proposals will be opened and read in Room 1108.

Contract documents may be seen at the office of the Engineer of Design of the Authority, Room 1115. Documents will be furnished upon deposit of $30.00 per set for not more than three sets to any one company (each set including one copy of the contract drawings). Additional sets will be furnished upon payment of $30.00 per set, which payment is not returnable. Deposits and payments shall be delivered to the Treasury Department, Room 1001, where a receipt in duplicate will be issued. A copy of the receipt shall be delivered to Room 1115, where the documents will be furnished.

Those who have submitted a bid on the contract will receive a refund of the deposit for each set of documents, not exceeding three, returned within forty days after the opening of proposals. Those who have not submitted a bid will receive a refund of one-half of the deposit for each set of documents, not exceeding three, returned within forty days after the opening of proposals.

THE PORT OF NEW YORK AUTHORITY
Donald V. Lowe, Chairman

New York, November 15, 1956

Bids: January 23, 1957

Government of Iraq

MINISTRY OF ECONOMICS
TOBACCO MONOPOLY
ADMINISTRATION
CIGARETTE FACTORY AT
SULAYMANIYAH

1. The TOBACCO MONOPOLY ADMINISTRATION of the Government of IRAQ invites tenders for furnishing and delivering, all machinery and equipment required for an airconditioned Cigarette Factory at Sulaymaniyah, Iraq, and supervising the installation and the satisfactory operation of the Factory for a period of 12 calendar months, in accordance with specifications, conditions and addenda.

2. Copies of the documents for tender may be inspected at the following adresses on or after 25 October 1956.

a) The offices of the Director General, Tobacco Monopoly Administration, Baghdad, Iraq.

b) Iraq Embassies in Washington, London, and Paris; and Iraq Legations in Bonn, Brussels, and Rome.

3. Copies of the documents for tender may be obtained on or after 25 Oct. 1956 upon payment of I.D. 25/-(Twenty-five Iraqi Dinars) from the offices of the Director General, Tobacco Monopoly Administration, Baghdad, Iraq.

4. Tenders must be written in English, and shall be enclosed in a sealed package and endorsed clearly on the outside with the words "Tender for Cigarette Factory at Sulaymaniyah". They shall be addressed to the Director General, Tobacco Monopoly Administration, Baghdad, Iraq, and delivered on or before 12 noon, Baghdad time, 23 January 1957. If sent by post, the tenders shall be registered, but the tenderers must assure themselves of delivery to the Director General in due time.

5. The tender must be accompanied by a bid bond of ID.10,000 (Ten thousand Iraqi Dinars). The bid bond shall be in the form of a certified cheque from a bank in Iraq, or the bidder may submit with his bid, a letter of guarantee obtained from a bank established in Iraq. The bid bond is returnable subject to the conditions mentioned in the specifications.

6. Tenders not submitted in the time specified or not accompanied by the bid bond will not be considered.

7. The Director General reserves the right to amend the documents. Any amendments will be in the form of addenda and shall be distributed to the prospective tenderers, in time to be included in the tender.

8. The Tobacco Monopoly Administration does not bind itself to accept the lowest or any tender.

BAQIR H. HASANI,
DIRECTOR GENERAL AND CHAIRMAN
OF BOARD OF DIRECTORS
TOBACCO MONOPOLY
ADMINISTRATION

Read the Official Proposal Columns of ENGINEERING NEWS-RECORD This Week and Every Week

OFFICIAL PROPOSALS

Bids: January 22, 1957

Port of Corinto, Nicaragua, C.A.

PORT CONSTRUCTION—PHASE I
PORT CONSTRUCTION—PHASE II
AUTORIDAD PORTUARIA DE CORINTO
MANAGUA, NICARAGUA

Sealed bids in triplicate for Port Construction, Phase I and II, at the Port of Corinto, will be received by the Autoridad Portuaria de Corinto, hereinafter referred to as the Autoridad, Edificio Cerna, Calle Central Este, entre 4 y 5 Ave., 4° Piso, Managua, Nicaragua, C.A. until 10:00 A.M. Nicaragua time on January 22, 1957, at which time the bids will be opened.

Phase I of the work consists of the construction of a new wharf approximately 370 meters long, including dredging and disposal of dredged materials; furnishing and placing rock and sand fill, riprap and filter blankets; furnishing and placing concrete piles and concrete deck structure; furnishing and installing timber fendering; and furnishing and installing deck fittings and track work. Listed below are the estimated qualities for the principle items of work.

85,000 C.M.	Dredging
46,000 Metric Tons	Rock Fill
139,000 C.M.	Sand Fill
26,000 L.M.	Reinforced Concrete Pile
5,000 C.M.	Concrete

Phase II of the work consists generally of the following construction: 1) Two transit sheds approximately 50 meters wide and 117 meters long; a pump house approximately 3.8 meters wide and 5.0 meters long; and a truck service shelter approximately 9.1 meters wide by 17.4 meters long; all steel frame structures with protected metal roofing and siding. 2) A guard house approximately 3.7 meters square, of concrete unit masonry construction with concrete roof and built up roofing. 3) Masonry and steel partitions; overhead steel and hollow metal doors; commercial projected steel windows; plumbing; sprinkler systems; electrical work, painting and miscellaneous incidental items of work for the building structures. 4) Fire pump and fuel tank; fuel dispensing units and storage tanks and interconnecting piping. 5) Water tower for fire protection system and standby pump. 6) Utilities, including fire and domestic water mains, sanitary waste and storm drainage, and electrical distribution. 7) Reinforced concrete paving of port area and railroad track work.

Separate Contract Documents including plans and specifications have been prepared for Phase I and for Phase II and may be obtained from the Autoridad upon payment of One Hundred and Seventy Five Cordobas for each separate complete set of Contract Documents, which money will not be refunded.

The Contract Documents may be examined at the above offices of the Autoridad, the offices of the Consulate General of Nicaragua in New York City and at the New York offices of Tippetts-Abbett-McCarthy-Stratton Engineers.

Bids may be submitted for Phase I, Phase II, or both combined. A separate proposal form is provided for the combined bid.

The Autoridad reserves the right to reject any or all bids and waive any informality or irregularity in bids received.

Each bid shall be accompanied by a bank guarantee from a bank approved by the Autoridad, or bid bond satisfactory to the Autoridad, in the amount of two (2) percent of the total price in Cordobas.

The total bid price in Córdobas will be deemed to be the total dollar equivalent amount of the bid multiplied by 7.0.
AUTORIDAD PORTUARIA DE CORINTO
Mangua, Nicaragua

CONTRACTORS
WATCH
THIS SECTION

for New Projects

Publish your announcements thru the "Proposal Section" of Engineering News-Record and get their bids.

COMMONWEALTH OF MASSACHUSETTS: Department of Public Works. NOTICE TO CONTRACTORS: Sealed proposals for State Highway and Bridge Work on Auto Route 6 in the Towns of MARION and WAREHAM will be received at Room 427, 100 Nashua Street, Boston, Mass., until 2.00 P.M. of TUESDAY, November 20, 1956 and at that place and time publicly opened and read. Proposal guaranty: $20,000.00. Charge for plans and proposal forms: $15.00, amount returnable only to bidders. Complete information at said office; plans on display at District office in MIDDLEBOROUGH. Minimum wage and dump-truck rates have been established. Right reserved to waive any informality in or reject any or all proposals. An award will not be made to a Contractor who is not equipped to undertake and complete the work.
By: CARL A. SHERIDAN, Commissioner of Public Works. November 3, 1956

U. S. Government

DEPARTMENT OF THE INTERIOR, Bureau of Reclamation. Sealed bids (Specifications No. DC-4803) will be received at Weaverville, California, until December 20, 1956, for furnishing labor and materials for Clear Creek Tunnel, Trinity River Division, Central Valley Project, California, Location near Redding, California. Principal items are 150,000 cu. yds. open cut excavation; 675,000 cu. yds. excavation in tunnel; 8,000,000 lbs. furnishing and installing steel tunnel supports; 175,000 cu. yds. concrete; 14,500,000 lbs. furnishing and placing reinforcement bars; and other work. Completion time 1,720 days. For particulars, address Bureau of Reclamation, Weaverville, California, or Building 53, Denver Federal Center, Denver 2, Colorado. W. A. Dexheimer, Commissioner.

DEPARTMENT OF THE INTERIOR, Bureau of Reclamation. Sealed bids (Specifications No. DC-4798) will be received at Building 234, Camp White, Oregon, until December 18, 1956, for furnishing labor and materials for Earthwork, Concrete Canal Lining, and Structures for Howard Prairie Delivery Canal, Station 0+00 to Station 541+00, and Soda Creek Feeder Canal, TalentDivision, Rogue River Basin Project, Oregon.- Location east of Ashland, Oregon. Principal items are 194,000 cu. yds. excavation; 23,400 cu. yds. compacting embankments; 8,560 cu. yds. concrete in structures and lining; 2,766 lin. ft. 48-inch precast-concrete pipe siphon; and other work. Completion time 690 days. For particulars, address Bureau of Reclamation, P. O. Box 386, Camp White, Oregon; or Building 53, Denver Federal Center, Denver 2, Colorado. W. A. Dexheimer, Commissioner.

DEPARTMENT OF THE INTERIOR, Bureau of Reclamation. Sealed bids (Specifications No. DC-4804) will be received at Weaverville, California, until December 19, 1956, for furnishing labor and materials for Earthwork, Structures and Surfacing, County Road Improvement, Trinity River Bridge to Trinity Dam, Central Valley Project, California. Location near Lewiston, California. Principal items are 750,000 cu. yds. excavation for roadway; 4,670 lin. ft. furnishing and laying 8-inch to 60-inch corrugated metal pipe; 35,000 tons crushed rock base; 260 tons liquid asphalt; and other work. Completion time 300 days. For particulars, address Bureau of Reclamation, Project Construction Engineer, Weaverville, California; or Building 53, Denver Federal Center, Denver 2, Colorado. W. A. Dexheimer, Commissioner.

DEPARTMENT OF THE INTERIOR, Bureau of Reclamation. Sealed bids (Invitation No. DS-4805) will be received at Denver, Colorado, until December 20, 1956, for furnishing materials for a steel warehouse, 100-feet wide by 320-feet long, for Glen Canyon Dam and Power Plant, Colorado River Storage Project, Arizona-Utah. Delivery is desired within 150 days. For particulars, address Bureau of Reclamation, Building 53, Denver Federal Center, Denver 2, Colorado. W. A. Dexheimer, Commissioner.

OFFICIAL PROPOSALS

Bids: November 27, 1956

Contract 439

MARGARETVILLE-ARKVILLE SEWERS

SEALED BIDS will be received by the Board of Water Supply, at its offices, thirteenth floor, 120 Wall Street, New York City, until 11:00 A.M. Eastern Standard Time on Tuesday, November 27, 1956 for Contract 439, for the construction of about six miles of sewers, including a railroad crossing, four stream crossings, manholes and other appurtenances, and a total of about six miles of house connections. The sewers will be from six to 15 inches in diameter and the house connections six inches in diameter. The location of the proposed work is in the Village of Margaretville and in the hamlet of Arkville, in the Town of Middletown, Delaware county, New York.

At the above place and time the bids will be publicly opened and read. Pamphlets containing information for bidders, forms of bid and contract, specifications, contract drawings, requirements as to surety, etc., can be obtained in Room 1312 (Acting Secretary's Office), at the above address, upon application in person or by mail, by depositing the sum of five dollars ($5.00) in cash or its equivalent for each pamphlet. Within 30 days following the award of contract or rejection of bids, the full amount of such deposit will be refunded for each pamphlet submitted as a bid and a refund of four dollars ($4.00) will be made for each other pamphlet returned in acceptable condition. Arrangements will be made whereby prospective bidders desiring blueprints of the contract drawings for their own use may secure same; the cost thereof to be paid by them. For further particulars, apply at the office of the Chief Engineer at the above address.

IRVING V. A. HUIE, President, EDWARD C. MAGUIRE, HERBERT M. ROSENBERG, Commissioners, Board of Water Supply; BETTY COHEN, Acting Secretary.

Bids: November 29, 1956

New York State Road Work

NOTICE TO CONTRACTORS

STATE DEPARTMENT OF PUBLIC WORKS, ALBANY, N. Y.—Pursuant to the provisions of the Barge Canal Improvement Law and Highway Law, sealed proposals will be received, until 10:30 A.M., EST on November 29, 1956 by Henry A. Cohen, Director, Bureau of Contracts and Accounts, 14th Floor, the Governor Alfred E. Smith State Office Building, Albany, N. Y. for:

Contract U. S. 93 for
Lowering Sills, Extending Gates
and Miscellaneous Work at Lock 23
Erie Canal, Onondaga County and
Lock 1, Oswego Canal, Oswego Co., N. Y.

Maps, plans and specifications may be examined and obtained at the following offices:

(a) Bureau of Contracts and Accounts, 14th Floor The Gov Alfred E. Smith State Office Bldg., Albany, New York.
(b) Department of Public Works, 270 Broadway, New York City, N. Y.
(c) In addition to the above mentioned offices, plans, maps and specifications for Contract U. S. 93 may be examined and obtained at the office of Mr. William Robinson, District Engineer, 301 E. Water Street, Syracuse 1, New York.

The deposit for Plans and Proposal Forms for U. S. 93 is $10.00. A refund in full will be made to bidders for return of one set in good condition within 30 days of award or rejection of bids; refund for all other sets in good condition, similar period, will be 50% of deposit.

The Engineer's Estimate of Cost for Contract U. S. 93 is confidential and will be made known at the time of receiving bids. Proposals for U. S. 93 must be submitted in a separate sealed envelope with the name and number of the contract plainly endorsed on the outside of the envelope. Each proposal must be accompanied by draft or certified check, payable to the order of the "State of New York, Commissioner of Taxation and Finance" for the sum of five percentum, (5%) of the bid. The retention and disposal of the bidding check, the execution of the contract and bonds shall conform to the provisions of the Barge Canal Improvement Law and to the Highway Law as set forth in "Instructions to Bidders" in the contract specifications.

JOHN W. JOHNSON
Supt. of Public Works

OFFICIAL PROPOSALS

Bids: December 14, 1956.

Construction of Sewers

The City of Springfield, Missouri, will receive sealed proposals for the construction of interceptor and main trunk sanitary sewers until 10:00 A.M., Central Standard Time on the 14th day of December, 1956, at the office of the City Clerk, Springfield, Missouri.

All proposals received will be publicly opened and read aloud in the City Council Chambers at Springfield, Missouri, beginning at 10:00 A.M., Central Standard Time, on the 14th day of December, 1956.

The contract documents, including plans and specifications, are on file and available for inspection at the office of the Director of Public Works of the City of Springfield, at Springfield, Missouri, and at the office of Consoer, Townsend & Associates, Consulting Engineers, 360 East Grand Avenue, Chicago 11, Illinois.

Copies of documents, including plans and specifications, required for review and/or bidding purposes may be obtained only from the Director of Public Works by depositing $15.00 for proposed Division C; $15.00 for proposed Division D; and $15.00 for proposed Division E at the office of the Director of Public Works for each set of documents so obtained.

Since the documents, excluding the plans, comprise forms, information and specifications applicable to all three (3) Divisions, a single document will be issued upon request for plans for one or more than one Division. The full amount of the deposit for one set of documents and one-half of the deposit for any additional sets of documents will be refunded to each bidder who submits a formal proposal to the City of Springfield and who also returns the plans (and specifications on additional sets) in good condition to the Director of Public Works within ten (10) days after his bid security has been returned to him.

Equipment manufacturers, subcontractors, and others who do not submit formal proposals to the City of Springfield will be refunded one-half (½) the amount of the deposit for all sets of complete documents, including plans and specifications, returned in good condition to the Director of Public Works within ten (10) days after the opening of bids. No refund will be made for documents received by the Director of Public Works after this ten (10) day period.

A certified check or bank draft, drawn on a solvent bank, payable without condition to the City of Springfield, Missouri, in an amount not less than five per cent (5%) of the bid shall be submitted with each proposal, as a guarantee that if the proposal is accepted by the City of Springfield, a contract will be entered into and the performance of the contract properly secured. No bid shall be withdrawn after the opening of proposals without the consent of the City of Springfield, Missouri, for a period of thirty (30) days after the scheduled time of closing bids. The bid securities of all bidders, except that submitted with the lowest acceptable proposal on each Division, will be returned within ten (10) days after the time of opening bids. The bid security of the lowest acceptable proposal on each Division may be held by the City of Springfield until a construction contract has been executed and a satisfactory performance bond and a satisfactory labor and material bond in the sum of the full amount of his contract has been delivered to the City. The City of Springfield reserves the right to reject any or all proposals and to waive any informalities or irregularities in the bids received, or to accept any proposal on any one Division or a combination of Divisions which is deemed most favorable to the City, at the time and under conditions stipulated in the Instructions to Bidders.

The improvements on which proposals are solicited are divided into three (3) Divisions and bidders may submit a proposal on any one or a combination of Divisions as listed in the Proposal Form. The proposal on each Division shall include furnishing of all labor, materials, equipment, tools, supplies, etc., for a complete operating installation. The work to be constructed under each Division is briefly described as follows:

DIVISION C—SOUTH CREEK MAIN INTERCEPTOR SEWER:

This Division includes the furnishing and installation of approximately 12,000 lineal feet of reinforced concrete pipe sewer in 48" and 60" sizes, in open cut and tunnel, complete with appurtenances.

DIVISION D—TUNNEL, WILSON CREEK TO SOUTH CREEK:

This Division includes the furnishing and installation of approximately 8,200 lineal feet of 60" internal diameter concrete lined rock tunnel, 60" internal diameter reinforced concrete pipe in open cut, and 60" internal diameter reinforced concrete pipe encased in concrete, together with all appurtenances.

DIVISION E—TRUNK SEWER EXTENSIONS—NORTH AND EAST SIDES:

This Division includes the furnishing and installation of extensions to existing trunk sewers on the north and east sides of the City of Springfield. These extensions include approximately 12,600 lineal feet of reinforced concrete, cast iron and vitrified tile pipe sewers in sizes ranging from 10" to 21", together with all appurtenances.

Plans and specifications for this project were prepared by Consoer, Townsend & Associates, Consulting Engineers, 360 East Grand Avenue, Chicago 11, Illinois.

Dated at Springfield, Missouri, this 31st day of October, 1956.

CITY OF SPRINGFIELD, MISSOURI
W. B. Avery, City Manager

Bids: December 5, 1956

State of Rhode Island and Providence Plantations

DEPARTMENT OF ADMINISTRATION
DIVISION OF PURCHASES
NOTICE TO BRIDGE CONTRACTORS

Sealed Proposals enclosed in an envelope endorsed "Proposal for R.I. Contract No. 5655, F. A. Project No. I-01(10), Superstructure of Pawtucket Bridge No. 550" and addressed to the State Purchasing Agent, R.I. Department of Administration, Division of Purchases, 125 State House, Providence 2, Rhode Island, will be received until 11:30 A.M. on the 5th. day of December 1956, at which time they will be opened and read in public.

R.I. Contract No. 5655, R.I. Federal Aid Project No. I-01(10), Pawtucket Bridge No. 550, Construction Contract Two, County of Providence, Pawtucket, Rhode Island. Construction consists of the superstructure for a 5-span deck girder bridge having a length of 760 feet and a width of 109 feet, and includes concrete deck slab, structural railing and highway pavement. Approximate principal quantities: 2700 tons of structural steel, 2385 cubic yards of concrete in reinforced concrete deck, and 8,000 square yards of asphalt pavement.

Bids for the above work must be made on blanks furnished by the Department of Public Works, Division of Roads and Bridges. Plans, Specifications and Special Provisions may be examined at Room 125, State House, or Room 232, State Office Building, Providence, Rhode Island, on and after November 7, 1956 every week day except Saturdays and holidays, between the hours of 8:30 A.M. and 4:30 P.M. Blanks for submitting Proposals may be obtained through the office of the State Purchasing Agent at Room 125 State House. A deposit of $100.00 shall be made for each set of contract documents which will be refunded if Plans and Specifications are returned in good condition within two weeks after the opening of bids.

A certified check or bid bond payable to the State of Rhode Island, or cash, in the amount of $50,000 must be furnished by each bidder. This Proposal Guaranty will be returned after the contract has been executed, unless forfeited in accordance with the stipulations in the proposal.

A performance bond of one hundred (100) percent of the contract price with a satisfactory surety company will be required of the sucessful bidder. The Division of Purchases reserves the right to reject any or all bids.

FEDERAL REQUIRED CONTRACT PROVISIONS: The attention of prospective bidders is called to the fact that this project is to be bid upon and the contract executed under the rules and regulations for carrying out the provisions of the Federal-Aid Highway Act of 1956 and the Special Provisions, dated October 12, 1954, as amended and supplemented, as required by the Department of Commerce, Bureau of Public Roads.

WAGES OF LABOR ON INTERSTATE HIGHWAY PROJECTS: The prevailing rate of wages for laborers and mechanics employed by contractors or subcontractors on the initial construction of highway projects on the Interstate System, authorized under the Federal Highway Act of 1956 shall be paid wages at rates not less than those prevailing on the same type of work on similar construction in the immediate locality as determined by the U. S. Secretary of Labor in accordance with the act of August 30, 1935, known as the Davis-Bacon Act, under the decision No. R-3891, which is part of the contract.

Chapter 290 of the R.I. General Laws, 1938, as amended, requires that "the contractor to whom the contract is awarded and any subcontractor under him shall have ordinarily paid the prevailing rate of per diem wages and shall continue to pay the prevailing rate of per diem wages and the general prevailing rate for regular, holiday, overtime and other working conditions to all workmen needed to execute the contract or work". The schedule of prevailing wage rates of per diem wages in the locality in which the work is to be performed for each craft, mechanic, teamster, laborer or type of workman needed to execute the contract work is on file in the office of the Rhode Island Department of Labor.

On State, City and Town projects Chapter 291 of the General Laws of 1938 as amended, requires that Rhode Island citizens be given preference in employment.

SUBLETTING OR ASSIGNING THE CONTRACT: The attention of bidders is directed to the Standard Specifications and Special Provisions covering subletting or assigning the contract.

DEPARTMENT OF ADMINISTRATION
DIVISION OF PURCHASES
By Joseph L. Byron
State Purchasing Agent

Bids: December 19, 1956

Construction of Branch Interceptor Louisville and Jefferson County Metropolitan Sewer District Louisville, Kentucky

Sealed proposals for the construction of the 38th Street Branch Interceptor Sewer in Louisville, Kentucky, will be received on Wednesday, December 19, 1956, until 12:00 o'clock Noon, Central Standard Time at the District Office, 412 West Market Street, Louisville, Kentucky, at which time they will be publicly opened and read.

Alternate proposals for bids for constructing the Interceptor Sewer will be taken in open cut and tunnel. All excavation will be in sandy and clayey materials and in paved City Streets. The approximate lengths of the Interceptor are:

1. 36" R. C. C. Pipe 4670 lin. ft.
2. 30" R. C. C. Pipe 3080 lin. ft.
3. 24" Pressure Main 1324 lin. ft.
4. Junction chambers, manholes and appurtenances

Plans, Specifications and information for Bidders will be available November 15, 1956, at the Office of the District which will be furnished to prospective bidders upon the deposit of $20.00 for complete set of Plans and Specifications. Said deposit will be refunded upon return of the Plans and Specifications in good condition within 30 days after the date of opening the bids.

Bidder's proposal must be accompanied by a Certified Check in an amount not less than ten per cent (10%) of the lump sum price or prices, plus the evaluated prices of the other items of the proposal, for the highest alternate bid. Successful bidder must furnish one hundred per cent performance bond.

Louis J. Herrmann, Sr.
Chairman of the Board

U. S. Government

DEPARTMENT OF THE INTERIOR, Bureau of Reclamation. Sealed bids (Specifications No. DC-4795) will be received at Cody, Wyoming, until December 19, 1956, for furnishing labor and materials for rehabilitation of Lower Outlet Works and Penstock Intakes at Buffalo Bill Dam, Shoshone Project, Wyoming. Location near Cody, Wyoming in Park County. Principal items are 4,800 cu. yds. excavation; 1,360 cu. yds. concrete; unwatering lower outlet tunnel; and other work. Completion time 800 days. For particulars, address Bureau of Reclamation, P. O. Box 839, Cody, Wyoming; or Building 53, Denver Federal Center, Denver 2, Colorado. W. A. Dexheimer, Commissioner.

DEPARTMENT OF THE INTERIOR, Bureau of Reclamation. Sealed bids (Specifications No. DC-4800) will be received at Kanab, Utah, until December 18, 1956, for furnishing labor and materials for Colorado River Bridge, Glen Canyon Dam, Colorado River Storage Project, Arizona-Utah. Location near Lees Ferry, Arizona. Principal items are 2,650 cu. yds. of concrete; furnishing and erecting 7,250,000 pounds structural steel; furnishing and placing 335,000 pounds of reinforcement bars; and other work. Completion time 750 days. For particulars, address Bureau of Reclamation, P. O. Box 267, Kanab, Utah; or Building 53, Denver Federal Center, Denver 2, Colorado. W. A. Dexheimer, Commissioner.

ENGINEERS

Designers Detailers Draftsmen
for work on
Bridges, Expressways, Turnpikes

PERMANENT POSITIONS DEPENDING ON EXPERIENCE AND ABILITY
PAID VACATION, SICK LEAVE HOSPITALIZATION, LIFE INSURANCE
INCLUDE EDUCATION, EXPERIENCE, REFERENCES AND SALARY EXPECTED IN APPLICATION LETTER

Howard, Needles, Tammen & Bergendoff
1805 GRAND AVE. KANSAS CITY 8, MO.

ENGINEERS

Opportunity for growth with a new division of an old, established company.

Openings for engineers with
Architectural
Structural
Mechanical
Plastics
experience in building products field.

Send complete personal and employment history with compensation requirements. (Chicago location.)

P-3453, Engineering News-Record
520 N. Michigan Ave., Chicago 11, Ill.

ENGINEERS
COME SOUTH!

We have immediate openings for Engineers—Designers—Detailers—Draftsmen—Civil—Highway—Structural—Traffic—Architectural—Mechanical—Electrical. Company-paid hospitalization, life insurance and retirement. 40-hour week. Air-conditioned offices. Salaries $400 to $800, depending on education and experience. Permanent position. Excellent opportunities for advancement. Send complete resume of education and experience with salary requirement to:

PALMER & BAKER, Inc.
P. O. Box 346
MOBILE, ALABAMA

Engineering Agency
209 S. State St., 7th fl.
Chicago 4, Ill.
Wabash 2-2900
ALL POSITIONS 100% FREE

Structural Draftsmen
$3.00-$5.50 hr.

Experience in any phase of construction drafting is welcome. Interested in young men getting started as well as heavier experience.

Ask for R. A. Beal
Call—Write—Wire

EMPLOYMENT OPPORTUNITIES

DISPLAYED —RATES— **UNDISPLAYED**

The advertising rate is $28.25 per inch for all advertising appearing on other than a contract basis.
An Advertising Inch is measured ⅞" vertically on a column—3 columns 30 inches to a page.
Subject to Agency Commission.

$2.10 per line, minimum 3 lines.
Position Wanted ½ of above rate.
Box Numbers—counts as 1 line.
Discount of 10% if full payment is made in advance for 4 consecutive insertions.
Not subject to Agency Commission.

Send NEW ADS to ENGINEERING NEWS-RECORD, P. O. Box 12, N. Y. 36, N. Y.

ASSISTANT MANAGER

For Industrial Construction Division

Degree desirable; 10-15 years' administrative, executive & technical experience; knowledge of field construction for the supervision of activities of the industrial construction division. Extensive travel, liberal per diem.

DIVISION MANAGER

For Power Plant Projects Design

10-15 years in thermal power plant engineering, design, layout & project work. Degree required.

EXECUTIVE SALES ENGINEER

For Development of New Power Plant Business

10-15 years' experience in thermal power plant designing, development, economic studies & sales. Personal contact with people in this industry required. Degree desirable. Extensive travel, liberal per diem.

Rapidly-expanding world-wide engineering firm located on the West Coast offers Relocation Expenses & Outstanding Company Benefits. Send resume to:

P-3449, Engineering News-Record
Classified Adv. Div., P. O. Box 12, New York 36, N. Y.

REPLIES (Box No.): Address to office nearest you c/o This publication Classified Adv. Div.
NEW YORK: P. O. Box 12 (36)
CHICAGO: 520 N. Michigan Ave. (11)
SAN FRANCISCO: 68 Post St. (4)

POSITIONS VACANT

Estimator for North Jersey Area—Experienced in heavy construction work, process piping, pipe lines, dams and bridges. Please submit complete resume, noting salary range and availability. P-3277, Engineering News-Record.

Teaching appointments for September, 1957, available at university-associated College of Engineering in field of Civil Engineering. Salary and rank commensurate with experience and academic qualifications. Primary teaching field open as present faculty is flexible; preference, if any, would be in sanitary engineering and allied fields. Suburban location, Middle West, adjacent to large industrial center. P-3268, Engineering News-Record.

City Engineer: Unusual opportunity for graduate Civil Engineer or equivalent with professional license in southern Pennsylvania city. Experience essential in land surveying, street and sewer design and construction and related municipal work. Experience desirable in zoning and subdivision control. No structural design is involved. Would be in charge of Engineering Department, supervise survey crew and draftsmen, and would be expected to meet the public as required. Salary range $7,000 to $8,500 with usual benefits. Permanent non-political position for right man. Send resume of training and experience to: Borough of Chambersburg, 100 South Second Street, Chambersburg, Pa. Attention: J. G. Cree.

Wanted: Office Engineers and Draftsmen experience in the design of municipal paving and sewer projects. Also construction inspectors for large sewer improvement project. Live in beautiful Ozarks, excellent school system—grade, high school and college—reasonable living costs, salary commensurate with training and experience, plus paid vacation and sick leave. Contact Personnel Department, City Hall, Springfield, Missouri.

Estimator—Buffalo, New York Area experienced on large building propects. Please furnish experience record and salary requirements. Johnson, Drake & Piper, Inc. 2760 Walden Avenue, P. O. Box 2567, Buffalo 25, New York.

Chairman of civil engineering department in college in New York State. Ph.D. desirable, not essential. Position open summer of 1957. P-3324, Engineering News-Record.

POSITIONS VACANT

Professor or associate professor in civil engineering and mechanics. College in New York State. Term starting February or September 1957. Ph.D. desirable, not required. P-3328, Engineering News-Record.

Engineers and draftsmen structural for steel and concrete design Public Buildings. Consulting Engineers office. Call or write giving training and experience. Saul Shaw & Co., 24 Commerce St., Newark, N. J.

Wanted: Draftsmen, also Bridge Designers and Highway Designers, preferably with some field experience for major highway and bridge projects. Forward education and experience records along with salary requirements. Brookhart & Tyo, Consulting Engineers, 1729 N. Front Street, Harrisburg, Penna.

Civil Engineer: To supervise Engineering Department in rapidly growing Santa Clara Valley City. Population 21,000 will increase to 45,000. Must have 5 years experience in C. E. Salary range $553-673. Submit a letter of application giving experience, education and personal background to Personnel Office, City Hall, Mountain View, Calif.

Associate Engineer ($425 to $575) in New Mexico Health Department. B.S. in civil or sanitary engineering. Write: Merit System, Box 939, Santa Fe, New Mexico.

Designers—Steel, Concrete, Electrical Piping, Air-Cond., Power Plants & Industrial Bldgs. Marbarry Corp., 120 Greenwich St., N.Y.C. Rector 2-3749.

Experienced Estimator, Capable of preparing estimates, pricing, purchasing, subcontract negotiation. Permanent position with old established and progressive General Contractor located near Chicago. Send complete history including education, past experience, reference and salary expected. P-3364, Engineering News-Record.

Wanted, Civil Engineering Draftsmen, Ink Tracers, Computers, Land Surveyors. Only well qualified need apply. Give experience record and salary expected in first letter. P-3379, Engineering News-Record.

Carpenter foreman or carpenter superintendent who is qualified to take over 3 highway bridges and complete same. Must be thoroughly familiar with plans and specifications. P-3386, Engineering News-Record.

(Continued on page 136)

Plan Your Future with

BECHTEL

In California on Hydro Electric Power Design

- Work in Los Angeles
- Liberal relocation allowances for you and your family
- Excellent facilities in area for advanced education
- Advancement based on merit
- Organized program of Personnel Development
- Personal accident insurance paid by the company
- Group insurance with liberal company assistance
- Opportunities in diversified types of engineering and drafting
- Contact with latest technological developments
- Air conditioned modern offices.

Immediate Openings

Supervising Engineers
Hydraulic Experience

Engineers
Civil
Hydraulic
Structural
Electrical
Mechanical

Designers
Piping
Electrical
Structural

Men experienced in design of earth-fill or concrete dams, spillways, penstocks and hydro electric power stations are desirable. Allied experience acceptable.

Send resume to
Manager of Employment & Placement
Industrial Relations Division

BECHTEL
Corporation
220 Bush St., San Francisco 4, Calif.

For an immediate personal interview you may phone:
Paul Keating, Plaza 7-4400, New York City
Joe Braddick, Fairfax 3-2401, Houston, Texas
Bill Milligan, Tucker 1549, Los Angeles, Calif.
Don Palmer, Douglas 2-4032, San Francisco, Calif.

Engineers Architects

Highway Designers—Draftsmen
Rochester & Harrisburg, Pa., Jackson, Miss. & Ft. Lauderdale, Fla.
Bridge Designers—Draftsmen
Harrisburg, Pa.-College Park, Md.-Ft. Lauderdale, Fla., Jackson, Miss.
Architectural Designers—Draftsmen
Rochester, Pa.
Civil Engineering Draftsmen
Jackson, Miss.
Ink Tracers—Computors
Rochester, Pa., Jackson, Miss.

Air Mail Resume TO R. L. SHAW, *Personnel Director*

MICHAEL BAKER, Jr., INC.

BAKER BLDG. *Consulting Engineers* ROCHESTER, PA.

TONNAGE OXYGEN LOW TEMPERATURE PROCESSING

The leading company in this essential and growing industry offers an exceptional opportunity for qualified persons to become a part of the permanent staff of its newly formed Engineering Construction Division.

- Field supervision of construction.
- Piping design and layout.
- Structures, buildings, and foundation design.
- Electrical design for powered process machinery.
- Instrumentation.

Openings for all levels of experience. Apply to B. H. VanDyke

AIR PRODUCTS, INC.

P. O. Box 538 Allentown, Pa.

ENGINEERS

Key positions open for experienced Engineers to be in responsible charge of individual projects with excellent opportunities for advancement.

CIVIL OR SANITARY ENGINEER to Design Sewage Treatment Plants and Sewage Works.

STRUCTURAL DESIGNERS experienced in Concrete and Steel Design of Sewage Treatment, Water Treatment Plants, or the design of Hydraulic Structures in connection with Dams.

SOILS ENGINEER experienced in Slip Circle Analysis Method for Design of Earth Dams.

TRAFFIC ENGINEER experienced in O. and D. and Parking Surveys and Analysis of Data.

Also key positions for:

HYDRAULIC ENGINEER experienced in Earth and Concrete Dam Design.

CIVIL OR SANITARY ENGINEER as Principal Assistant in Design.

Ideal living conditions. Vacations and sick leave, Bonus, Insurance and Retirement Benefits.

Send complete resume to—

GANNETT FLEMING CORDDRY & CARPENTER, INC.

P. O. Box 366 Harrisburg, Pennsylvania

ENGINEERS

The Sherwin-Williams Company, world's largest manufacturer of paints, varnishes and lacquers, has two excellent engineering positions available at its main Engineering and Construction center located at 115th and Cottage Grove in the southern section of Chicago, Illinois.

Project Engineer

Desire a graduate M.E. with approximately three to five years' experience, preferably in a chemical plant, who will be able to take plans from architects, design or layout engineers, and make complete installations in present manufacturing departments as well as in new departments or divisions. Must have supervisory ability as he will supervise at least two or more subordinates. This is a position of promotional opportunity.

Structural Design Engineer

Applicants should have a B.S. degree in Civil Engineering with aspirations of obtaining structural engineer license. Design structures such as building additions, alterations in existing buildings and new buildings from time to time, as well as designing steel and structural supports for additional equipment and material loads in existing buildings. Also has the opportunity to handle some process engineering work. Should have supervisory ability since he will, after training, supervise the work of draftsmen in the department. Experience in structural design preferred but not necessary.

Please state age, education, experience, salary desired and other information. All replies confidential.

Industrial Relations Department
The Sherwin-Williams Co.
101 Prospect Avenue, N. W.
Cleveland 1, Ohio

ENGINEERS

Live and Work in a small progressive City near Columbus, Ohio. Positions open, Consultants office employing 40—50.

(A) Structural engineer, C.E. graduate, registered, with minimum 5 years experience designing reinforced concrete and structural steel. Supervision of structural design section.

(B) Mechanical or civil engineer with minimum 5 years experience design and/or constructing sewage and water treatment plants to check shop drawings and supervise construction work.

Salaries open; Permanent position for qualified engineers. Full information desired.

P-3305, Engineering News-Record
520 No. Michigan Ave., Chicago 11, Ill.

HIGHWAY DESIGN ENGINEERS

Permanent positions for men with degrees and 2 to 5 years' experience or equivalent. Work for old established consulting firm in Harrisburg, Pennsylvania. Excellent living conditions, fully paid retirement, insurance, vacation, holidays, new air-conditioned offices, hospitalization insurance available. Send resume to Modjeski and Masters, Harrisburg, Pennsylvania.

ENGINEERS

Long established firm of consulting engineers with world-wide practice needs both beginners and experienced civil, electrical, mechanical, and foundation engineers for interesting work on large dams, powerplants, and river control works. Permanent positions. Liberal employee benefits. Starting salaries dependent on qualifications. Please send complete resume to Hugo Niemi, Personnel Manager.

HARZA ENGINEERING CO.

400 W. Madison St. Chicago 6, Ill.

BECHTEL

AREA ENGINEERS
SENIOR ENGINEERS

Foreign Employment
Saudi Arabia

Field Engineers with refinery or related construction experience.

Office Engineers with heavy industrial construction experience on planning, estimating, costs, material takeoff, scheduling.

No Family Housing

Send resume to:
Manager of Employment & Placement
Industrial Relations Division

BECHTEL
Engineers and Builders
for Industry
220 Bush Street
San Francisco 4, California

ENGINEERS
Are you worth up to
$10,000 A YEAR?

Important permanent positions, paying from $6,500 to $10,000 a year with unusual future opportunity, have been created by the expansion program of our large, long-established engineering and construction firm. We need qualified engineers, designers and draftsmen experienced in structural, concrete, mechanical and piping design. Engineering offices are in several major American cities and Canada. Excellent working conditions. Generous company benefits. Our employees know of this ad.

Investigate this opportunity. Write today, giving age, education and experience. Your inquiry will be kept strictly confidential and will be answered promptly.

P-3067, Engineering News-Record
520 N. Michigan Ave., Chicago 11, Ill.

SUPERINTENDENT

Wanted by a substantial company now producing concrete masonry building units a superintendent to take charge of designing, building and operating an additional plant in which all types of pre-cast structural shapes will be produced.

Exceptional opportunity for the right man.

In making application, please state experience and salary desired.

P-3310, Engineering News-Record
520 No. Michigan Ave., Chicago 11, Ill.

ENGINEERS
Civil & Structural

Permanent positions for squad leaders, designers and draftsmen with established consulting firm for large hydro-electric and irrigation projects. Liberal benefits. Salary commensurate with qualifications. Submit complete experience record and salary requirements.

ERIK FLOOR & ASSOCIATES, INC.
139 N. Clark St. Chicago 2, Ill.

HIGHWAY ENGINEERS
DESIGNERS
DRAFTSMEN
Drainage Engineers

FOR OFFICE WORK IN ST. LOUIS ON HIGHWAYS EXPRESSWAYS AND ASSOCIATED CIVIL WORKS

- *Permanent employment for qualified men*
- *Ample opportunity for advancement based on merit*
- *Generous transportation & moving allowances*

Plus Employee Benefit and Retirement Plan, Paid Vacations, Holidays, Sick Leave. Blue Cross available.

PLEASE WRITE FULLY TO OR INQUIRE AT

SVERDRUP & PARCEL ENGINEERING CO.
1134 LOCUST ST. ST. LOUIS 1, MO.

ENGINEERS
APPLY NOW FOR 1957 FOREIGN WORK

Some Immediate Openings

CIVIL, ELECTRICAL and MECHANICAL ENGINEERS and INSPECTORS—

Needed for supervision on northern air bases at attractive salaries. Some seasonal, others one year or more. No dependents' quarters.

Submit resume stating education, experience, salary requirement, and availability, or send for our application form.

FAY, SPOFFORD & THORNDIKE, Inc.
Consulting Engineers
11 Beacon St., Boston 8, Mass.
Personnel Dept. Tel: LAfayette 3-8300

TRAFFIC ENGINEER

Graduate Engineer with at least one year of traffic engineering experience or education. Experience in highway engineering desirable but not necessary.

SALARY: $6500 to $8000

Apply: Malcolm E. Austin

CLARKESON ENGINEERING CO. INC.
285 Columbus Ave. Boston 16, Mass.

TOP-FLIGHT
ENGINEERS
DESIGNERS
DRAFTSMEN

McKEE has openings for top men to fill important, permanent positions, with excellent prospects for promotion to supervisory, staff and executive posts in our expanding organization.

Our Metals, Refinery and Industrial Divisions offer you wide choice of opportunity to make fullest use of your talents in the design of refineries, blast furnaces, steel, sintering, chemical and industrial plants and their auxiliaries.

Investigate the advantages of top compensation, ideal working conditions, employment security, advancement opportunity and many generous benefits available to you at McKee.

Telephone TOwer 1-2300, Cleveland, Ohio or write to Edward A. Kelner, Arthur G. McKee & Company, 2300 Chester Ave., Cleveland 1, Ohio

Arthur G. McKee & Company
Engineering offices in
CLEVELAND, OHIO • UNION, N.J. • TORONTO, ONT.

ENGINEER

Civil or mechanical engineering graduate preferred. Practical knowledge of soil mechanics desirable. Excellent opportunity for alert young engineer. Submit complete resume including salary desired.

RAYMOND CONCRETE PILE COMPANY
(Boring Division)
140 Cedar Street New York 6, N. Y.

EMPLOYMENT OPPORTUNITIES

POSITIONS VACANT

(Continued on page 123)

Wanted: Civil Engineer, registered in New Jersey, at least 10 years experience in road and bridge design and construction. Must have executive ability. State qualifications in full, experience resume, references and salary requirements. Reply to P-3307, Engineering News-Record.

Junior Construction Cost Engineer. Some knowledge of estimating desirable. Excellent opportunity with long established international company. Location New York City. P-3347, Engineering News-Record.

Teaching Personnel for the department of Mechanics, B.S. in engineering required, Masters Degree preferred. No teaching or industrial experience necessary. Salary range $4000 to $6500 for nine months. Rank and salary dependent upon qualifications. Location Southwest. P-3417, Engineering News-Record.

Wanted: Graduate Mechanical Engineer to age 35 New York office international and domestic contractor—permanent job. Must have at least two years experience specifying and inspecting contractors heavy equipment. P-3418, Engineering News-Record.

Engineering—With experience on sewers and pavements to supervise field construction. Permanent position under Civil Service with retirement plan. Apply Personnel Director City Hall, Royal Oak, Michigan.

Civil or Sanitary Engineers salary open—depending upon qualifications. Send resume to Gardner & Sterling, Consulting Engineers, P. O. Box 74, Salisbury, Maryland.

Experienced Estimator and Chief Engineer between the ages of 34 and 48 for preparing estimates, pricing, purchasing, expediting, and job management. Permanent position for the right man with Midwest General Contracting firm specializing in industrial, commercial and public works. As this job will be in the capacity of assistant to the president, none but top men need apply. Send complete history, including education, past experience, references, salary expected, and photograph, if available. P-3451, Engineering News-Record.

Structural Engineers—Two to ten years experience on buildings or bridges. Attractive offer with progressive consulting firm. Box 121, Station H, Toledo, Ohio.

POSITIONS VACANT

Draftsmen—Opportunity for growth with a new division of an old, established company. Openings for draftsmen with architectural, structural or mechanical experience. Send complete personal and employment history with compensation requirements. (Chicago location). P-3452, Engineering News-Record.

City Engineer for city of 26,000 population. Graduate engineer required—state salary expected, experience, age, availability and references. Reply City Manager, Gloucester, Mass.

EMPLOYMENT AGENCY

Wanted Engineers, Designers, Draftsmen All lines. Chemists, teachers and industrial engineers. Recent grads. Cleveland Engineering Agency 2132 E. 9, Cleveland.

EMPLOYMENT SERVICE

Salaried Positions $6,000 to $35,000. We offer the original personal employment service (established 46 years). Procedure of high standards individualized to your personal requirements. Identity covered. Particulars—R. W. Bixby, Inc., 559 Brisbane Bldg., Buffalo 3, N. Y.

POSITIONS WANTED

Civil Engineer, 50, Administrative, executive, expressways, bridges, steel and concrete structures, sewage, design and construction. Available Nov. 22 PW-3293, Engineering News-Record.

Project manager graduate professional engineer, 43. Heavy background in power and industrial plants—engineer — design — construction—management. Present project terminating. Staff available. PW-3287, Engineering News-Record.

Construction Executive, Chief Estimator fully experienced, quantity survey to completion, subs, purchases, job manage heavy industrial, commercial, monumental, prefer N. Y., N.E., Mid-Atlantic States. PW-3313, Engineering News-Record.

Civil Engineer Graduate (39), wide experience in construction, estimating, survey and office, desires responsible position with reputable company in Caribbean or South America. Would consider partnership in growing Florida concern. PW-3423, Engineering News-Record.

POSITIONS WANTED

Superintendent, Heavy & Bridge Construction, 19 years experience, bid to completion, $200. PW-3420, Engineering News-Record.

Construction Engineer—B.Sc. Arch. Eng.— Age 36—4 years structural engineering, 10 years building construction estimating, purchasing, supervision, labor negotiations, complete responsibility. PW-3442, Engineering News-Record.

Materials Testing Engineer — 8 years exp., college degree, desires position preferably in New Jersey. Presently supervising Spanish technicians on air base program. Available Feb. 1957. PW-3443, Engineering News-Record.

Construction Administrative Executive capable of heading construction program. 25 years wide and diversified experience—heavy in plans and specifications production; budget control; awarding contracts; field management. Registered Architect; Registered professional engineer. Available December 1st. PW-3440, Engineering News-Record.

Construction Executive or engineer 25 years experience on heavy industrial construction, at home & abroad, mostly in oil refineries, highways, rubber & TNT plants & factory type buildings. Seek a permanent connection, location immaterial. PW-3425, Engineering News-Record.

Salesman, estimator, production man experienced in large scale industrial roofing and sheet metal contracting, wants worth-while connection with growing firm. Can produce profitable sales in volume. Write PW-3430, Engineering News-Record.

Management position wanted in industrial roofing and sheet metal contracting, by highly experienced executive, capable and well-known in the industry. Write PW-3433, Engineering News-Record.

Construction Superintendent: 25 years experience, field supervision constructing industrial commercial, institutional bldgs, large scale housing, churches, etc.; desires similar position with reliable organization; will travel. PW-3426, Engineering News-Record.

SELLING OPPORTUNITY WANTED

Industrial Product manufacturer, established in all branches industries and administrations, network representatives France and Benelux, seeks all articles for dinstribution. Reference clients on request. Write Agence Havas No. 281/598 Rue Vivienne 17, Paris.

SEARCHLIGHT SECTION

(Classified Advertising)

BUSINESS OPPORTUNITIES — **EQUIPMENT USED or RESALE**

UNDISPLAYED ——RATES—— *DISPLAYED*

$2.10 a line, minimum 3 lines. To figure advance payment count 5 average words as a line.

BOX NUMBERS count as one line additional in undisplayed ads.

DISCOUNT of 10% if full payment is made in advance for four consecutive insertions of undisplayed ads.

The advertising rate is $23.60 per inch for all advertising appearing on other than a contract basis. Contract rates quoted on request.

AN ADVERTISING INCH is measured ⅞ inch vertically on one column, 3 columns—30 inches to a page.

EQUIPMENT WANTED or FOR SALE ADVERTISEMENTS acceptable only in Displayed Style.

Send NEW ADVERTISEMENTS or Inquiries to Class. Adv. Div. of Engineering News-Record, P. O. Box 12, N. Y. 36, N. Y. November 29th issue closes November 16th.

REPLIES (Box No.): Address to office nearest you c/o This publication Classified Adv. Div.
NEW YORK: P. O. Box 12 (36)
CHICAGO: 520 N. Michigan Ave. (11)
SAN FRANCISCO: 68 Post St. (4)

SPECIAL SERVICE

Contract Disputes? Government construction contractors who have contract questions under dispute are offered my experience in the settlement or the appeal of said disputes. SS-2433, Engineering News-Record.

WANTED

Anything within reason that is wanted in the field served by Engineering News-Record can be quickly located through bringing it to the attention of thousands of men whose interest is assured because this is the business paper they read.

PARTNER

Mill Supply and Construction Company needs partner to check fabrication in New Orleans and supervise foreign installations of machinery and equipment. Required investment $6,000.

BO-3444, Engineering News-Record
520 N. Michigan Ave., Chicago 11, Ill.

2400 HP Alco Diesel,

16 cylinder, VEE type, 9" bore, 10½" stroke. Supercharged. Modern unit. Suitable for dredge or Marine service.

ALJON ELEC. DIESEL CO.
904 Pacific St. Bklyn. 38, N. Y.

WANTED
By marine contractor, two steel deck barges, one steel dumper barge, one steel tank barge & one small tug.
D. W. HARRINGTON
Bromo Seltzer Bldg., Baltimore 1, Md.
Saratoga-7-2647

Engineers—Foremen—Office Men

Learn latest methods to organize and run work. Prepare for the top jobs.
Send post card for details.
GEO. E. DEATHERAGE & SON CONSTRUCTION CONSULTANTS
P.O. Box 921 Lake Worth, Florida

PIPE
Surplus New & Used
FOR SALE

Thousands of SUCCESSFUL BUILDERS USE
Building Labor Caculator
150 tables cover structural and finish in hours—tradesmen, helpers, foremen, and materials allowing normal waste. 1956 printing, ten day free inspection, money back guarantee, $10.00 postpaid:
TAMBLYN SYSTEM, Gordon M. Tamblyn
5732 Highland Court North, Kansas City 16, Mo.

PILING · PILE FITTINGS · PIPE
CULVERTS · VALVES & FITTINGS
SPECIALISTS IN PRE-FAB. PIPING
ALBERT
PIPE SUPPLY CO., INC.
Berry at North 13 Sts., B'klyn, N. Y.
ALBERT PIPE SUPPLY APS

STRUCTURAL ENGINEERING
ARCHITECTURAL ENGINEERING
OUR COURSES of instruction by mail HAVE HELPED THOUSANDS to better positions and to pass State Board Examinations. Forty-third year.
WILSON *Engineering Corp*
College House Offices HARVARD SQ. CAMBRIDGE MASS

PIPE
VALVES and FITTINGS
All Sizes in Stock
NEW-USED
GREENPOINT IRON & PIPE CO. INC
Baggett and Stagg Streets Brooklyn, N.Y.

COMPRESSOR DIRECTORY
World's Best Rebuilts

25 CFM 2000 psi Ingersoll
48 CFM 3500 psi Ingersoll
60 CFM Worth Portable (3)
88 CFM 100 psi 6x5 Worth H B
75 CFM Worth Portable (4)
105 CFM Worth Portable (3)
125 CFM Worth Portable (2)
137 CFM 100 psi 7x7 Ing. ESI
210 CFM Worth Portable (4)
234 CFM 100 psi 9x9 Penn 3AT
277 CFM 100 psi 8⅜ - 4⅜x5 CP. PE4
315 CFM Worth-Jaeger-Diesel (4)
434 CFM Vacuum 14x7 Worth
464 CFM 100 psi 12x11 Gardner RX
538 CFM 100 psi Worth M 100-New
545 CFM 100 psi Allis Chalm. Rotary (2)
622 CFM Vacuum 18x6 Ingersoll
686 CFM 100 psi 14x13 Ing. ESI
720 CFM Vacuum 18x7 Worth
868 CFM 100 psi 17-10x12 CP. OCB
1546 CFM 100 psi 21-12½x14 CP-OCE Syn.
2018 CFM Vacuum 26x11 Ing. ESI
5748 CFM 50 psi 29-24x21 Ing. PRE (2)
6000 CFM 28 psi-31½-31½x14 Ing. XHE (2)

American
AIR COMPRESSOR CORP.
DELL AVE. & 48th ST. NORTH BERGEN, N. J.
Telephone UNion 5-4848

SAVE THOUSANDS!
UNUSED 6x6 ARMY TRUCKS

***2½-TON, GMC & INTERNATIONAL**



- From Government Storage!
- Unused and Guaranteed!
- Factory-New Condition!
- Reconditioned trucks also available!

Why invest in expensive new trucks and equipment needed to get the roughest off-road jobs done when you can save up to $3,000 on ONE truck alone—and get the job done right!

Compare our tandem axle trucks with front wheel drive, 10 forward speeds, overdrive and new mud and snow tires with similar equipment elsewhere. See for yourself how TWO of our trucks cost you even LESS than one new truck!

If planning to buy a truck, get in touch with us right away. There's no obligation . . . and we deliver on approval!

For Specifications, Prices, Delivery Write, wire or phone COLLECT—JAckson 5-7841
Milton Y. Toombs, Jr. Sales Manager

MEMPHIS EQUIPMENT CO.
Construction and automotive equipment and parts
766 S. THIRD ST. • MEMPHIS, TENN.

CRANES FOR RENT

CRAWLERS — Capacities to 60 tons, Booms to 180 ft.
TRUCK CRANES — Capacities to 35 tons, Booms to 130 ft.

P and H, Lima and Manitowoc.
Top-Condition erection cranes

ROGER SHERMAN
CRANE SERVICE, INC.
East Hartford, Connecticut JAckson 8-4106

JAW & GYRATORY CRUSHERS
DRYERS, KILNS & COOLERS
FEEDERS
PULVERIZERS
BALL MILLS
ROD MILLS
FLOTATION EQUIPMENT
MINE HOISTS
COMPRESSORS
SHOVELS & CRANES
BRIDGE CRANES
CRAWLER CRANES

WE BUY AND SELL EQUIPMENT THROUGHOUT NORTH AND CENTRAL AMERICA

A. J. O'NEILL
Lansdowne, Pa.
Phila. Phones: MAdison 3-8300 — 3-8301

FOR SALE or RENT

25 ton Ohio Diesel Loco. Crane. 1947.
30 ton Browning Diesel Loco. Crane. 1947
40 ton Ind. BH Steam Loco. Crane. 1942.
25 ton American Stiffleg. 100' Bm.
30 ton American #2 Guy Derrick. 90' Bm.
140 HP 2D Diesel Hoists 15000# SLP.
110 HP Amer. 3D #100 Hoist w/ Swinger.
45 ton Davenport Diesel Elec. Loco. 1942.
65 ton Whitcomb Diesel Elec. Loco. 1945.
1½ yd. Northwest #o Diesel Crane New 1948.
1½ yd. Bucyrus Erie 38B Diesel Crane. 1948.
60 ton Manitowoc 3900 Erection Crane. Rent.
100 HP Lucey Portable Boilers. 200# WP.

MISSISSIPPI VALLEY EQUIPMENT CO.
509 Locust St. St. Louis 1, Mo.

FOR SALE

Sargent M-410 ⅝ yd. Basic Unit, #10379, Oliver Diesel engine, 25' x 10" boom; on 375 Zeligson Carrier

Quickway Model 105A 5/10 yd. Basic Unit, #14060, Continental F-233 engine; on Model 1066 Crane Carrier

Buckeye Model 308 Utility Ditcher, #153, Chrysler gasoline engine, equipped wo to dig 20" wide, 5'6" deep

All above equipment new in June and July, 1956

Murphy Model 24 Diesel engine, 232 hp @ 1200 rpm; heat exchangers; twin disc enclosed clutch; flexible coupling, extended shaft with two outboard bearings. New—never been used. For sale at less than dealer's cost.

Fairbanks-Morse Centrifugal pump, 10" suction, 8" discharge, 75 hp F-M Motor, 2000 gpm @ 115' head. Excellent condition

Link Belt LS 85 Shovel-Dragline combination, #7A1024, Cat engine. Fair condition. Priced to sell

Barber-Greene 44-B Trencher, dig 5'6" deep, 18" wide. Good operating condition.

Tri-State Equipment Co., Inc.
520 Mulberry Jackson 5-3716
Memphis, Tenn.

FORSYTHE EQUIPMENT CO., INC.
MANITOWOC SPEEDCRANES
RENTALS

Capacities to 70 Tons
Booms to 140 ft. and 30 ft. jibs.
Special rates on long rentals

Exeter 2-6125 37-11 Vernon Blvd.
Long Island City 1, New York

FOR SALE
DIESEL ELECTRIC LOCOMOTIVES

STANDARD GAUGE

25 - 35 - 40 - 50 - 65 - 75 - 100 tons

Write for Details

FRANK M. JUDGE & CO., INC.
7010 Empire State Building
New York 1, N. Y.

FOR SALE

ONE USED HYSTER TOWING WINCH, Serial Number not available. Probably a 1944 model. Good working condition.

ONE USED LUFKIN TOWING WINCH, Model 60, Serial Number 627 for TD-14 Crawler Tractor.

RISH EQUIPMENT COMPANY
P. O. Box 120—Annex Station
Cincinnati 14, Ohio

8½ YD. SMITH TRUCK MIXER

Used as Demonstrator for short time.
Excellent Condition.

Hodge & Hammond, Inc.
720 Garrison Avenue, Bronx, N. Y. C.
New York Phone—Kilpatrick 2-2400
New Jersey Phone—Market 3-5424

The world's largest selection of *quality* Used Construction Equipment . . .

John Fabick Tractor Company—a Caterpillar dealer—has assembled the most complete selection of used construction equipment in the world. Machines of every type, make, price and condition are "in-stock". Many are backed by a $10,000 Performance Bond. Whatever you need, whatever you want to pay, wherever you want it shipped—Fabick can help you! Write, wire or phone today for a complete listing or for information on a specific machine.

LOOK AT THESE "BUYS" . . .

U-157 Cat D4 Tractor 60", N. O., with Cat 44 Hyd. Control and HT4 Traxcavator. S/N 7U6523. 15" flat shoes. Fender-mounted fuel tank. Track roller guards. Heavy-duty fenders. Full flow filters. Elect. start. 75" bucket. A-1 shape. F.O.B. Marion, Ill. **$8,500**

U-327 Allis-Chalmers HD5G Tractor, N. O., with Tractomotive hyd. loader. S/N 2614. 13" triple bar grousers. Track roller guards. Crankcase guard. Elect. start and lights. 75" bucket with ten teeth. Good operating condition. F.O.B. Flora, Ill. **$5,000**

WRITE E. F. KUBEL . . .

JOHN FABICK TRACTOR CO.

FABICK USED EQUIPMENT

A CATERPILLAR DEALER

3100 GRAVOIS AVENUE ST. LOUIS 1, MISSOURI

PHONE PR 2-8900

Cat and Caterpillar are registered trademarks—®

SURVEYING INSTRUMENTS

USED • REBUILT • SALE
RENT • REPAIRING

TRANSITS AND LEVELS

New or Rebuilt Sale or Rent

Headquarters for REPAIRS — any make — Factory Service. We will also buy your old instruments or take them in trade.

A complete line of Engineering Instruments and equipment for field or office. Write for Catalog NRL 611.

WARREN-KNIGHT CO.

Manufacturers of Transits and Levels

136 No. 12th St., Philadelphia 7, Penna.

TRANSITS & LEVELS

Various Makes
NEW & REBUILT

Fully equipped modern shops — all makes and models repaired — all work guaranteed — prompt service — complete line field supplies.

INSTRUMENTS RENTED

Midwest Representative: W. & L. E. Gurley

NATIONAL BLUE PRINT CO.

Established 1914
210 S. Canal St. Chicago (6), Ill.

RAILS—TIES

TRACK ACCESSORIES *NEW and RELAYING*

Railway Track Material

NOW DISMANTLING

18 miles 90# ARAB; 3 miles 90# ASCE; 5 miles 85# ASCE; all 33' lengths; 20 miles 76# section, all 30' lengths. All rails relaying quality, complete with angle-bars and tie-plates punched to conform. Also over 50,000 excellent used, creosoted, 6x8x8'6" cross ties.

Address inquiries carload or more to S. FELDMAN

Morrison Railway Supply Corp.

Rand Bldg. Buffalo, N. Y.

Phone: MOhawk 5820

RAILROAD Cross and Switch **TIES**

Promptly from adequate stocks
NEW and USED *(as available)*

GILLIS & COMPANY

29 East Madison St. Chicago 2

RAILS - TIE PLATES

Frogs & Switches—Track Accessories

W. H. DYER CO., INC.

2110-X Railway Exchange Bldg., St. Louis 1, Mo.

NEW—RAILS—Relayers

All sizes and weights. Also frogs, switches, spikes, bolts, tie plates, contractors' and mine equipment carried in stock.

M. K. FRANK

480 Lexington Ave. New York, N. Y.
Reno, Nevada
Park Bldg. Pittsburgh, Pa.
Carnegie, Pa.

RAILS—New & Relaying from Largest Warehouse Stocks in U.S.

L. B. FOSTER CO.

PGH. 30 • N.Y. 7 • CHI. 4 • ATL. 8 • HOUST. 2 • L.A. 5

RAILS

NEW — RELAYING — TIES — Fastenings

MIDWEST STEEL CORP.

502 DAVIDSON BUILDING

CHARLESTON W. VA

IMMEDIATE DELIVERY

---

expert repairs

or complete overhauling by skilled craftsmen on all makes and types. Precision guaranteed.

FINE RENTAL INSTRUMENTS

Reasonable rates, on monthly or yearly basis. All instruments guaranteed to be in first class condition.

David White COMPANY

ALL MAKES

REPAIRS RENT REAL EXPERTS

BUFF

69 Day St., New York WOrth 2-2797

SPECIALIZED REBUILDING

of surveying and engineering instruments. All makes and models expertly repaired in modern shop. All work guaranteed.

Distributors for Brunson Instruments

Hickerson Instrument Co.

8 North Edmondson Avenue, Indianapolis 19, Indiana

Watch—
the *Searchlight Section*
for
Equipment Opportunities

DON'T WAIT
WF-H BEAMS
PILE SECTIONS
NEW • USED • IN STOCK

8" B P	36#	19/35'
10" B P	42#	45/50'
12" B P	53#	60/65'
14" B P	73#	60/65'
14" B P	89#	60/65'

We are also interested in purchasing your surplus material.

We assure you our prices will be the best obtainable.

Call HY DRACHMAN
STEEL CORPORATION
14-23 34th Ave., Astoria, N. Y.
Phones: AStoria 8-4484 8-8023

FOR SALE or RENT—EASY TERMS
Rebuilt—A 1 Condition
48B Bucyrus Erie Shovel 2 cy Diesel
Northwest Model Shovel, 1½ cy
Comb. Caterpillar D8 & 80 Scraper
10 ton Buffalo Springfield Gas Roller
International Vibro-Tamper
WILLIAMS CONSTRUCTION COMPANY
Box 145 Balto. 20, Md. Murdock 6-6600

LOW COST INSTALLATION AND OPERATION

CABLEWAYS
IMMEDIATE SHIPMENT
ELECTRIC, STEAM or DIESEL
CAPACITY 3 TO 20 TONS
SELL, RENT or BUY

FOR DAMS, BRIDGES, BREAKWATERS, FILTRATION AND SEWERAGE PLANTS

FOR SPEED, ECONOMY, EFFICIENCY, FLOOD SAFETY, LABOR REDUCTION

AMBURSEN DAM CO. INC.
295 MADISON AVE NEW YORK

CONCRETE PLANT
JOHNSON 4 COMPARTMENT
Automatic Concrete Plant with 750 barrel silo, 2 cy. Smith Mixer.
Extra equipment for job site operation.
Subject to Prior Sale
CONSTRUCTION SERVICE COMPANY
P. O. Box 311 Bound Brook, N. J.

EUCLIDS
Used 13 yd. bottom dumps
Cummins & General Motors Powered
Located - Texas - Pa. - N. Y. State
Write, wire or Phone
L. B. SMITH, INC.
Camp Hill, Penna.
Tel: Harrisburg, Regent 7-3431

NEW AND REBUILT
STORAGE BATTERY
LOCOMOTIVES
1½ to 10 Ton — 18" to 56" Track Gauge
GREENSBURG MACHINE CO.
Greensburg, Pennsylvania

PILING
SURPLUS NEW and USED For Sale or Rent

20-25 Yard
Tractor Drawn Scraper
with four 24:00 x 32, 24 ply tires
Excellent Condition
HODGE & HAMMOND, INC.
720 Garrison Ave., Bronx,
New York City
NY Phone: Kilpatrick 2-2400
NJ Phone: Market 3-5424

NEW. SURPLUS
STEEL SHEET PILING

BELVAL Z
perfect range of corrugated sections most economical section modulo

AMERLUX STEEL PRODUCTS CO.
NEW YORK 17, N. Y.
Direct Mill Office of the
ARBED
STEEL MILLS
IN LUXEMBOURG

BELVAL P *straight web section best deflected bending*

We do a Nation-Wide business in
STEEL SHEET PILING

IMMEDIATE SHIPMENT

156 pcs. 60 ft. Carn. MP-112—Illinois
310 pcs. 60 & 50 ft. Beth. ZP-32—New York
220 pcs. 60-30 ft. Carn. MP-116—Illinois
115 pcs. 50-40 ft. Inland I-23—Kansas
210 pcs. 30 ft. carn. MP-116—Colorado
44 pcs. 25 ft. Carn. MP-115—Kansas
58 pcs. 20 ft. Carn. MP-116—Tennessee
Other Lengths & Sections at Various Locations

PILE DRIVING EQUIPMENT
Vulcan and McKiernan-Terry
Steam Pile Hammers and Extractors
Hoists and Boilers

MISSISSIPPI VALLEY EQUIPMENT CO.
509 Locust St., Chestnut 1-4474, St. Louis, Mo.

DIESEL
POWER PLANT GENERATOR
FOR SALE BY OWNER

GENERATOR
1000 K W, 1250 KVA, .80 PF, 2300 Volt, 3 phase, 60 Cycle, 720 RPM, General Electric, Serial 5610882.

DIESEL ENGINE
General Motors, Cleveland Diesel Engine, 16 Cyl., Model 278A, rated 1440 HP at 720 RPM, Serial 9855.

ACCESSORY EQUIPMENT
Generator control panel, lube and fresh water coolers, filters, air intake silencer, carbon dioxide engine killing unit, pyrometer board, engine control board, day tanks, heat exchangers, alarm system, compressors, air storage tanks, centrifuge, exhaust silencer, 32 x 48 Butler steel building housing unit.

TRANSFORMERS:
4—333KVA 2400—240/480 volts, General Electric.

Located at Greene, No. Dakota on trackage offered where it and as it, subject to prior sale.

J. L. SHIELY COMPANY
1101 No. Snelling Ave.
St. Paul 13, Minnesota.
Midway 6-8601

STEEL SHEET PILING
415 pcs. Beth. AP-3, 16', 20' & 35'
617 pcs. Beth. DP-2, 20', 32' & 40'
175 pcs. Beth. ZP-32, 30' to 32½'
2 STIFF LEG DERRICKS
185 Ton 85' B 52' Mast 20' BW 50' Sills
15 Ton 116' B 39' Mast 13' B Wheel
R. C. STANHOPE, INC.
60 E. 42nd St., N. Y. 17, N. Y.

LARSSEN SHEET PILING
WESTERN SERVICES CORPORATION
representative of SIDELOR FRANCE
601 E. Linden Ave., Linden, N. J.
HUnter 6-4000
STOCK AVAILABLE IN LINDEN, N. J.

RENT STEEL SHEET PILING
Get the exact lengths and sections you need of all standard sections, delivered *on time*—and at Foster's usual low rental rates

H-BEARING PILE
PIPE FOR PILING
LIGHT-WEIGHT STEEL PILING
PILE HAMMERS & EXTRACTORS

L.B. FOSTER co.
PITTSBURGH 30 • NEW YORK 7 • CHICAGO 4
ATLANTA 8 • HOUSTON 2 • LOS ANGELES 5

STEEL SHEET PILING
AVAILABLE FOR PROMPT SHIPMENT

Pcs.	Section	Length	Location
110	MP-115	60 ft.	Kansas City
100	MP-116	60 ft.	Kansas City
244	MP-116	35 ft.	Wisconsin
260	MP-112	14 to 17 ft.	Iowa
160	MP-116	28 to 30 ft.	Colorado
130	MP-112	19 to 25 ft.	Montana
50	MP-116	24 to 27 ft.	Kentucky

CONMACO PHONE DRexel 1-3930
CONTRACTORS MACHINERY COMPANY
804 KANSAS AVE., KANSAS CITY, KANSAS

Additional Searchlight Advertising on following page

PROFESSIONAL SERVICES

NEW ENGLAND

Jackson & Moreland, Inc.
Engineers and Consultants

Design and Supervision of Construction

Reports — Examinations — Appraisals

Machine Design—Technical Publications

Boston New York

Metcalf & Eddy
ENGINEERS

Investigations Reports Design
Supervision of Construction
and Operation
Management Valuation Laboratory
1300 Statler Building, Boston 16

MIDDLE ATLANTIC

Edwards, Kelcey & Beck
Consulting Engineers

Reports, Design Supervision
Subways, Expressways, Traffic, Parking
Harbor Works, Bridges, Tunnels
Housing and Industrial Developments

Newark, New Jersey
New York Philadelphia Boston

John Clarkeson
Consulting Engineer

Civil Engineers — Consulting Services

Highways, Airports, Bridges
Surveys, Waterfront Facilities

Albany and Watertown, N. Y.

Donald J. Belcher & Associates, Inc.
Aerial Photographic Analysis

Engineering Soils Maps
Materials Location Maps
Bedrock Contour Maps
Bedrock Profiles of Center Lines
Soil Profiles of Center Lines
Drainage Maps

For location of highways, dams, pipelines, industrial sites, airports, and watershed development.

130 Forest Home Drive Ithaca, N. Y.

E. Lionel Pavlo
Consulting Engineer

Design, Supervision, Reports
Bridges, Highways, Expressways
Marine Structures, Public Works
Industrial Construction, Airports

7 E. 47th St. New York 17, N. Y.

Severud-Elstad-Krueger
Consulting Engineers

Structural Design - Supervision
Reports - Buildings - Airports
Special Structures

415 Lexington Avenue
New York 17, N. Y.

D. B. Steinman
Consulting Engineer

BRIDGES
HIGHWAYS
Design, Construction
Strengthening, Investigations,
Reports, Advisory Service

117 Liberty St., New York 6, N. Y.

Lockwood, Kessler & Bartlett, Inc.
Engineers *Surveyors*

Civil Engineering Investigations, Reports and Designs, Supervision of Construction, Cadastral, Geodetic, Topographic & Engineering Surveys, Photogrammetric Engineering and Mapping.

One Aerial Way Syosset, N. Y.

Kain and Hooven
Consulting Engineers

Civil—Structural—Industrial

Registered—Pennsylvania, Delaware, New Jersey

44 S. Lansdowne Ave., Lansdowne, Pa.

Robert W. Lowry, Inc.
Consulting Engineers

Robert W. Lowry M. Lepkaluk
Design, Supervision, Reports, Long Span & Movable Bridges, Expressways, Highways, Airports, Prestress Design, Stress Analysis & Strengthening

227 Pine Street, Harrisburg, Pa.
122 E. 42nd Street, N. Y., N. Y.

Michael Baker, Jr., Inc.

Consulting Engineers, Civil Engineers, Planners & Surveyors; Airports & Highway Design; Water Works & Sewerage Design & Operation; Aerial Topo Maps; Surveys; Reports & Investigations; Irrigation. Home Off.—Rochester, Pa. Br. Off.: Jackson, Miss.; Harrisburg, Pa.; College Park, Md.

Sprague & Henwood, Inc.
Drilling Services

Foundation Investigations, Soil Testing & Test Borings, Grout Hole Drilling & Pressure Grouting, Diamond Core Drilling

Main Office
221 W. Olive Street, Scranton, Pa.

Branches:
1009 Western Savings Fund Bldg., Philadelphia, Pa.
11 W. 42nd St., New York, New York
200 Magee Bldg., Pittsburgh, Pa.
Box 645, Grand Junction, Colorado
Buchans, Newfoundland

Buchart Engineering Corp.
Engineers

Highways — Bridges — Toll Roads
Sewerage — Industrial Waste and Disposal — Water Works — Surveys — Reports — Design — Supervision — Consultation — Industrial — Municipal — Structures

611 W. Market St., York, Pennsylvania

SOUTH

Harry Hendon and Associates
ENGINEERS
(Formerly Polk, Powell and Hendon)

Harry H. Hendon L. E. Hoffmann
A. B. Jowers
Civil Engineers—Public Utilities

10 Office Park Circle, Mountain Brook
Birmingham 9, Alabama

Duval Engineering & Contracting Co.
General Contractors

FOUNDATION BORINGS
For Engineers and Architects.

Jacksonville Florida

Rader and Associates
Engineers - Architects

Sewage Disposal, Water Works, Ports, Airports, Bridges, Highways, Office and Commercial Buildings, Industrial Plants, Reports, Investigations, Consultations.

111 N.E. 2nd Avenue, Miami 32, Fla.

MIDDLE WEST

Consoer, Townsend & Associates

Water Supply, Sewerage, Flood Control & Drainage, Bridges, Express Highways, Paving, Power Plants, Appraisals, Reports, Traffic Studies, Airports, Gas & Electric Transmission Lines.

351 East Ohio St., Chicago 11, Illinois

Mobile Drilling Contract Division, Inc.
Soil and Foundation Engineering

Foundation Investigation, Analysis & Design — Earth Dam & Embankment Design — Pavement Design — Compaction Control — Soil Sampling & Testing — Core Drilling

960 N. Penn. Ave., Indianapolis 4, Ind.

Toledo Testing Laboratory
Engineers—Chemists

Concrete — Soils — Asphalt
Inspection Research
Tests Development
Foundation Investigation
Borings — Diamond Drilling — Load Tests
Soils Mechanics Laboratory

1810 North 13th St. Toledo 2, Ohio

When you need a SPECIALIST in a hurry . . .

Engineering News-Record's Professional Service Section offers the quickest, most direct method of contacting consultants who may be available NOW.

FOREIGN

Ingenieria Especializada De Mexico, S. A.

Consulting Engineers, Contractors offering a complete engineering service in Latin America cement and lime plants; hydro, thermo & diesel electric plants manufacturing & process plants.

Plaza Santos DeGollado #10-301, Mexico 1, D. F.

GEOLOGISTS

Geologic Associates
ENGINEERING GEOLOGISTS

Studies and Reports
Foundation Investigations
Specialized Drilling and Sampling

1500 8th Ave. So — Nashville, Tenn.
9-1519 Phones 5-4402

INSPECTION & TEST

A. W. Williams Inspection Co.

Established 1921—Member A.C.I.I.
Inspection — Testing — Analyses — Supervision. Foundation Investigations. Soil Borings, Soil Mechanics, Concrete and Asphalt Design and Control, Radiography, Sampling, Calibrations, Timber and timber treatment inspections. Complete testing laboratory service.
Main Office: 208 Virginia St., Mobile, Ala.

The Haller Testing Laboratories, Inc.

Testing and Inspection of Construction Materials for:
Expressways—Airports
Structures—Bridges

Complete Soils Laboratory

Borings—Drilling—Load Tests

140 Cedar St., N. Y. 6, N. Y.
Boston, Mass.
Plainfield, N. J. New Haven, Conn.

ALWAYS READY

Yes, these consultants are always ready to help you with any problem concerning engineered construction. Call on them with the assurance that you will be receiving the finest of professional advice.

SEARCHLIGHT SECTION

(Continued from preceding page)

6" PIPE FOR SALE

30 Miles of 6¼" O.D. Armco, Spiralweld linepipe, 11-lb., 10 GA, 6" I.D. with 5" welded 6⅝" O.D.—6" I.D. end Collars and Victaulic Couplings. Can be beveled for welding. Material like new. Can be inspected, Mt. Pleasant, Michigan. Was used in 500# gas line. F.O.B. cars, 90¢ per foot.

EVALUATION AND SALES SERVICE

P. O. Box 416 — Mt. Pleasant, Michigan
Phone SPring 3-3981

FOR SALE

250 HELTZEL 13" face x 10" base highway paving forms—

¼" material 10'-0" long with three wedged stake pockets and one slide lock per 10'-0" section—new forms—never used—substantial discount.

FS-3424, Engineering News-Record
520 N. Michigan Ave., Chicago 11, Ill.

1750 HP Baldwin Diesel,

8 cylinder, Supercharged 650 RPM, model 608 SC 12¾ x 15½ stroke. Suitable for dredge or Marine service. Modern unit.

ALJON ELEC. DIESEL CO.
904 Pacific St. Bklyn. 38, N. Y.

LOCOMOTIVE FOR SALE

PLYMOUTH 35-ton gasoline powered, standard gauge switcher, 240 HP LeRoi motor, Timken journal bearings, air brakes, railway couplers, 1943, good operating condition, 0-4-0; will pull 800 tons. Midwest.

H. Y. SMITH CO.
828 N. Broadway Milwaukee 2, Wis.

If there is anything you want
that other readers can supply
OR . . . something you don't want—
that other readers can use—
Advertise it in the
SEARCHLIGHT SECTION

ADVERTISERS IN THIS ISSUE

Allison Engine Div., G. M. C. 118
Aluminum Co. of America 79, 88
American Bitumuls & Asphalt Co. 83
American Bridge Div., U. S. Steel Corp. 71
American Foreign Ins. Assn. 73
American Mutual Liability Ins. Co. 42, 43
American Steel & Wire Div., U. S. Steel Corp. 65-68
American Vitrified Prod. Co. 5
Armco Drainage & Metal Prod., Inc. 48

Barco Mfg. Co. 56
Behlen Mfg. Co. 92
Belmont Iron Works 90
Bethlehem Steel Co. 86
Bruning Co., Inc., Charles 57
Buffalo Forge Co. 80
Butler Mfg. Co. 52
Byers Co., A. M. ..... 2nd Cover

Case Foundation Co. 99
Caterpillar Tractor Co. 30, 31
Cen-Vi-Ro Pipe Co. 32
Chevrolet Motor Div., General Motors Corp. 60, 61
Cities Service Oil Co. 109
Clayton Mfg. Co. 99
Clow & Sons, James B. 78
Cole Mfg. Co., R. D. 131
Committee on Steel Pipe Research 106

Dravo Corp. 97, 131
Dudgeon, Inc., Richard 88

Economy Forms Corp. 90
Euclid Div., G. M. C. 10

Ford Motor Co., Indust. & Engine Div. 15

Gahagen Construction Corp. 90
Goodyear Tire & Rubber Co. 1
Griffin Wellpoint Corp. 54
Gulf Oil Corp. 105
Gunite Concrete & Construction Co. 94

Hartford Fire Ins. Co. 37
Hartford Accident & Indemnity Co. 37
Heltzel Steel Form & Iron Co. 74, 75
Hercules Motors Corp. 64
Horn Co., Inc., A. C., Div. of Sun Chem. Corp. 39
Hose-McCann Telephone Co., Inc. 112
Hughes Bros., Inc. 100
Hyatt Bearings Div., G. M. C. 18

International Harvester Co. 12, 13
Irving Subway Grating Co. 113

Jenkins Bros. 20
Johns-Manville Corp. 62
Joy Mfg. Co. 91

Kaiser Aluminum & Chem. Corp. 53
Keasbey & Mattison Co. 41
Kensington Steel Co. 49
Kohler Co. 100

The Lamson & Sessions Co. 115
Larsen Prod. Corp. 82
Lefax Co. 94
Lehigh Portland Cement Co. 93
LeRoi Co. 76
Leschen Wire Rope Div., H. K. Porter Co., Inc. 63
Lipe-Rollway Corp. 11
Louisville Cement Co. 4
Luria Engr. Corp. 89

Masters Builders Co. ..... 3rd Cover
McKiernan-Terry Corp. 92

Naylor Pipe Co. 8
Northwest Engineering Co. 3

Olin Film Div. 9
Owens Corning Fiberglas Corp. 111

Pennsylvania Drilling Co. 88
Perlite Div., Gt. Lakes Carbon Corp. 95
Phoenix Bridge Co. 90
Pittsburgh Coke & Chem. Co. 101
Pittsburgh Corning Corp. 85

Republic Steel Corp. 50, 51
Robertson Co., H. H. 59
Roebling's Sons Corp., John A. 116
Ryerson & Sons, Inc., Jos. T. 77

Sauerman Bros., Inc. 70
Schramm, Inc. 58
Servicised Prod. Corp. 14
Sparling Meter Co. 112
Spencer, White & Prentis, Inc. 77
Surco Int. Corp. 96
Superior Lidgerwood Mundy Corp. 94
Symons Clamp & Mfg. Co. 2

Templeton Kenly & Co. 94
Texas Co. ..... 4th Cover
Thew Shovel Co., The 55
Timken Roller Bearing Co. 28
Truscon Laboratories 69

Underpinning & Foundation Co. 32
U. S. Rubber Co. 16
U. S. Steel Corp. 6, 7
United Steel Fabricators, Inc. 72
Universal Form Clamp Co. 81

Yeomans Bros. Co. 38
Youngstown Sheet & Tube Co. 98

Professional Services 130

CLASSIFIED ADVERTISING
F. J. Eberle, Business Mgr.

Employment Opportunities 123-126
Proposals 120-122
Educational 126
Equipment (For Rent, Sales Wanted) 126-130

ENGINEERING NEWS-RECORD

330 West 42 St., New York 36—LOngacre 4-3000

ABP Member

Number of copies of this issue printed 76,799

D. S. Robertson, Advertising Manager
D. J. Cassidy, Business Manager

ADVERTISING REPRESENTATIVES

New York, 36—330 W. 42 St.,
C. D. Neulen, H. T. Olsen
J. C. White

Chicago, 11—520 No. Michigan Ave.,
L. H. Hunt, W. G. Payne

San Francisco, 4—68 Post St.,
J. W. Otterson, R. C. Alcorn

Philadelphia, 3—17th and Sansome Sts.,
D. G. Jensen

Cleveland, 15—Hanna Bldg.,
E. E. Duff, Jr., F. P. DiToro

Detroit, 26—Penobscot Bldg.,
J. A. Houghton

St. Louis, 8—Continental Bldg.,
B. F. Horn

Los Angeles, 17—1125 W. Sixth St.,
H. L. Keeler

Atlanta, 3—Rhodes-Haverty Bldg.,
W. D. Lanier

Dallas, 2, Adolphus Tower Bldg.,
G. Jones, D. C. Billian

OTHER SALES OFFICES:

Pittsburgh, 22—919 Oliver Bldg.,
Boston, 16—350 Park Square Bldg.,
London, McGraw-Hill House



WELDED CONSTRUCTION FOR HIGH PRESSURES

● Whatever your need in pressure vessels, lumber-treating cylinders, storage tanks, processing or chemical vessels—of your special or conventional design, you can depend on COLE for vessels built in strict accordance with ASME Code . . . from aluminum, stainless or carbon steels, and alloys. Write for *Tank Talks*.

R. D. COLE MANUFACTURING CO. COLE NEWNAN, GEORGIA

R. D. COLE MFG. COMPANY
Newnan, Ga.



SAFETY IS FIRST WITH TRI-LOK!

Replace your slippery, rickety old wooden floors with the safest flooring available . . . *Tri-Lok* and *Tri-Forged* Grating. Here are some outstanding features: long life, unusual strength, adaptability, handling ease, minimum weight, maximum openings for light and ventilation. *Tri-Lok* and *Tri-Forged* products meet government specifications, are available in a wide range of panel sizes.

Department D-2511
DRAVO CORPORATION
Pittsburgh 22, Penna.
National Distributors

Not Entirely for Us

COMPLETION IN GREAT BRITAIN of the world's first nuclear power plant—the 92,000-kw Calder Hall Station (ENR Oct. 25, p. 48)—revealed that some new and unusual techniques were required in its construction. It may, therefore, be useful to point out that, while these techniques are worth study by U. S. engineers and construction men, it is not likely that all of them will be applicable to U. S. nuclear power-plant construction.

The reason why the British installation is different rests in a fundamental difference in the view taken of nuclear power over there. Great Britain's coal supply is unsatisfactory—even to the point where more and more of this conventional fuel has to be imported at high cost—so that the economics of nuclear power are more attractive to the British than to us. As a consequence, in 1953, Great Britain, through its Atomic Energy Authority, made the decision to construct a nuclear prototype plant on a crash basis, using an early—and bulky—type reactor.

Moreover—spurred by sheer necessity—the British committed themselves to this one type of reactor for at least the next ten years. The U. S. is fortunate in having an abundance of conventional fuel at present and can proceed at a less rapid and more economical pace. In conjunction with private power, the Atomic Energy Commission is building a number of nuclear prototype plants with many different types of reactors.

The difference in approaches is characterized by the reactors at Calder Hall and at Shippingport, Pa., where the first U. S. nuclear power plant is under construction. The former is a graphite-moderated, gas-cooled unit fueled by natural uranium contained in a 100-psi pressure vessel, 40 ft in diameter and 60 ft high. At Shippingport, the reactor is a pressurized-water type in a 2,000-psi vessel, only 9 ft in diameter and 33 ft high.

The Calder Hall vessel posed a dramatic challenge to its builders. They had to weld 2-in. plate in the field into a vessel, which is of record size for the pressure involved, and then devise some means of heat treating the metal in place. Also, stress distribution of a 60-ton steel grid, 35 degrees redundant, which supports the graphite pile had to be gaged so deflections could be determined precisely. In sharp contrast, the smaller size of the Shippingport reactor permitted shop fabrication—an exacting but not unduly difficult operation even with 8½-in. plate.

Concrete work at both jobs is impressive, but again the British were forced into the bolder construction. For the biological shield, they utilized a dense dry mix weighing 162 lb per cu ft. It had to be formed to 0.1-in. tolerance and placed in 7-ft thicknesses up to a height of 90 ft. After considering dense concrete, the Shippingport designers settled for 5 ft of ordinary (albeit heavily reinforced) concrete, which is placed around the large steel vessels designed to contain the plant.

Thus, while American engineers have evolved several construction innovations at Shippingport, they are not confronted with such demanding requirements as the British. Visitors at the site hear the comment that Shippingport is just another heavy construction job—bigger and more exacting than most, but not unusually demanding.

The builders of Calder Hall faced and overcame unprecedented design and construction problems. Undoubtedly, their contribution is of great significance in Britain, where Calder Hall construction is to be duplicated, in essence at least in eight additional power plants. It is more difficult to assess the effect on the American scene where the probability is against reactors of the Calder Hall type being constructed. But the advances in welding large pressure vessels on site, heat treating them in place, calculating deflections of highly redundant grids, and placing dense concrete in great thicknesses and to extremely close tolerances may well find individual application in the United States. It is for that reason that the Calder Hall experience is of interest over here.

Metal Pipe for Sanitary Sewers

IT IS APPARENT from the article on the Raritan Valley cleanup on page 34 of this issue that the jury of professional opinion still has to render a verdict on corrugated metal pipe for sanitary sewers. For due to the natural reluctance of all concerned with this pioneer job to voice possibly premature judgments, the article is far from the last word. In fact, different interpretations of the unembellished facts and public statements, which it sets forth, could lead to some unwarranted conclusions.

It is true that the contractor who is installing the corrugated pipe has had difficulty. But most of the early troubles have been resolved, although the joint can stand improvement. The supplier, Armco Metal & Drainage Products Co., well realizes this, and is working on some modifications.

Also, while installation problems are significant, the most important consideration is how the pipe will behave in the ground. A complete evaluation is possible only after many years of use, but up to this time, after extensive probing of the situation, we have heard no derogatory information concerning performance of the pipe. Indeed, there is feeling that the flexible nature of the joint has advantage in soils tending to settle excessively.

The construction agency, Middlesex County Sewerage Authority, and the consultants, Metcalf & Eddy and C. J. Kupper, deserve great praise for pioneering another material in the sanitary sewer field.

Their experience indicates that prospective users of corrugated metal pipe for sanitary sewers should keep an open mind. The Raritan Valley experience should not be a deterrent, but rather a basis for more knowledgeable evaluation.

THE TRADE MARK THAT COMES TO LIFE . . .

. . . to serve you with products that aid in obtaining, more economically, the qualities you want in concrete.

Our half century of experience is promptly available for:

1. product-selection consultation
2. product-use service on the job . . . through the 43 branch offices shown here staffed by more than 100 Master Builders skilled fieldmen.

If you are associated with concrete in any way, you will benefit by calling in one of these men.

THE MASTER BUILDERS COMPANY

Division of American-Marietta Company

CLEVELAND 3, OHIO • TORONTO 9, ONTARIO

POZZOLITH • MASTERPLATE • EMBECO and other products for the improvement of concrete and mortar.

Rocky Mountain highway needs skid-resistant pavement

Constructing skid-resistant Texaco Asphaltic Concrete pavement on U. S. Route 550, where this highway crosses the Molas Divide in Colorado at an elevation of 10,000 feet.

CONTRACTORS

Lowdermilk Brothers Construction Company, Denver, Colo.

Sterling Sand & Gravel Company, Fort Collins, Colo.

Completed Texaco Asphaltic Concrete surface at the left and the 6-inch broken stone base at the right.

U. S. Route 550 crosses the Molas Divide near Silverton, Colo., about 10,000 feet above sea level. On the curves and grades of such a mountain highway, dependable skid-resistance is an exceptionally important quality in a pavement.

A hot-mix Texaco Asphaltic Concrete pavement has been constructed on this 6.8 mile section of U.S-550. Laid to a compacted thickness of two inches, this skid-resistant, rugged wearing surface is supported by a six-inch foundation of crushed stone. The Texaco asphalt surface and the stone base form a completely flexible pavement from the subgrade up, which is capable of absorbing heavy traffic year after year, with a minimum of maintenance.

Hot-mix Texaco Asphaltic Concrete is one of many heavy-duty, intermediate and low-cost types of construction for highways, streets, airports and parking areas obtainable with Texaco asphaltic products. Helpful information about the methods and materials recommended for all these types is supplied in two free booklets. Copies may be obtained without obligation from our nearest office.

ENGINEERING · RESEARCH · EDUCATION
THE ASPHALT INSTITUTE
MEMBER

THE TEXAS COMPANY, Asphalt Sales Div., 135 E. 42nd Street, New York City 17
Boston 16 Chicago 4 Denver 1 Houston 1 Jacksonville 2 Minneapolis 3 Philadelphia 2 Richmond 19

TEXACO
REG. T. M.

TEXACO ASPHALT